



February 24, 2020

Ms. Cathy Amoroso  
National Priorities List Coordinator  
U.S. Environmental Protection Agency, Region 4  
61 Forsyth Street, SW  
Atlanta, GA 30303

**Subject: Final Focused Site Inspection Report, Revision 1  
Patterson Street Solvent Plume  
EPA Contract No. EP-S4-14-03  
EPA Identification No. NCN000404887  
Technical Direction Document (TDD) No. TT-05-041**

Dear Ms. Amoroso:

The Tetra Tech Superfund Technical Assessment and Response Team (START) is submitting revision 1 of the enclosed final focused site inspection (SI) report regarding the Patterson Street Solvent Plume site in Greensboro, Guilford County, North Carolina. The SI report includes figures (Appendix A); tables (Appendix B); field logbook notes, field sheets, and boring logs (Appendix C); a photographic log of SI activities (Appendix D); a photographic log of the surface water samples (Appendix E), and Tetra Tech's review of field quality control samples (Appendix F). Attachment 1 contains the U.S. Environmental Protection Agency (EPA) Laboratory Services and Applied Sciences Division (LSASD) analytical data packages.

Please call me at (678) 775-3101 if you have any questions or comments regarding this submittal.

Sincerely,

A handwritten signature in black ink that reads 'Quinn Kelley'.

Quinn Kelley  
Tetra Tech START IV Project Manager

A handwritten signature in black ink that reads 'Andrew F. Johnson'.

Andrew F. Johnson  
Tetra Tech START IV Program Manager

Enclosure

cc: Katrina Jones, EPA Project Officer  
Angel Reed, Tetra Tech START IV Document Control Coordinator

**FINAL  
FOCUSED SITE INSPECTION REPORT**

Revised/approved. 3/9/2020  
*Cathy Amoroso*

**PATTERSON STREET SOLVENT PLUME  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA**

**U.S. EPA ID NO. NCN000404887**

**REVISION 1**

**Prepared for**

**U.S. ENVIRONMENTAL PROTECTION AGENCY  
Region 4  
Atlanta, Georgia 30303**



Contract No.	:	EP-S4-14-03
TDD No.	:	TT-05-041
Date Prepared	:	February 24, 2020
EPA Task Monitor	:	Cathy Amoroso
Telephone No.	:	(404) 562-8637
Prepared by	:	Tetra Tech
START Project Manager	:	Quinn Kelley
Telephone No.	:	(678) 775-3101

Prepared by

Reviewed by

Approved by

*Quinn Kelley*

Quinn Kelley  
START IV Project Manager

*Shanna Davis*

Shanna Davis  
START IV Technical Reviewer

*Andrew F. Johnson*

Andrew F. Johnson  
START IV Program Manager



TDD No. TT-05-041  
Patterson Street Solvent Plume  
Focused Site Inspection Report



## CONTENTS

1.0	INTRODUCTION .....	1
2.0	SITE BACKGROUND .....	2
3.0	FOCUSED SITE INSPECTION ACTIVITIES .....	3
3.1	SAMPLE COLLECTION, METHODOLOGY, AND PROCEDURES .....	3
3.2	DEVIATIONS FROM THE QUALITY ASSURANCE PROJECT PLAN .....	4
4.0	ANALYTICAL SUPPORT, METHODOLOGY, VALIDATION, DATA QUALITY, AND DATA QUALIFIERS .....	5
4.1	ANALYTICAL SUPPORT, METHODOLOGY, AND VALIDATION .....	5
4.2	ANALYTICAL DATA QUALITY AND DATA QUALIFIERS .....	5
5.0	SOURCE SAMPLING .....	6
5.1	GROUNDWATER SAMPLING .....	7
5.1.1	Site Geology .....	7
5.1.2	Site Hydrogeology .....	7
5.1.3	Groundwater Sampling Analytical Results .....	8
5.2	SURFACE WATER SAMPLING ANALYTICAL RESULTS .....	8
5.3	SOURCE CONCLUSIONS .....	9
6.0	SOIL EXPOSURE AND SUBSURFACE INTRUSION PATHWAY .....	9
6.1	SOIL EXPOSURE COMPONENT .....	9
6.2	SUBSURFACE INTRUSION COMPONENT .....	10
6.2.1	Relevant Previous Investigations .....	10
6.2.2	SI Indoor Air, Crawl Space Air, and Soil Gas Sampling Analytical Results .....	11
7.0	AIR MIGRATION PATHWAY .....	12
7.1	RELEVANT PREVIOUS INVESTIGATIONS .....	12
7.2	SI AMBIENT AIR SAMPLING ANALYTICAL RESULTS .....	13
7.3	AIR MIGRATION PATHWAY TARGETS .....	13
7.4	AIR MIGRATION PATHWAY CONCLUSIONS .....	13
8.0	SUMMARY AND CONCLUSIONS .....	14
9.0	REFERENCES .....	16

## APPENDICES

### Appendix

A	FIGURES
B	TABLES
C	FIELD LOGBOOK NOTES, FIELD SHEETS, AND BORING LOGS
D	SITE INSPECTION PHOTOGRAPHIC LOG
E	SURFACE WATER PHOTOGRAPHIC LOG
F	REVIEW OF FIELD QUALITY CONTROL SAMPLES

## ATTACHMENT

1	EPA LABORATORY SERVICES AND APPLIED SCIENCES DIVISION (LSASD) ANALYTICAL DATA PACKAGES
---	---

## 1.0 INTRODUCTION

The U.S. Environmental Protection Agency (EPA) tasked the Tetra Tech, Inc. (Tetra Tech) Superfund Technical Assessment and Response Team (START) to conduct a focused site inspection (SI) at the Patterson Street Solvent Plume (PSP) site in Greensboro, Guilford County, North Carolina (EPA Identification Number [No.] NCN000404887). The focused SI was completed under Contract No. EP-S4-14-03, Technical Direction Document (TDD) No. TT-05-041. The SI was conducted with cooperation and assistance from the North Carolina Department of Environmental Quality (NCDEQ).

The primary objectives of an SI are to determine whether a release of hazardous substances to the environment has occurred, and whether the release has the potential to be placed on the National Priorities List (NPL). The NPL identifies releases, or threatened releases, of hazardous substances posing a serious enough risk to public health or the environment to warrant further investigation and possible remediation under the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (CERCLA), and the Superfund Amendments and Reauthorization Act of 1986.

Information gathered during the focused SI is used to generate a preliminary Hazard Ranking System (HRS) score. The HRS score is the primary criterion EPA uses to determine whether a site is eligible for placement on the NPL. Generally, an SI is the first CERCLA investigation at a site where waste and environmental samples are collected and analyzed to support a site evaluation according to the HRS.

Objectives of the focused SI at the PSP site were as follows:

- Obtain and review relevant file material.
- Document current site conditions.
- Collect and analyze samples to establish representative background levels.
- Collect samples to document observed releases to the soil exposure and subsurface intrusion pathway and the air migration pathway.
- Evaluate the target population for the air migration pathway.
- Obtain any other missing HRS data.

The remainder of this focused SI report regarding the PSP site is organized as follows:

- Section 2.0 briefly discusses the site background, including the site location and description. For a complete site background, see the final Preliminary Assessment Report, dated May 9, 2019 (Reference [Ref.1]).
- Section 3.0 describes the following: focused SI field activities during the week of September 9, 2019, and supplemental sampling activities on December 3 and 4, 2019; sample collection, methodology, and procedures; and deviations from the final quality assurance project plan (QAPP), dated June 21, 2019, and final QAPP addendum, dated November 20, 2019 (Refs. 2; 3).

- Section 4.0 discusses analytical support, methodology, validation, data quality, and data qualifiers.
- Section 5.0 identifies source sampling locations and presents analytical results.
- Section 6.0 discusses the soil exposure and subsurface intrusion pathway, including the surface soil, indoor air, crawl space air, and soil gas sampling locations and analytical results.
- Section 7.0 discusses the air migration pathway, including ambient air sampling locations and analytical results, as well as targets associated with this pathway.
- Section 8.0 summarizes and presents conclusions of the focused SI report.
- Section 9.0 lists sources referenced during preparation of this report.
- Figures are in Appendix A. Tables are in Appendix B. Field logbook notes, field sheets, and boring logs are in Appendix C. The SI photographic log is in Appendix D. The surface water photographic log is in Appendix E. Tetra Tech's review of field quality control (QC) samples is in Appendix F. The EPA Region 4 Laboratory Services and Applied Sciences Division (LSASD) analytical data packages are in Attachment 1.

## 2.0 SITE BACKGROUND

This section briefly discusses the site background, including the site location and description. Previous investigations relevant to the pathways of concern are discussed in Sections 6.0 and 7.0. For a complete site background, including all previous investigations, see the final Preliminary Assessment Report, dated May 9, 2019 (Ref. 1).

The PSP site is defined as a contaminated groundwater plume with no definitive source. The PSP site is located in about 349.1 acres of land surrounding the intersection of Patterson Street and South Holden Road in Greensboro, Guilford County, North Carolina (see Figure 1 in Appendix A); the boundaries of the site are not defined in this SI. Several industrial facilities are within the Patterson Street industrial corridor, including Ashland Chemical, Inc. (Ashland Chemical); Dow Corning Corporation (Dow Corning); Ecoflo, Inc. (Ecoflo); and the North Carolina Department of Transportation Site # 61 (NC DOT), among others (see Figure 2 in Appendix A). The Patterson Street industrial corridor hosts major suppliers of blended bulk chemicals to furniture, textile, and other manufacturing businesses (Ref. 1, p. 2). Releases to the environment of chlorinated volatile organic compounds (CVOC) are known or suspected to have occurred at four NCDEQ Inactive Hazardous Site Branch (IHSB) sites and three Resource Conservation and Recovery Act (RCRA) sites along the Patterson Street industrial corridor (Ref. 1, p. 2). Geographic coordinates at the PSP site, measured at the intersection of Patterson Street and South Holden Road, are latitude 36.057192 degrees north and longitude 79.841981 degrees west (see Figure 1 in Appendix A).

This SI focused on: (1) a residential neighborhood within the PSP site and south of the Patterson Street industrial corridor (henceforth referred to as the “neighborhood study area”), and (2) unnamed tributaries originating within the neighborhood study area that this SI report refers to as the “urban ditch” unnamed tributary and the “bedrock” unnamed tributary. The neighborhood study area is bordered to the north by Immanuel Road, to the east by Belmar Street, to the south by North Hayden Street, and to the west by South Holden Road (see Figure 3 in Appendix A).

The EPA hypothesizes that the contaminated groundwater plume beneath the neighborhood study area is discharging to unnamed tributaries (urban ditch and bedrock) that flow through the neighborhood, and that from these unnamed tributaries volatilization of contaminants into the ambient air occurs. The purpose of the focused SI was to gather analytical data by collecting environmental field samples from groundwater, surface water, surface soil, soil gas, indoor air, crawl space air, and ambient air to evaluate whether groundwater contamination is affecting surface water and ambient air in the neighborhood study area. The focused SI provided additional data to assist EPA with determining whether additional vapor intrusion (VI) investigations would be necessary. Given the large number of potential sources of the groundwater contamination in the Patterson Street industrial corridor, definitive identification of a single or multiple sources of contamination was beyond the scope of the focused SI.

### **3.0 FOCUSED SITE INSPECTION ACTIVITIES**

This section addresses field observations and sampling procedures at the neighborhood study area, including sample collection, methodology, and procedures, as well as deviations from the final QAPP and final QAPP addendum. SI sampling was conducted in accordance with the EPA-approved final QAPP dated June 21, 2019, and the EPA-approved QAPP addendum, dated November 20, 2019 (Refs. 2; 3).

#### **3.1 SAMPLE COLLECTION, METHODOLOGY, AND PROCEDURES**

Tetra Tech conducted the focused SI sampling event during the week of September 9, 2019, and on December 3 and 4, 2019. Sampling locations are depicted on Figure 4 in Appendix A and described in Table 1 of Appendix B. During the sampling events, Tetra Tech collected five surface soil samples (including one duplicate), eight groundwater samples (including one duplicate), 13 surface water samples (including one duplicate and one seep), two indoor air samples, six crawl space air samples, 15 soil gas samples (including one split), and 16 ambient air samples (including two duplicates) (see Table 1 in Appendix B).

Tetra Tech followed sample collection procedures outlined in the final QAPP and final QAPP addendum (Refs. 2; 3). All samples were collected in accordance with EPA Region 4 LSASD Field Branches Quality System Technical Procedures (FBQSTP) (Refs. 4; 5; 6; 7; 8; 9).

### **3.2 DEVIATIONS FROM THE QUALITY ASSURANCE PROJECT PLAN**

Some sampling locations during the field sampling events differed from sampling locations proposed in the final QAPP and final QAPP addendum because of site conditions. The following deviations in the field were documented in logbook notes, field sheets, and boring logs (see Appendix C):

- Pore water samples were not collected from either unnamed tributary because the pore water samplers could not penetrate the stream bed. Tetra Tech attempted to collect a pore water sample at the seep that forms the urban ditch (PSP22); however, the pump did not produce enough water for the sample.
- Soil gas implants were mudded in (mud appeared in tubing during sampling) at PSP17 and PSP18; therefore, soil gas samples were not collected at these locations (see Appendix C, pp. C-37, C-38).
- Ambient air samples (PSP20-AA and PSP20-AA-DUP) were added to the samples collected from PSP20.
- Because of several feet of fill material in the boring at sampling station PSP22, this sampling location was abandoned. This Station ID was applied to the seep location on the north side of Camborne Street, where a surface water sample and ambient air sample were collected.
- Access was not granted to sampling station PSP23; therefore, no samples were collected at this location.
- When a vacuum was applied to the soil gas implant at sampling station PSP26, no flow occurred; therefore, a soil gas sample was not collected at this location (see Appendix C, p. C-44).
- Refusal was encountered at 8 feet below ground surface (bgs) at sampling station PSP26; therefore, the temporary well proposed for this location was not installed; instead a temporary well was installed at PSP25 where a groundwater sample was collected (see Appendix C, pp. C-102, 104).
- Access was not granted to the original PSP28 location south of West Florida Street; therefore, a location in the parcel north of West Florida Street was designated PSP28 instead. PSP27 was also relocated so that PSP27 and PSP28 were evenly distributed across the property.
- The temporary monitoring wells installed at PSP27 and PSP28 did not produce water; therefore, groundwater samples were not collected at these locations.
- Temporary monitoring wells were allowed to stabilize for 24 hours after installation before sampling.
- Indoor air samples were planned at PSP25, PSP26, PSP29, and PSP30; however, access was not granted to the inside of these residences.

## **4.0 ANALYTICAL SUPPORT, METHODOLOGY, VALIDATION, DATA QUALITY, AND DATA QUALIFIERS**

This section outlines analytical support, methodology, and validation, as well as analytical data quality and data qualifiers. EPA Region 4 LSASD analytical data packages are in Attachment 1, and the Tetra Tech field QC sample review is in Appendix F.

### **4.1 ANALYTICAL SUPPORT, METHODOLOGY, AND VALIDATION**

The EPA Region 4 LSASD laboratory analyzed all samples collected during the focused SI for CVOCs, including 1,1-dichloroethene (DCE); cis-1,2-DCE; trans-1,2-DCE; tetrachloroethene (PCE); trichloroethene (TCE); and vinyl chloride, in accordance with the Laboratory Services Branch's (LSB) Laboratory Operations and Quality Assurance Manual (LOQAM), May 2019 (Ref. 10).

The EPA Region 4 LSASD reviewed all data in accordance with the Contract Laboratory Program (CLP) Statement of Work (SOW) and the LSB LOQAM methods and guidelines (Attachment 1, pp. A1-1, A1-45, A1-82, A1-103). To determine whether additional qualifications were warranted, Tetra Tech reviewed all field duplicate and field QC blank samples (equipment and field) in accordance with the EPA Contract Laboratory Program National Functional Guidelines (NFG) for Superfund Organic Methods Data Review, EPA-540-R-2017-002, January 2017 (Ref. 11). Based on the results of Tetra Tech's review, additional qualifiers were added to the analytical data where appropriate (see Appendix F).

### **4.2 ANALYTICAL DATA QUALITY AND DATA QUALIFIERS**

All analytical data were subject to a quality assurance review, as described in the EPA Region 4 LSASD laboratory data evaluation guidelines. The text and analytical data tables presented in this report provide some concentrations as qualified with a "J," indicating that the identification of the analyte is acceptable but the reported value is an estimate. Some sample results are reported with a "U" qualifier, meaning that the analyte was not detected at or above the minimum reporting limit (MRL). The MRL is sample-specific and analyte-specific, and depends on preparation weights and volumes, dilutions, and moisture content of soil. Some sample results are reported with a "UJ" qualifier, meaning that the analyte was not detected at or above the MRL, which was considered approximate as a result of deficiencies in one or more QC criteria. Constituent concentrations in samples that equal or exceed three times detected background concentrations or that equal or exceed the sample-specific and analyte-specific MRLs for non-detect background sample results are considered elevated. Analytical data sheets are in Attachment 1, and the Tetra Tech field QC sample review is in Appendix F.

## 5.0 SOURCE SAMPLING

This section discusses the sources evaluated at the neighborhood study area, and sampling locations and analytical results for samples collected from the sources. EPA hypothesizes that the contaminated groundwater plume beneath the neighborhood study area is discharging to unnamed tributaries that flow through the neighborhood study area, and that from these unnamed tributaries volatilization of contaminants into the ambient air occurs. Therefore, the source evaluated for the neighborhood study area is the contaminated groundwater plume discharging to the unnamed tributaries. Thus, the sources identified and discussed in this SI report include: (1) a contaminated groundwater plume with no identified source, and (2) contaminated surface water hypothesized to have resulted from discharge of contaminated groundwater to surface water.

All source samples were analyzed for CVOCs (1,1-DCE; cis-1,2-DCE; trans-1,2-DCE; PCE; TCE; and vinyl chloride). All groundwater source analytical results were compared to EPA Regional Screening Levels (RSL) for tapwater and EPA Maximum Contaminant Levels (MCL) (Refs. 12; 13). All surface water source analytical results were compared to background and EPA Surface Water Screening Values (SWSV) for freshwater (Ref. 14). Because of the industrial setting of the area, a suitable background groundwater location was not identified. The unnamed tributaries originate within the neighborhood study area; therefore, background surface water samples were collected from a separate, similar stream less than 1 mile southeast of the neighborhood study area.

Eight groundwater samples (including one duplicate) were collected within the neighborhood study area. Temporary monitoring well depths ranged from 6.5 to 20 feet bgs. Screen length for the wells was either 5 or 10 feet depending on the depth of the well. Ten surface water samples (including one duplicate) were collected from the bedrock and urban ditch unnamed tributaries (see Appendix E). Additionally, a surface water sample (PSP22-SEEP) was collected from a seep that forms the urban ditch unnamed tributary, and two background surface water samples were collected from a nearby similar tributary. Source sampling locations are depicted on Figure 4 in Appendix A. Installation and development of temporary monitoring wells were conducted in accordance with the EPA Region 4 LSASD FBQSTP for the Design and Installation of Monitoring Wells (SES DGUID-101-R1), January 2013 (Ref. 4). Source sampling activities were conducted in accordance with the EPA Region 4 LSASD FBQSTP for Groundwater Sampling (SES DPROC-301-R4), April 2017, and for Surface Water Sampling (SES DPROC-201-R4), December 2016 (Refs. 5; 6). Prior to intrusive work, a geophysical survey occurred at each sampling location to ensure no presence of obstructions, such as utility lines or tanks.



## **5.1 GROUNDWATER SAMPLING**

This section briefly discusses the site geology and hydrogeology, as well as the groundwater analytical results.

### **5.1.1 Site Geology**

Geology at the PSP site reflects the regional geology of the Carolina Slate Belt. The regolith consists of the soil layer and saprolite. The soil layer is about 3 feet thick and consists of dark brown to black clayey silt to silty clay with a high concentration of organic material. The saprolite consists of fine sandy silts to silty sands weathered from parent material, and is the dominant feature of the regolith. Its thickness ranges from 3 to 37 feet (Ref. 24, p. 2-3). The transition zone is beneath the regolith, and consists of clay to silty sand, with fragments of white feldspar, amphiboles, and minor quartz (Ref. 24, p. 2-4). The transition zone occurs between 15 and 37 feet bgs, and is about 12 to 17 feet thick. During installation of a well at the PSP site, bedrock was encountered at 51 feet bgs and consisted of moderately to slightly weathered, moderately hard to hard white and dark green porphyritic to aphanitic diorite in closely spaced fracture joints (Ref. 24, p. 2-4).

### **5.1.2 Site Hydrogeology**

The groundwater system at the PSP site is similar to regional hydrogeology, and is composed of, in descending order, (1) saturated saprolite consisting of weathered bedrock with little residual structure; (2) transition zone, less weathered, which is more transmissive and retains the fracture structure and pattern of the underlying bedrock; and (3) bedrock zone (Ref. 24, p. 2-6). Descriptions of these hydrogeologic zones appear in boring logs recorded in the PSP site area (Ref. 24, p. 57).

The saprolite zone is reddish-brown in color; is composed of fine sand, silt, and clay; and contains relict bedrock features, such as mineral grains. Generally, thickness of the saprolite ranges from 50 to 70 feet, but is only 10 to 20 feet thick near streams (Ref. 25, pp. 4-4, 4-5).

The transition zone separates the saprolite and the fractured bedrock, and is divided into two sub-units, the unconsolidated zone and a highly-fractured rock zone (Ref. 25, p. 4-5). The unconsolidated transition zone is composed of a mixture of sand and gravel-sized fragments of weathered bedrock, and the fractured rock transition zone is composed of highly fractured bedrock. Boring logs advanced in the Patterson Street site area indicate encounter with the transition zone at depths ranging from 10 to 85 feet bgs, with thicknesses ranging from 15 to 64 feet (Ref. 25, p. 4-5).



The fractured bedrock zone is composed of gneissic granite with schist layers and diorite with veins of quartz and feldspar (Ref. 25, p. 4-6). Topography of the bedrock surface is highly variable. Top of bedrock was encountered at depths ranging from 55 to 124 feet bgs (Ref. 25, p. 4-6). Fracture frequency and orientation were measured at three monitoring well locations, and fracture characteristics differed at each location. Additionally, results of aquifer pump tests indicated hydraulic conductivity differences of two to three orders of magnitude within wells about 170 feet apart. The varying depths at which bedrock was encountered, differences in fracture frequency and orientation, and vastly different hydraulic conductivities within short distances highlight the extremely complex subsurface conditions in the Patterson Street site area (Ref. 25, p. 4-7).

### **5.1.3 Groundwater Sampling Analytical Results**

Groundwater samples collected within the neighborhood study area contained 1,1-DCE up to 220 micrograms per liter ( $\mu\text{g/L}$ ); cis-1,2-DCE up to 140  $\mu\text{g/L}$ ; PCE up to 460  $\mu\text{g/L}$ ; and TCE up to 640  $\mu\text{g/L}$ . Vinyl chloride and trans-1,2-DCE were not detected in groundwater samples at concentrations above sample-specific MRLs. cis-1,2-DCE; PCE; and TCE were detected at concentrations exceeding both their EPA RSLs for tapwater and EPA MCLs. 1,1-DCE was detected at concentrations exceeding its EPA MCL (see Table 2 in Appendix B). Detected concentrations of 1,1-DCE; PCE; and TCE exceeded their EPA Vapor Intrusion Screening Levels (VISL) Target Groundwater Concentrations (195  $\mu\text{g/L}$ , 14.9  $\mu\text{g/L}$ , and 1.19  $\mu\text{g/L}$ , respectively), indicating a potential for volatile contaminants in groundwater to cause vapor intrusion into overlying structures (Ref. 16). In September 2018, Ashland Chemical collected a groundwater sample from monitoring well MW-32BR, located adjacent to the bedrock unnamed tributary within the neighborhood study area, that contained 1,1-DCE (150  $\mu\text{g/L}$ ); cis-1,2-DCE (89  $\mu\text{g/L}$ ); PCE (560  $\mu\text{g/L}$ ); and TCE (380  $\mu\text{g/L}$ ) (Ref. 15, Table 2, Figure 2).

## **5.2 SURFACE WATER SAMPLING ANALYTICAL RESULTS**

Surface water samples collected from both the urban ditch and bedrock unnamed tributaries contained elevated concentrations of 1,1-DCE up to 40  $\mu\text{g/L}$ ; cis-1,2-DCE up to 20  $\mu\text{g/L}$ ; PCE up to 88  $\mu\text{g/L}$ ; TCE up to 33  $\mu\text{g/L}$ ; and vinyl chloride up to 1.3  $\mu\text{g/L}$ . Trans-1,2-DCE was not detected in surface water samples at concentrations above sample-specific MRLs. Contaminant concentrations did not exceed EPA SWSVs for freshwater (see Table 3 in Appendix B). Each of these contaminants meet the definition for volatility (i.e. Henry's Law Constant greater than  $1\text{E-}5$  or vapor pressure greater than 1), indicating potential for the contaminant to volatilize from surface water into ambient air.

The seep that forms the urban ditch unnamed tributary contained elevated concentrations of cis-1,2-DCE at 2.8 µg/L; PCE at 3.0 µg/L; and TCE at 2.1 µg/L (see Table 3 in Appendix B).

### 5.3 SOURCE CONCLUSIONS

Tetra Tech collected eight groundwater samples (including one duplicate) throughout the neighborhood study area in September 2019. In addition, Tetra Tech collected 13 surface water samples (including one duplicate and one seep). Analytical results indicate the presence of 1,1-DCE; cis-1,2-DCE; PCE; and TCE at elevated concentrations in both groundwater and surface water samples.

## 6.0 SOIL EXPOSURE AND SUBSURFACE INTRUSION PATHWAY

This section discusses the soil exposure and subsurface intrusion pathway, including sampling locations and analytical results from samples collected and recounts relevant previous investigations. Surface soil, soil gas, indoor air, and crawl space air sampling locations are depicted on Figure 4 in Appendix A and described in Table 1 of Appendix B.

### 6.1 SOIL EXPOSURE COMPONENT

To rule out overland flow as a source of contamination in surface water, Tetra Tech collected five surface soil (0 to 6 inches bgs) samples (including one duplicate) at residential properties adjacent to the unnamed tributaries. Land use surrounding the neighborhood study area is a mixture of industrial, commercial, and residential (Refs. 17, Figure 1-1; 18, Figure 1). The topography of the neighborhood study area slopes to the south and east toward unnamed tributaries (urban ditch and bedrock) (see Figure 1 and Figure 2 in Appendix A).

Surface soil samples were collected in accordance with the EPA Region 4 LSASD FBQSTP for Soil Sampling (SESDPROC-300-R3), August 2014 (Ref. 7). All surface soil samples were analyzed for 1,1-DCE; cis-1,2-DCE; trans-1,2-DCE; PCE; TCE; and vinyl chloride. Analytical results from surface soil samples were compared to EPA RSLs for residential soil (Ref. 12). The complete set of EPA Region 4 analytical data sheets is in Attachment 1, and the Tetra Tech field QC sample review is in Appendix F.

CVOCs were not detected in any of the surface soil samples. These results indicate that overland flow is likely not the cause of CVOC contamination of the unnamed tributaries (urban ditch and bedrock) within the neighborhood study area.

## 6.2 SUBSURFACE INTRUSION COMPONENT

Discussed below are previous investigations relevant to this pathway of concern, as well as analytical results from soil gas, indoor air, crawl space air, and ambient air sampling for this SI. A complete vapor intrusion pathway consists of five elements: (1) a subsurface source of vapor-forming chemicals is present beneath and near a building; (2) vapors form and have a route along which to migrate toward the building; (3) the building is susceptible to soil gas entry, which means openings exist for the vapors to enter the building; (4) vapor-forming chemicals comprising the subsurface vapor source are present in the indoor environment; and (5) the building is occupied when these chemicals are present indoors (Ref. 21, p. 22).

Soil gas samples were collected in accordance with the EPA Region 4 LSASD FBQSTP for Soil Gas Sampling (SESDPROC-307-R3), May 2014 (Ref. 8). Indoor air, crawl space air, and ambient air samples were collected in accordance with the EPA Region 4 LSASD FBQSTP for Ambient Air Sampling (SESDPROC-303-R5), March 2016 (Ref. 9). Before initiating crawl space and indoor air sampling, Tetra Tech reviewed with each resident the list of potential household sources on the NCDEQ *Indoor Air Building Survey and Sampling Form*. All listed household products present within the residence were sealed in a plastic bag 12 hours before sampling. Crawl space, indoor air, and ambient air samples were collected in individually-certified, 6-liter, stainless steel Summa canisters with 24-hour flow controllers.

All soil gas, indoor air, and crawl space air samples were analyzed for CVOCs (1,1-DCE; cis-1,2-DCE; trans-1,2-DCE; PCE; TCE; and vinyl chloride). Based on the predominant wind direction (west-northwest) during the December 2019 event, ambient air sample PSP25-AA was chosen to represent background conditions for comparison to results from indoor air and crawl space air samples also collected in December 2019. A detailed description of SI ambient air sampling is in Section 7.0 of this SI report. Analytical results from soil gas samples were compared to EPA VISLs (Ref. 15). In addition to background, results from indoor air and crawl space air samples were also compared to EPA RSLs for residential air. The complete set of EPA Region 4 analytical data sheets is in Attachment 1, and the Tetra Tech field QC sample review is in Appendix F. Soil gas, indoor air, crawl space air, and ambient air sampling locations are depicted on Figure 4 in Appendix A, and described in Table 1 of Appendix B.

### 6.2.1 Relevant Previous Investigations

In June and October 2016, S&ME, on behalf of NCDEQ, investigated six residential properties on Camborne Street, south of Patterson Street (Ref. 19, pp. 1, 2, 11) (see Figure 4 in Appendix A). During the investigation, five crawl space air samples and two indoor air samples were collected to assess

potential VI risks (Ref. 19, pp. 1, 2). Indoor air sample results indicated the presence of TCE at concentrations exceeding the NCDEQ Inactive Hazardous Site Branch (IHSB) Indoor Air Screening Level (IASL) (Ref. 19, pp. 3, 12). Crawl space air sample results indicated the presence of PCE and TCE at concentrations greater than NCDEQ IHSB IASLs (Ref. 19, pp. 3, 12). Temporary air filters were offered to residents to reduce health risks until installations of mitigation systems, or more permanent filter systems, could occur (Ref. 22, p. 1).

Based on findings from the June and October 2016 NCDEQ investigations, in May 2017, Tetra Tech, on behalf of EPA, conducted an assessment (“Stage 1”) to determine if conditions warranted a removal action. The assessment included crawl space air and soil gas sampling along the same street within the neighborhood study area (Ref. 18, p. 2). Exterior soil gas and crawl space air sample results indicated the presence of PCE and TCE at concentrations exceeding their respective EPA VISLs and NCDEQ IHSB IASLs (Ref. 18, p. 4).

Based on the results of the Stage 1 investigation, in March 2018, Tetra Tech, on behalf of EPA and NCDEQ, performed additional assessment work (described as “Stage 2”) (Ref. 23, pp. 1, 2). Results of the “Stage 1” assessment indicated the presence of PCE and TCE in crawl space air and soil gas samples at concentrations exceeding EPA and NCDEQ comparison criteria (Ref. 23, p. 2). The purpose of Stage 2 activities was to delineate the lateral extent of contamination by sampling external soil gas over a wide radius, extending downgradient from the Patterson Street industrial corridor (Ref. 23, p. 2). Based on data gathered during the Stage 2 investigation, the plume does not appear to extend west of South Holden Road or east of the north/south stretch of Swan Street. The southern extent of the plume was not identified because access could not be obtained to proposed sampling locations at residential properties south of Swan Street (Ref. 23, p. 3, Enclosure 1, Figure 2).

## **6.2.2 SI Indoor Air, Crawl Space Air, and Soil Gas Sampling Analytical Results**

During the focused SI, Tetra Tech collected six crawl space air samples at six residential properties. Additionally, two indoor air samples were collected at two of the six residential properties. Ambient air sample PSP25-AA was selected to represent background concentrations for indoor air and crawl space air samples. Indoor air samples contained elevated concentrations of 1,1-DCE (up to 0.41 micrograms per cubic meter [ $\mu\text{g}/\text{m}^3$ ]); PCE (up to 1.6  $\mu\text{g}/\text{m}^3$ ); and TCE (up to 0.93  $\mu\text{g}/\text{m}^3$ ). Crawl space air samples contained elevated concentrations of 1,1-DCE (up to 2.8  $\mu\text{g}/\text{m}^3$ ); PCE (up to 2.8  $\mu\text{g}/\text{m}^3$ ); and TCE (up to 1.1  $\mu\text{g}/\text{m}^3$ ). TCE concentrations exceeded the EPA RSL for residential air in one indoor air and three crawl space air samples (see Table 5 in Appendix B). Indoor air and crawl space air concentrations were

similar to ambient air concentrations, indicating that indoor air concentrations may be attributable to VI or to outdoor air entering the home, or a combination of both.

Tetra Tech collected 15 exterior soil gas samples (including one split) throughout the neighborhood study area. Soil gas samples contained 1,1-DCE up to 700  $\mu\text{g}/\text{m}^3$ ; cis-1,2-DCE up to 740  $\mu\text{g}/\text{m}^3$ ; trans-1,2-DCE up to 11  $\mu\text{g}/\text{m}^3$ ; PCE up to 3,600  $\mu\text{g}/\text{m}^3$ ; TCE up to 3,300  $\mu\text{g}/\text{m}^3$ ; and vinyl chloride up to 35  $\mu\text{g}/\text{m}^3$  (see Table 6 in Appendix B). Soil gas concentrations of PCE, TCE, and vinyl chloride exceed the EPA VISL Target Sub-Slab and Near-source Soil Gas Concentrations.

## 7.0 AIR MIGRATION PATHWAY

This section discusses the air migration pathway, recounts relevant previous investigations, specifies the targets associated with the pathway, and draws pathway-specific conclusions. Also discussed are sampling locations and analytical results for samples collected to evaluate the air migration pathway during the focused SI.

Ambient air samples were collected in accordance with the EPA Region 4 LSASD FBQSTP for Ambient Air Sampling (SESDPROC-303-R5), March 2016 (Ref. 9). Ambient air sampling locations are depicted on Figure 4 in Appendix A and described in Table 1 of Appendix B. For samples collected September 9 and 10, 2019, the predominant wind direction was from the east at about 5 miles per hour (mph); therefore, ambient air sample PSP24-AA was chosen to represent background for September 2019 samples. For samples collected December 3 and 4, 2019, the predominant wind direction was from the west-northwest at about 8 mph; therefore, ambient air sample PSP25-AA was chosen to represent background for December 2019 samples (Ref. 26).

All ambient air samples were analyzed for 1,1-DCE; cis-1,2-DCE; trans-1,2-DCE; PCE; TCE; and vinyl chloride. Analytical results from ambient air samples were compared to data from background ambient air samples and EPA RSLs for residential air (Ref. 12). The complete set of EPA Region 4 analytical data sheets is in Attachment 1, and the Tetra Tech field QC sample review is in Appendix F.

### 7.1 RELEVANT PREVIOUS INVESTIGATIONS

In June 2016, S&ME, on behalf of NCDEQ, investigated six residential properties on Camborne Street, south of Patterson Street (Ref. 19, pp. 1, 2, 11) (see Figure 4 in Appendix A). During the investigation, one ambient air sample was collected. The ambient air sample contained 1,1-DCE at 0.172  $\mu\text{g}/\text{m}^3$ , and TCE at 0.131  $\mu\text{g}/\text{m}^3$  (Ref. 19, pp. 3, 9, 12).

Based on the June 2016 S&ME sample results, Tetra Tech collected two additional ambient air samples in October 2016 along Camborne Street (Ref. 18, pp. 1, 2, Figure 3). One ambient air sample contained TCE at  $0.73 \mu\text{g}/\text{m}^3$  (Ref. 18, Table 2).

## **7.2 SI AMBIENT AIR SAMPLING ANALYTICAL RESULTS**

During the SI, Tetra Tech collected nine ambient air samples (including one duplicate) during the September 2019 event and five ambient air samples (including one duplicate) during the December 2019 event throughout the neighborhood study area.

Ambient air samples collected in September 2019 contained elevated concentrations of 1,1-DCE (up to  $3.7 \mu\text{g}/\text{m}^3$ ); cis-1,2-DCE (up to  $2.1 \mu\text{g}/\text{m}^3$ ); trans-1,2-DCE (up to  $0.40 \mu\text{g}/\text{m}^3$ ); PCE (up to  $6.6 \mu\text{g}/\text{m}^3$ ); TCE (up to  $3.3 \mu\text{g}/\text{m}^3$ ); and vinyl chloride (up to  $0.16 \mu\text{g}/\text{m}^3$ ). PCE exceeded its EPA RSL for residential air in one sample (PSP28), and TCE concentrations exceeded its EPA RSL for residential air in six samples (see Table 7 in Appendix B).

Ambient air samples collected in December 2019 contained elevated concentrations of PCE (up to  $0.99 \mu\text{g}/\text{m}^3$ ) and TCE (up to  $0.96 \mu\text{g}/\text{m}^3$ ). TCE concentrations exceeded its EPA RSL for residential air in two samples (see Table 7 in Appendix B).

## **7.3 AIR MIGRATION PATHWAY TARGETS**

About 9,044 people live within 1 radial mile of the study area, and about 133,924 people live within 4 radial miles of the study area. The residential population within a 4-mile radius of the study area is distributed as follows: >0 to 0.25 mile, 246 persons; >0.25 to 0.50 mile, 1,871 persons; >0.50 to 1.0 mile, 6,927 persons; >1.0 to 2.0 miles, 28,948 persons; >2.0 to 3.0 miles, 46,514 persons; >3.0 to 4.0 miles, 49,418 persons (Ref. 20).

## **7.4 AIR MIGRATION PATHWAY CONCLUSIONS**

The neighborhood study area is within a mixed industrial, commercial, and residential area. Site-related CVOCs have been detected in ambient air within the study area at elevated concentrations and/or exceeding EPA comparison criteria. About 246 people reside within 0.25 mile of the study area (Ref. 20).

## 8.0 SUMMARY AND CONCLUSIONS

The PSP site is defined as a contaminated groundwater plume with no definitive source. The PSP site is located in about 349.1 acres of land surrounding the intersection of Patterson Street and South Holden Road in Greensboro, Guilford County, North Carolina. Site boundaries have not been defined. Several industrial facilities are within the Patterson Street industrial corridor, including Ashland Chemical, Dow Corning, Ecoflo, and the NCDOT Site # 61, among others. The Patterson Street industrial corridor hosts major suppliers of blended bulk chemicals to furniture, textile, and other manufacturing businesses. Releases to the environment of CVOCs are known or suspected to have occurred at four NCDEQ IHSB sites and three RCRA sites along the Patterson Street industrial corridor. Given the large number of potential sources of the groundwater contamination in the Patterson Street industrial corridor, definitive identification of a single or multiple sources of that contamination was beyond the scope of the SI.

This SI focused on: (1) a residential neighborhood, referred to as the neighborhood study area, south of the Patterson Street industrial corridor, and (2) unnamed tributaries originating within the study area referred to as the urban ditch unnamed tributary and the bedrock unnamed tributary. The study area is bordered to the north by Immanuel Road, to the east by Belmar Street, to the south by North Hayden Street, and to the west by South Holden Road.

EPA hypothesizes that the contaminated groundwater plume is discharging to unnamed tributaries (urban ditch and bedrock) that flow through the neighborhood, and that from these unnamed tributaries volatilization of contaminants into the ambient air occurs. Therefore, the source evaluated was the contaminated groundwater plume discharging to the unnamed tributaries.

Groundwater samples collected within the study area contained cis-1,2-DCE; PCE; and TCE at concentrations exceeding both their EPA RSLs for tapwater and EPA MCLs. 1,1-DCE was detected at concentrations exceeding its EPA MCL. In September 2018, Ashland Chemical collected a groundwater sample from monitoring well MW-32BR, located within the neighborhood study area, that contained 1,1-DCE; cis-1,2-DCE; PCE; and TCE.

Surface water samples collected from both the urban ditch and bedrock unnamed tributaries contained elevated concentrations of 1,1-DCE; cis-1,2-DCE; PCE; TCE; and vinyl chloride. No CVOCs exceeded EPA SWSVs for freshwater. The seep that originates the urban ditch contained elevated concentrations of cis-1,2-DCE; PCE; and TCE.

To rule out overland flow as a source of contamination in surface water, Tetra Tech collected five surface soil samples at residential properties adjacent to the unnamed tributaries. CVOCs were not detected in any of the surface soil samples.

Tetra Tech collected two indoor air and six crawl space air samples during the SI. Indoor air and crawl space air samples contained elevated concentrations of 1,1-DCE; PCE; and TCE. TCE concentrations exceeded its EPA RSL in one indoor air and three crawl space air samples.

Tetra Tech collected 15 exterior soil gas samples throughout the neighborhood study area. Soil gas samples contained 1,1-DCE; cis-1,2-DCE; trans-1,2-DCE; PCE; TCE; and vinyl chloride. Soil gas concentrations of PCE, TCE, and vinyl chloride exceed the EPA VISLs.

Tetra Tech collected 16 ambient air samples throughout the neighborhood study area. Ambient air samples contained elevated concentrations of 1,1-DCE; cis-1,2-DCE; trans-1,2-DCE; PCE; TCE; and vinyl chloride. PCE exceeded the EPA RSL for residential air in one sample (PSP28), and TCE concentrations exceeded the EPA RSL for residential air in eight samples.

The same chlorinated solvents found in source samples (groundwater and surface water) were also found in soil gas and air samples.

The PSP site is within a mixed industrial, commercial, and residential area. Several factors suggest that the PSP site may pose a risk to human health via air migration, and site-related CVOCs have been detected in ambient air within the neighborhood study area. About 246 people reside within 0.25 mile of the PSP site.

Based on a review of historical documentation, communications with NCDEQ personnel, and analytical data acquired during the SI, Tetra Tech recommends further action under CERCLA at the PSP site at the discretion of EPA.



## 9.0 REFERENCES

1. Tetra Tech, Inc. (Tetra Tech). Final Preliminary Assessment Report for Patterson Street Solvent Plume. May 9, 2019.
2. Tetra Tech. Final Quality Assurance Project Plan for Patterson Street Solvent Plume. June 21, 2019.
3. Tetra Tech. Final Quality Assurance Project Plan Addendum for Patterson Street Solvent Plume. November 21, 2019.
4. U.S. Environmental Protection Agency (EPA), Region 4 Laboratory Services and Applied Sciences Division (LSASD). Field Branches Quality System and Technical Procedures (FBQSTP) for Design and Installation of Monitoring Wells (SESDGUID-101-R1). January 29, 2013. Accessed on-line at: <https://www.epa.gov/quality/quality-system-and-technical-procedures-lsasd-field-branches>.
5. EPA, Region 4, LSASD. FBQSTP for Groundwater Sampling (SESDPROC-301-R4). April 26, 2017. Accessed on-line at: <https://www.epa.gov/quality/quality-system-and-technical-procedures-lsasd-field-branches>.
6. EPA, Region 4, LSASD. FBQSTP for Surface Water Sampling (SESDPROC-201-R4). December 16, 2016. Accessed on-line at: <https://www.epa.gov/quality/quality-system-and-technical-procedures-lsasd-field-branches>.
7. EPA, Region 4, LSASD. FBQSTP for Soil Sampling (SESDPROC-300-R3). August 21, 2014. Accessed on-line at: <https://www.epa.gov/quality/quality-system-and-technical-procedures-lsasd-field-branches>.
8. EPA, Region 4, LSASD. FBQSTP for Soil Gas Sampling (SESDPROC-307-R3). May 14, 2014. Accessed on-line at: <https://www.epa.gov/quality/quality-system-and-technical-procedures-lsasd-field-branches>.
9. EPA, Region 4, LSASD. FBQSTP for Ambient Air Sampling (SESDPROC-303-R5). March 30, 2016. Accessed on-line at: <https://www.epa.gov/quality/quality-system-and-technical-procedures-lsasd-field-branches>.
10. EPA, Laboratory Services Branch. Laboratory Operations and Quality Assurance Manual. Effective Date: May 21, 2019.
11. EPA, Office of Superfund Remediation and Technology Innovation. National Functional Guidelines for Organic Superfund Methods Data Review, EPA-540-R-2017-002. January 2017.
12. EPA. Regional Screening Levels Summary Table (TR=1E-06, HQ=0.1). November 2019. Accessed on-line at: <https://www.epa.gov/risk/regional-screening-levels-rsls-generic-tables>.
13. EPA, Office of Water. 2018 Edition of the Drinking Water Standards and Health Advisories, EPA 822-F-18-001. March 2018. Accessed on-line at: <https://www.epa.gov/dwstandardsregulations/2018-drinking-water-standards-and-advisory-tables>.

14. EPA, Scientific Support Division. Region 4 Ecological Risk Assessment Supplemental Guidance. March 2018. Accessed on-line at: <https://www.epa.gov/risk/regional-ecological-risk-assessment-era-supplemental-guidance>.
15. Arcadis U.S., Inc. (Arcadis). 2018 Annual Groundwater and Semiannual Surface Water Sampling Report, Former Ashland Facility, Greensboro, North Carolina. March 21, 2019.
16. EPA. Vapor Intrusion Screening Levels. Accessed: January 22, 2020. Accessed on-line at: <https://www.epa.gov/vaporintrusion/vapor-intrusion-screening-level-calculator>.
17. Shield Environmental Associates, Inc. (Shield Environmental). Phase III Site Investigation Report for Dow Corning Corporation, Greensboro Facility. March 1998.
18. Tetra Tech. Removal Assessment Letter Report – Final, Patterson Street Solvent Plume. May 5, 2017.
19. S&ME, Inc (S&ME). Crawlspace and Indoor Vapor Sampling Chemical and Solvents, Inc. Site. October 10, 2016.
20. Tetra Tech. Project Note to File. Subject: Population within distance rings for Patterson Street Solvent Plume. December 17, 2018.
21. EPA, Office of Solid Waste and Emergency Response (OSWER). OSWER Technical Guide for Assessing and Mitigating the Vapor Intrusion Pathway from Subsurface Vapor Sources to Indoor Air, OSWER Publication 9200.2-154. June 2015.
22. North Carolina Department of Environment and Natural Resources (NCDENR), Division of Waste Management. Crawlspace Air Sampling Results – 2832 Camborne Street. July 15, 2016.
23. Tetra Tech. Removal Assessment Letter Report – Draft, Patterson Street Solvent Plume – Stage 2. April 13, 2018.
24. URS Corporation. Site Characterization Report – Revision 1, Dow Corning Corporation. June 2014.
25. Arcadis. Comprehensive RCRA Facility Investigation Report – Phase III, Former Ashland Distribution Facility. September 2013.
26. Tetra Tech. Project Note to File with Attachment. Subject: Wind Directions and Speeds for Site Inspection Sampling Events, Patterson Street Solvent Plume. Attachment: Daily Observations. December 5, 2019.

## APPENDIX A


### FIGURES

(Four Pages)

#### **Figure**

- 1 SITE LOCATION
- 2 PATTERSON STREET SOLVENT PLUME AREA
- 3 NEIGHBORHOOD STUDY AREA
- 4 SI SAMPLING LOCATIONS






## Legend

★ Site Location



0 1,000 2,000  
Feet

Map Source:  
USGS 7.5 Minute Topographic Quadrangle Map:  
Greensboro, NC 1997.



United States  
Environmental Protection Agency  
Region 4

## FIGURE 1 Site Location

**TDD Name:** Patterson Street Solvent  
Plume Site


**TDD No.:** TT-05-041

**City:** Greensboro **County:** Guilford **State:** North Carolina




**Date:**  
1/15/2019  
**Analyst:**  
dale.vonbusch





- Legend**
- Drainage Ditch
  - Railroad Spur
  - Former Railroad Spur
  - Stream
  - Underground Stream
  - Direction of Flow
  - Approximate Study Area
  - Building
  - Former Building



Notes:  
NCDOT - North Carolina Department of Transportation  
TAPCO - Thompson Arthur Paving Company  
Map Source:  
Bing Maps Aerial Imagery, 2015.


 **United States Environmental Protection Agency Region 4**

**FIGURE 2**  
**Patterson Street Solvent Plume Area**


**TDD Name:** Patterson Street Solvent Plume Site  
**TDD No.:** TT-05-041  
**City:** Greensboro  
**County:** Guilford  
**State:** North Carolina

 **TETRA TECH**  
**Date:** 1/21/2020  
**Analyst:** dale.vonbusch





- Legend**
- Railroad Spur
  - Unnamed Tributary
  - Underground Stream
  - Direction of Flow
  - Culvert
  - Approximate Extent of Neighborhood Study Area



Map Source:  
Bing Maps Aerial Imagery, 2015.

 **United States  
Environmental Protection Agency  
Region 4**


**FIGURE 3**  
Neighborhood Study Area

<b>TDD Name:</b>	Patterson Street Solvent Plume Site	
<b>TDD No.:</b>	TT-05-041	
<b>City:</b>	<b>County:</b>	<b>State:</b>
Greensboro	Guilford	North Carolina

 **TETRA TECH**

**Date:**  
1/21/2020  
**Analyst:**  
dale.vonbusch





**Legend**

- ▲ Surface Water Sample
- Groundwater, Soil Gas, Ambient Air, and Surface Soil Sample
- Soil Gas, Crawl Space Air, Indoor Air, and Ambient Air Sample
- ◆ Soil Gas Sample
- Soil Gas and Ambient Air Sample
- Groundwater Sample
- Surface Water and Ambient Air Sample
- Groundwater, Soil Gas, and Ambient Air Sample
- Groundwater, Soil Gas, Crawl Space Air, and Ambient Air Sample
- ◆ Ambient Air and Crawl Space Air Sample
- Crawl Space Air Sample
- Unnamed Tributary
- Underground Stream
- Direction of Flow
- ⤵ Culvert

Notes:  
PSP - Patterson Street Solvent Plume Site

Map Source:  
Bing Maps Aerial Imagery, 2015.

United States Environmental Protection Agency Region 4

**FIGURE 4**

SI Sampling Locations

<b>TDD Name:</b>	Patterson Street Solvent Plume Site	
<b>TDD No.:</b>	TT-05-041	
<b>City:</b>	<b>County:</b>	<b>State:</b>
Greensboro	Guilford	North Carolina

**TETRA TECH**

**Date:**  
1/31/2020

**Analyst:**  
dale.vonbusch



## **APPENDIX B**

### **TABLES**

(Nine Pages)

#### **Table**

1	SAMPLING LOCATIONS
2	ANALYTICAL RESULTS FOR GROUNDWATER SAMPLES
3	ANALYTICAL RESULTS FOR SURFACE WATER SAMPLES
4	ANALYTICAL RESULTS FOR SURFACE SOIL SAMPLES
5	ANALYTICAL RESULTS FOR CRAWL SPACE AIR AND INDOOR AIR SAMPLES
6	ANALYTICAL RESULTS FOR SOIL GAS SAMPLES
7	ANALYTICAL RESULTS FOR AMBIENT AIR SAMPLES



**TABLE 1**  
**PATTERSON STREET SOLVENT PLUME SI**  
**SAMPLING LOCATIONS**

Station ID	Sample ID	Depth (bgs)	Sample Matrix	Analysis	Sample Location
PSP01	PSP01-SW	NA	Surface Water	CVOCs	About 1,480 feet northeast from the intersection of South Holden Road and Camborne Street
	PSP01-SW-DUP				
PSP02	PSP02-SW	NA	Surface Water	CVOCs	About 1,270 feet east of the intersection of South Holden Road and Camborne Street
PSP03	PSP03-SW	NA	Surface Water	CVOCs	About 1,110 feet southeast of the intersection of South Holden Road and Camborne Street
PSP04	PSP04-SW	NA	Surface Water	CVOCs	About 1,060 feet southeast of the intersection of South Holden Road and Camborne Street
PSP05	PSP05-SW	NA	Surface Water	CVOCs	About 900 feet southeast of the intersection of South Holden Road and Camborne Street
PSP06	PSP06-SW	NA	Surface Water	CVOCs	About 740 feet southeast of the intersection of South Holden Road and Camborne Street
PSP07	PSP07-SW	NA	Surface Water	CVOCs	About 475 feet southeast of the intersection of South Holden Road and Camborne Street
PSP08	PSP08-SW	NA	Surface Water	CVOCs	About 1,110 feet southeast of the intersection of South Holden Road and Camborne Street
PSP09	PSP09-SW	NA	Surface Water	CVOCs	About 1,270 feet southeast of the intersection of South Holden Road and Camborne Street
PSP10	PSP10-GW	5 to 10 feet	Groundwater	CVOCs	About 470 feet southeast of the intersection of South Holden Road and Camborne Street
	PSP10-SF	0 to 6 inches	Surface Soil	CVOCs	
	PSP10-AA	NA	Ambient Air	CVOCs	
	PSP10-AA-DUP				
	PSP10-SG	1.5 to 2 feet	Soil Gas	CVOCs	
PSP11	PSP11-GW	2 to 7 feet	Groundwater	CVOCs	About 600 feet southeast of the intersection of South Holden Road and Camborne Street
	PSP11-SF	0 to 6 inches	Surface Soil	CVOCs	
	PSP11-SF-DUP				
	PSP11-AA	NA	Ambient Air	CVOCs	
	PSP11-SG	3.5 to 4 feet	Soil Gas	CVOCs	
PSP12	PSP12-GW	5 to 10 feet	Groundwater	CVOCs	About 730 feet southeast of the intersection of South Holden Road and Camborne Street
	PSP12-SF	0 to 6 inches	Surface Soil	CVOCs	
	PSP12-AA	NA	Ambient Air	CVOCs	
	PSP12-SG	2.5 to 3 feet	Soil Gas	CVOCs	
PSP13	PSP13-GW	15 to 20 feet	Groundwater	CVOCs	About 900 feet southeast of the intersection of South Holden Road and Camborne Street
	PSP13-SF	0 to 6 inches	Surface Soil	CVOCs	
	PSP13-AA	NA	Ambient Air	CVOCs	
	PSP13-SG	5.5 to 6 feet	Soil Gas	CVOCs	
	PSP13-SG-SPLIT				
PSP14	PSP14-SG	7 to 7.5 feet	Soil Gas	CVOCs	About 535 feet east of the intersection of South Holden Road and Camborne Street
	PSP14-CS	NA	Crawl Space Air	CVOCs	
	PSP14-IA	NA	Indoor Air	CVOCs	
	PSP14-AA	NA	Ambient Air	CVOCs	

**TABLE 1**  
**PATTERSON STREET SOLVENT PLUME SI**  
**SAMPLING LOCATIONS**

Station ID	Sample ID	Depth (bgs)	Sample Matrix	Analysis	Sample Location
PSP15	PSP15-SG	6.5 to 7 feet	Soil Gas	CVOCs	About 930 feet east of the intersection of South Holden Road and Camborne Street
PSP16	PSP16-AA	NA	Ambient Air	CVOCs	About 230 feet southeast of the intersection of South Holden Road and Camborne Street
	PSP16-SG	14.5 to 15 feet	Soil Gas	CVOCs	
PSP17	PSP17-GW	3.5 to 13.5 feet	Groundwater	CVOCs	About 330 feet southeast of the intersection of South Holden Road and Camborne Street
PSP19	PSP19-SG	6.5 to 7 feet	Soil Gas	CVOCs	About 740 feet east of the intersection of South Holden Road and Camborne Street
PSP20	PSP20-SG	5.5 to 6 feet	Soil Gas	CVOCs	About 880 feet southeast of the intersection of South Holden Road and Camborne Street
	PSP20-CS	NA	Crawl Space Air	CVOCs	
	PSP20-IA	NA	Indoor Air	CVOCs	
	PSP20-AA	NA	Ambient Air	CVOCs	
	PSP20-AA-DUP				
PSP21	PSP21-AA	NA	Ambient Air	CVOCs	About 1,070 feet southeast of the intersection of South Holden Road and Camborne Street
	PSP21-SG	2.5 to 3 feet	Soil Gas	CVOCs	
PSP22	PSP22-SEEP	NA	Surface Water	CVOCs	About 450 feet northeast of the intersection of South Holden Road and Camborne Street
	PSP22-AA	NA	Ambient Air	CVOCs	
PSP24	PSP24-GW	1.5 to 6.5 feet	Groundwater	CVOCs	Northeastern corner of West Florida Street and Belmar Street
	PSP24-GW-DUP				
	PSP24-AA	NA	Ambient Air	CVOCs	
	PSP24-SG	2.5 to 3 feet	Soil Gas	CVOCs	
PSP25	PSP25-GW	5 to 10 feet	Groundwater	CVOCs	About 77 feet southeast of the intersection of South Holden Road and Camborne Street
	PSP25-SG	1.5 to 2 feet	Soil Gas	CVOCs	
	PSP25-CS	NA	Crawl Space Air	CVOCs	
	PSP25-AA	NA	Ambient Air	CVOCs	
PSP26	PSP26-AA	NA	Ambient Air	CVOCs	About 170 feet northeast of the intersection of South Holden Road and Camborne Street
	PSP26-CS	NA	Crawl Space Air	CVOCs	
PSP27	PSP27-SG	9.5 to 10 feet	Soil Gas	CVOCs	About 600 feet southeast of the intersection of South Holden Road and Swan Street
PSP28	PSP28-AA	NA	Ambient Air	CVOCs	About 350 feet southeast of the intersection of South Holden Road and Swan Street
	PSP28-SG	6.5 to 7 feet	Soil Gas	CVOCs	
PSP29	PSP29-CS	NA	Crawl Space Air	CVOCs	About 235 feet northeast of the intersection of South Holden Road and Camborne Street
	PSP29-AA	NA	Ambient Air	CVOCs	
PSP30	PSP30-CS	NA	Crawl Space Air	CVOCs	About 175 feet northeast of the intersection of South Holden Road and Camborne Street
PSP31	PSP31-SW	NA	Surface Water	CVOCs	About 0.6 mile southeast of the bedrock stream in the PSP study area
PSP32	PSP32-SW	NA	Surface Water	CVOCs	About 0.75 mile southeast of the bedrock stream in the PSP study area

**TABLE 1**  
**PATTERSON STREET SOLVENT PLUME SI**  
**SAMPLING LOCATIONS**

Notes:

AA	Ambient air sample
bgs	Below ground surface
CS	Crawl space air
CVOCs	Chlorinated volatile organic compounds (1,1-DCE, cis-1,2-DCE, trans-1,2-DCE, PCE, TCE, and vinyl chloride)
DCE	Dichloroethene
DUP	Duplicate
GW	Groundwater sample
IA	Indoor air
ID	Identification
NA	Not applicable
PCE	Tetrachloroethene
PSP	Patterson Street Solvent Plume
SF	Surface soil sample
SG	Soil gas sample
SW	Surface water sample
TCE	Tetrachloroethene

**TABLE 2**  
**PATTERSON STREET SOLVENT PLUME SI**  
**ANALYTICAL RESULTS FOR GROUNDWATER SAMPLES**

Analyte	EPA RSL	EPA MCL	PSP10	PSP11	PSP12	PSP13	PSP17	PSP24		PSP25
	Tapwater		PSP10-GW	PSP11-GW	PSP12-GW	PSP13-GW	PSP17-GW	PSP24-GW	PSP24-GW-DUP	PSP25-GW
	Chlorinated Volatile Organic Compounds (µg/L)									
1,1-Dichloroethene	280	7	0.13 J	0.50 U	0.50 U	0.50 U	110	0.50 U	0.50 U	220
cis-1,2-Dichloroethene	36	70	0.50 U	0.50 U	0.50 U	0.50 U	140	0.50 U	0.50 U	74
Tetrachloroethene	11	5	0.50 U	0.50 U	0.29 J	0.50 U	460	0.50 U	0.50 U	140
trans-1,2-Dichloroethene	36	100	0.50 U	0.50 U	0.50 U	0.50 U	5.0 U	0.50 U	0.50 U	2.5 U
Trichloroethene	0.49	5	0.14 J	0.50 U	0.18 J	0.50 U	640	0.50 U	0.50 U	120
Vinyl chloride	0.019	2	0.50 U	0.50 U	0.50 U	0.50 U	5.0 U	0.50 U	0.50 U	2.5 U

Notes:

DUP	Duplicate
EPA	U.S. Environmental Protection Agency
GW	Groundwater
J	The identification of the analyte is acceptable; the reported value is an estimate.
MCL	2018 Maximum Contaminant Level
µg/L	Micrograms per liter
PSP	Patterson Street Solvent Plume
RSL	November 2019 Regional Screening Level (Target Risk=1E-06, Hazard Quotient=1.0) for tapwater
U	Analyte not detected at concentration at or above reporting limit.
	Shaded values exceed the EPA RSL for tapwater or the EPA MCL.

**TABLE 3**  
**PATTERSON STREET SOLVENT PLUME SI**  
**ANALYTICAL RESULTS FOR SURFACE WATER SAMPLES**

Analyte	EPA SWSV		Background		PSP01		PSP02	PSP03	PSP04	PSP05
	Freshwater		PSP31	PSP32	PSP01-SW	PSP01-SW-DUP	PSP02-SW	PSP03-SW	PSP04-SW	PSP05-SW
	Chronic	Acute	PSP31-SW	PSP32-SW						
Chlorinated Volatile Organic Compounds (µg/L)										
1,1-Dichloroethene	130	1,200	0.50 U	0.50 U	27	28	6.8	9.6	40	8.0
cis-1,2-Dichloroethene	620	5,500	0.50 U	0.50 U	1.8	1.8	5.4	12	20	5.3
Tetrachloroethene	53	430	0.50 U	0.50 U	5.9	5.8	16	88	49	8.6
trans-1,2-Dichloroethene	558	10,046	0.50 U	0.50 U	0.50 U	0.50 U	0.50 U	0.50 U	0.50 U	0.50 U
Trichloroethene	220	2,000	0.50 U	0.50 U	6.3	6.4	7.4	33	31	6.2
Vinyl chloride	930	8,400	0.50 U	0.50 U	0.52	0.54	0.26 J	0.84	1.3	0.27 J

Analyte	EPA SWSV		Background		PSP06	PSP07	PSP08	PSP09	PSP22
	Freshwater		PSP31	PSP32	PSP06-SW	PSP07-SW	PSP08-SW	PSP09-SW	PSP22-SEEP
	Chronic	Acute	PSP31-SW	PSP32-SW					
Chlorinated Volatile Organic Compounds (µg/L)									
1,1-Dichloroethene	130	1,200	0.50 U	0.50 U	6.9	7.4	28	24	0.25 J
cis-1,2-Dichloroethene	620	5,500	0.50 U	0.50 U	6.0	6.6	17	15	2.8
Tetrachloroethene	53	430	0.50 U	0.50 U	6.6	7.5	44	36	3.0
trans-1,2-Dichloroethene	558	10,046	0.50 U	0.50 U	0.50 U	0.50 U	0.50 U	0.50 U	0.50 U
Trichloroethene	220	2,000	0.50 U	0.50 U	6.2	7.1	24	20	2.1
Vinyl chloride	930	8,400	0.50 U	0.50 U	0.50 U	0.50 U	1.2	1.1	0.50 U

Notes:

DUP	Duplicate
EPA	U.S. Environmental Protection Agency
J	The identification of the analyte is acceptable; the reported value is an estimate.
µg/L	Micrograms per liter
PSP	Patterson Street Solvent Plume
SW	Surface water
SWSV	2018 Surface Water Screening Value
U	Analyte not detected at concentration at or above reporting limit.
<b>BOLD</b>	Bolded values are elevated, meaning that the values are three times the concentration of detected constituents in the background sample or greater than or equal to the non-detect concentration in the background sample.

**TABLE 4**  
**PATTERSON STREET SOLVENT PLUME SI**  
**ANALYTICAL RESULTS FOR SURFACE SOIL SAMPLES**

Analyte	EPA RSL	PSP10	PSP11		PSP12	PSP13
	Residential	PSP10-SF	PSP11-SF	PSP11-SF-DUP	PSP12-SF	PSP13-SF
<b>Chlorinated Volatile Organic Compounds (µg/kg)</b>						
1,1-Dichloroethene	230	0.79 UJ	0.92 U	0.85 U	0.80 U	0.87 U
cis-1,2-Dichloroethene	160	0.79 UJ	0.92 U	0.85 U	0.80 U	0.87 U
Tetrachloroethene	24	0.79 UJ	0.92 U	0.85 U	0.80 U	0.87 U
trans-1,2-Dichloroethene	1,600	0.79 UJ	0.92 U	0.85 U	0.80 U	0.87 U
Trichloroethene	0.94	0.79 UJ	0.92 U	0.85 U	0.80 U	0.87 U
Vinyl chloride	0.059	0.79 UJ	0.92 U	0.85 U	0.80 U	0.87 U

Notes:

DUP	Duplicate
EPA	U.S. Environmental Protection Agency
µg/kg	Micrograms per kilogram
PSP	Patterson Street Solvent Plume
RSL	November 2019 Regional Screening Level (Target Risk=1E-06, Hazard Quotient=1.0) for residential soil
SF	Surface soil
U	Analyte not detected at concentration at or above reporting limit.
UJ	Analyte not detected at concentration at or above reporting limit, which is considered approximate due to deficiencies in one or more quality control criteria.

**TABLE 5**  
**PATTERSON STREET SOLVENT PLUME SI**  
**ANALYTICAL RESULTS FOR CRAWL SPACE AIR AND INDOOR AIR SAMPLES**

Analyte	EPA RSL	Background	PSP14		PSP20	
		PSP25	Crawl Space	Indoor Air	Crawl Space	Indoor Air
	Residential	PSP25-AA	PSP14-CS	PSP14-IA	PSP20-CS	PSP20-IA
<b>Chlorinated Volatile Organic Compounds (µg/m<sup>3</sup>)</b>						
1,1-Dichloroethene	210	0.12 J	0.35	<b>0.41</b>	0.29	<b>0.36</b>
cis-1,2-Dichloroethene	NE	0.20 U	0.11 J	0.15 J	0.15 J	0.17 J
Tetrachloroethene	11	0.24 J	<b>1.6</b>	<b>1.1</b>	<b>2.8</b>	<b>1.6</b>
trans-1,2-Dichloroethene	NE	0.20 U	0.21 U	0.23 U	0.21 U	0.22 U
Trichloroethene	0.48	0.18 J	<b>0.98</b>	<b>0.93</b>	0.34	0.38
Vinyl chloride	0.17	0.13 U	0.14 U	0.15 U	0.14 U	0.14 U

Analyte	EPA RSL	Background	PSP25	PSP26	PSP29	PSP30
		PSP25	Crawl Space	Crawl Space	Crawl Space	Crawl Space
	Residential	PSP25-AA	PSP25-CS	PSP26-CS	PSP29-CS	PSP30-CS
<b>Chlorinated Volatile Organic Compounds (µg/m<sup>3</sup>)</b>						
1,1-Dichloroethene	210	0.12 J	0.23 J	<b>0.36</b>	<b>2.8</b>	0.23
cis-1,2-Dichloroethene	NE	0.20 U	0.22 U	0.11 J	0.095 J	0.20 U
Tetrachloroethene	11	0.24 J	0.68	<b>0.81</b>	<b>1.8</b>	0.51
trans-1,2-Dichloroethene	NE	0.20 U	0.084 J	0.21 U	0.11 J	0.20 U
Trichloroethene	0.48	0.18 J	0.25 J	<b>0.68</b>	<b>1.1</b>	0.44
Vinyl chloride	0.17	0.13 U	0.14 U	0.14 U	0.14 U	0.13 U

Notes:

AA	Ambient air
CS	Crawl space air
EPA	U.S. Environmental Protection Agency
IA	Indoor air
J	The identification of the analyte is acceptable; the reported value is an estimate.
µg/m <sup>3</sup>	Micrograms per cubic meter
NE	Not established
PSP	Patterson Street Solvent Plume
RSL	November 2019 Regional Screening Level (Target Risk=1E-06, Hazard Quotient=1.0) for residential air
U	Analyte not detected at concentration at or above reporting limit.
<b>BOLD</b>	Bolded values are elevated, meaning that the values are three times the concentration of detected constituents in the background sample or greater than or equal to the non-detect concentration in the background sample.
	Shaded values exceed the EPA RSL for residential air.
<b>BOLD</b>	Bolded and shaded values are elevated and equal or exceed the EPA RSL for residential air.

**TABLE 6**  
**PATTERSON STREET SOLVENT PLUME SI**  
**ANALYTICAL RESULTS FOR SOIL GAS SAMPLES**

Analyte	EPA VISL	PSP10	PSP11	PSP12	PSP13		PSP14	PSP15	PSP16
		PSP10-SG	PSP11-SG	PSP12-SG	PSP13-SG	PSP13-SG-SPLIT	PSP14-SG	PSP15-SG	PSP16-SG
Chlorinated Volatile Organic Compounds (µg/m³)									
1,1-Dichloroethene	6,950	0.13 J	0.31	0.21 U	0.39	0.39	700	1.2 U	3.0
cis-1,2-Dichloroethene	NE	0.20 U	0.12 J	0.19 U	0.097 J	0.13 J	740	0.20 U	0.21 U
Tetrachloroethene	360	2.1	1.0	9.5	0.64	0.66	3,600	3.5	190
trans-1,2-Dichloroethene	NE	0.20 U	0.20 U	0.19 U	0.22 U	0.22 U	11	0.20 U	0.21 U
Trichloroethene	15.9	0.64	0.36	0.26 U	0.33	0.36	3,300	0.37	0.42
Vinyl chloride	5.59	0.13 U	0.13 U	0.13 U	0.14 U	0.14 U	35	0.72	12

Analyte	EPA VISL	PSP19	PSP20	PSP21	PSP24	PSP25	PSP27	PSP28
		PSP19-SG	PSP20-SG	PSP21-SG	PSP24-SG	PSP25-SG	PSP27-SG	PSP28-SG
Chlorinated Volatile Organic Compounds (µg/m³)								
1,1-Dichloroethene	6,950	3.6 U	150	0.14 J	0.23 U	11	32	1.1
cis-1,2-Dichloroethene	NE	0.23 U	17	0.20 U	0.22 U	1.9 J	0.21 U	0.21 U
Tetrachloroethene	360	3.8	340	7.4	0.96	1,200	21	6.0
trans-1,2-Dichloroethene	NE	0.23 U	4.5	0.20 U	0.22 U	0.46 J	0.21 U	0.21 U
Trichloroethene	15.9	1.1	330	0.25 J	0.27 J	19	3.1	0.33
Vinyl chloride	5.59	4.1	3.1	0.59	0.14 U	0.14 UJ	0.13 U	0.17

Notes:

EPA	U.S. Environmental Protection Agency
J	The identification of the analyte is acceptable; the reported value is an estimate.
µg/m <sup>3</sup>	Micrograms per cubic meter
NE	Not established
PSP	Patterson Street Solvent Plume
SG	Soil gas
U	Analyte not detected at concentration at or above reporting limit.
UJ	Analyte not detected at concentration at or above reporting limit, which is considered approximate due to deficiencies in one or more quality control criteria.
VISL	EPA Vapor Intrusion Screening Levels for target sub-slab and near-source soil gas for residential properties (Target Risk=1E-6, Target Hazard Quotient=1.0)
	Shaded values exceed the EPA VISL.



**TABLE 7**  
**PATTERSON STREET SOLVENT PLUME SI**  
**ANALYTICAL RESULTS FOR AMBIENT AIR SAMPLES**

SEPTEMBER 2019 SAMPLING EVENT											
Analyte	EPA RSL	Background	PSP10		PSP11	PSP12	PSP13	PSP16	PSP21	PSP26	PSP28
		PSP24	PSP10-AA-DUP	PSP11-AA	PSP12-AA	PSP13-AA	PSP16-AA	PSP21-AA	PSP26-AA	PSP28-AA	
	Residential	PSP24-AA									
Chlorinated Volatile Organic Compounds (µg/m <sup>3</sup> )											
1,1-Dichloroethene	210	0.27	0.55	0.54	0.20 J	1.0	0.34	0.23 U	0.56	0.60	3.7
cis-1,2-Dichloroethene	NE	0.16 J	0.36	0.34	0.13 J	0.59	0.20 J	0.21 U	0.40	0.22	2.1
Tetrachloroethene	11	0.86	0.90 J	1.2 J	0.38	1.5	0.67	0.21 J	3.1	0.65	6.6
trans-1,2-Dichloroethene	NE	0.21 U	0.21 U	0.40	0.22 U	0.21 U	0.22 U	0.21 U	0.22 U	0.21 U	0.22 U
Trichloroethene	0.48	0.31	0.63	0.66	0.21 J	0.92	0.35	0.099 J	1.2	0.52	3.3
Vinyl chloride	0.17	0.13 U	0.14 U	0.14 U	0.14 U	0.13 U	0.14 U	0.14 U	0.14 U	0.14 U	0.16

DECEMBER 2019 SAMPLING EVENT							
Analyte	EPA RSL	Background	PSP14	PSP20		PSP22	PSP29
		PSP25	PSP14-AA	PSP20-AA	PSP20-AA-DUP	PSP22-AA	PSP29-AA
	Residential	PSP25-AA					
Chlorinated Volatile Organic Compounds (µg/m <sup>3</sup> )							
1,1-Dichloroethene	210	0.12 J	0.33	0.25	0.25	0.35	0.20 J
cis-1,2-Dichloroethene	NE	0.20 U	0.11 J	0.16 J	0.12 J	0.15 J	0.22 U
Tetrachloroethene	11	0.24 J	0.95	0.77	0.79	0.99	0.46
trans-1,2-Dichloroethene	NE	0.20 U	0.21 U	0.21 U	0.21 U	0.21 U	0.22 U
Trichloroethene	0.48	0.18 J	0.83	0.38	0.35	0.96	0.39
Vinyl chloride	0.17	0.13 U	0.13 U	0.14 U	0.14 U	0.13 U	0.14 U

Notes:

AA	Ambient air
DUP	Duplicate
EPA	U.S. Environmental Protection Agency
J	The identification of the analyte is acceptable; the reported value is an estimate.
µg/m <sup>3</sup>	Micrograms per cubic meter
NE	Not established
PSP	Patterson Street Solvent Plume
RSL	November 2019 Regional Screening Level (Target Risk=1E-06, Hazard Quotient=1.0) for residential air
U	Analyte not detected at concentration at or above reporting limit.
<b>BOLD</b>	Bolded values are elevated, meaning that the values are three times the concentration of detected constituents in the background sample or greater than or equal to the non-detect concentration in the background sample.
	Shaded values exceed the EPA RSL for residential air.
<b>BOLD</b>	Bolded and shaded values are elevated and equal or exceed the EPA RSL for residential air.

## **APPENDIX C**

### **FIELD LOGBOOK NOTES, FIELD SHEETS, AND BORING LOGS**

(108 Pages)

**==DEFYING==  
MOTHER NATURE®**

SINCE 1916



All components of  
this product are recyclable

**Rite in the Rain**

A patented, environmentally  
responsible, all-weather writing paper  
that sheds water and enables you to  
write anywhere, in any weather.

Using a pencil or all-weather pen,  
*Rite in the Rain* ensures that your  
notes survive the rigors of the field,  
regardless of the conditions.

© 2019

JL DARLING LLC  
Tacoma, WA 98424-1017 USA  
[www.RiteintheRain.com](http://www.RiteintheRain.com)

**Item No. 371FX**

NSN: 7530-01-642-7769  
ISBN: 978-1-60134-186-0

Made in the USA  
US Pat No. 6,863,940



25037153

TT-05-041

PATTERSON ST SOLVENT  
PLUME



*Rite in the Rain®*

ALL-WEATHER  
**UNIVERSAL**

Nº 371FX

LOGBOOK 1

6



2 9/9/19 Patterson L. Shaver

0700 START Kelley, Shaver, and Falkner  
mob to site

0720 START arrives on site

START Snyder on site with GPR @ 0930  
also NCDEQ on site

1300 - START Kelley, Shaver, and Falkner  
arrive at site. Meet with START Snyder.

1400 - Set up ambient air canisters  
for deployment.

1430 - Deployed ambient air canisters  
at seven locations (see field sheet  
for additional details).

1500 - Use thermal imaging camera  
to locate groundwater seeps.

1530 - Meet with EPA Cathy Amoroso.

1630 - check ambient air canisters

1700 - START done for day. <sup>AF</sup>

Amber Falkner  
09-09-2019

Scale: 1 square =

09-10-2019 3

0745 - START Snyder, Kelley, Shaver,  
and Falkner arrive at site.

Weather - 88°/68° cloudy. 10% chance  
of rain. wind: SSE at 5 mph.

0750 - check on ambient air canisters.

Note - Yesterday's wind: 5 mph ENE.

Today's wind: 4 mph E.

0800 START meets EPA & NCDEQ to  
discuss today's activities. NCDEQ  
will continue to canvas for access.  
The drillers won't arrive until tomorrow;  
therefore, START will collect the  
SW samples along the unnamed  
creek & deploy the last AA samples.

0830 START Snyder & EPA will  
scout the interior <sup>(west)</sup> branch of the  
creek while START Kelley, Shaver,  
& Falkner collect SW samples along  
the main (east) branch of the  
unnamed creek. See field forms  
for sample details.

1330 - START deploys AA Samples.  
See field forms.

1530 START processes samples.

1630 START done for the day.

Scale: 1 square =

Amber Kelley 9/10/19



4 9/11/19

0745 START arrives at the site.

Conducts H&S briefing. Meets driller.

0815 START calibrates the Horiba water quality meter.

0830 START & Cascade set up at PSP24 to collect GW & SG. See the field forms for sample details.

0850 Drill to ~6.5 feet bgs at PSP24 before refusal. Set well at 6.5 ft. Will let sit & sample later.

0920 Driller sets up at PSP13.

0930 START collects surface soil sample PSP13-SF from 0 to 1 ft bgs. Set well at 10 ft bgs. Will let sit & sample later.

0950 Driller sets up at PSP21.

See boring logs & field forms for details.

1020 - Driller sets up at PSP20 to set SG implant. Set at 5.5 - 6.0 ft bgs.

1048 - Driller sets up at PSP12. Drill well to ~10 ft before refusal. Well set at 5 ft bgs. SG implant installed at 2-3 ft bgs.

1118 - Drillers set up at PSP11. Drilled to 7 ft bgs before refusal. Well set at 2-7 ft bgs. No SG implant, soil saturated at 3 ft bgs. *Amber 9/11/19*

Scale: 1 square =

09/11/19 5

1135 - Second hole at PSP11 for SF duplicate.

1145 - Drillers set up at PSP10 for SF, SG, & GW. Well depth is ~10 ft bgs. SG implant will be installed after well abandoned.

1350 - Drillers set up at PSP18. SG implant set at 9 ft bgs.

1415 - Drillers set up at PSP16. SG implant not installed because 15 ft of clay bgs. PSP22 SG implant abandoned due to same clay backfill at PSP16.

1510 - Drillers set up at PSP25. Well bottom at 10 ft bgs. SG implant at 2 ft bgs. Well moved from PSP26 to PSP25. Drillers set up at PSP26. <sup>AF</sup> Well Refusal at 8 ft bgs. - SG implant installed at 8 ft bgs.

*Lab entry - find team to collect ambient air & ground water samples*

PSP-24, 1520, well purged dry, no collection

PSP-12, sample collection @ 1621 (groundwater)

PSP-11, well dry @ 1630

PSP-10, sample collected @ 1648

to hotel to process samples, other team to soil gas collected. Soil gas collection aborted. End of day @ 1900

Scale: 1 square =

*Shaw 9/11/19*

*Rite in the Rain*



<sup>6</sup> 09-12-2019

0745 - START arrives at site. Conducts H+S meeting.

0800 - Cascade and START set up at PSP17.

0815 - START Shaver + Falkner arrive at PSP<sup>13</sup> to collect groundwater samples. <sup>AF</sup> Well was dry.

0820 - START Shaver + Falkner arrive at PSP 24 to collect groundwater samples. Well was dry.

0825 - START Shaver + Falkner arrive at PSP12 to collect groundwater samples. Well was dry.

0845 - START Shaver + Falkner arrive at PSP25 to collect groundwater samples. <sup>Leah Entry (2nd team)</sup>

0800 drill @ PSP17

soil core @ 0818, refusal @ 13.5 ft BGS  
temp. well set @ 13.5 ft, 10 ft screen

0837 drill @ PSP14, refusal @ 7.5 ft BGS

soil gas implant set @ 7 ft BGS

0910 drill @ PSP19, soil gas implant set @ 7 ft BGS

0930 drill @ PSP15, soil gas implant set @ 7 ft BGS

Scale: 1 square =

Shaver 9/12/19

C-5

9/12/19

L. Shaver<sup>7</sup>

1025 drill @ PSP27, temp. well set @ 20 ft BGS with 10 ft screen

soil gas implant set between 9 and 10 ft BGS

1115 drill @ PSP28, temp. well set @

24 ft BGS w/ 10 ft screen

soil gas implant set b/w 6 & 7 ft BGS

1300 drill @ PSP-23, well set @

7 ft BGS, 5 ft screen

Late Entry, team 2 (soil gas) = START Shaver + Falkner  
1107 collection @ PSP-21, ~~etc.~~ see field sheet for details

1202 collection for soil gas for PSP15

1249 collection for soil gas for PSP19

Groundwater sample collection team 2

START Shaver and Kelley

1310 team 2 @ PSP-24 for groundwater  
see field sheet for details

Duplicate collected

1400 team 2 to PSP-17, see field sheet  
for groundwater collection details

~~1440~~ team 2 to PSP11, see field sheet  
for details

1500 team 2 to PSP-13, see field sheet  
for details.

Scale: 1 square =

Rite in the Rain



9/12/19  
 Late entry by team 1 for soil gas @  
 collection. START Snyder & Falkner Falkner  
 see field sheets for details  
 PSP 14 collection @ 1329  
 PSP 24 collection @ 1428  
 PSP 20 collection @ 1523

1600 START Kelley and Falkner to  
 process samples, START Shaver &  
 Snyder to continue soil gas collection  
 PSP 1-16 collected at 1629  
 PSP-10 collected @ 1721  
 PSP-11 collected @ 1811  
 see field sheets for details

Late entry: Drillers finished and are off-site

9/12/19

9/13/19

0630 START onsite, H&S meeting  
 Soil gas collection; see field sheets for  
 details:

sample	collection start time
PSP 28	0702
PSP 27	0747
PSP 13	0822 & split
PSP 24	0950
PSP 12	1032

9/13/19



10 12/3/2019

0730- START Kelley, Snyder and Falkner meet at site.

Note: Today's weather: 49° and partly cloudy. 5% chance precipitation.

Wind 3-10 mph W.

0745- START set up ambient air, crawl space air, and indoor air canisters.

0830- Deployed IA, AA, and CS air canisters at PSP20.

<sup>0907</sup>  
~~0900~~ - START collect surface water samples at PSP32.

0920- START collect surface water samples at PSP31.

1020- Deployed AA, IA, and CS air canisters at PSP14.

1025- Deployed AA air canister at PSP22.

1100- Deployed AA and CS air canisters and CS air canisters at PSP25 and PSP30, respectively.

1330- Deployed CS air canister at PSP26.

1400- Characterize creek directly below Patterson Street. Used tracer dye to

Scale: 1 square = \_\_\_\_\_  
Amber Falkner 12-3-2019  
C-7

12/3/2019

11

confirm sewer pipe flows into same creek samples were collected from.

Tracer dye confirmed sewer pipe found between Patterson Street and Immanuel Road is connected to sample stream.

1415- START Kelley, Snyder, and Falkner off-site.

1830- START Kelley, Snyder, and Falkner on-site.

1840- Deployed AA and CS at PSP29.

1845- START Kelley, Snyder, and Falkner off-site.

Note- Could not deploy IA air canister at PSP29 due to homeowner not home.

Amber Falkner  
12-3-2019

Scale: 1 square = \_\_\_\_\_

Rite in the Rain

12 12/4/19

0800 START arrives at 1402 Swan St  
to pick up 1A, CS, & AA PSP20  
canisters.

1000 START arrives at 2822 Camborne  
St to pick up PSP14-AA, CS, 1A  
Canisters. START also picks up  
PSP22-AA Canister.

1100 START arrives at 2841 Camborne  
St to pick up PSP25-CS & AA canisters.  
START also picks up PSP30-CS from  
2834 Camborne St.

1300 START arrives at 2836 Camborne St  
to pick up PSP26-CS & AA  
Canisters.

~~1415~~ 1415 START arrives at 2832 Camborne  
St to pick up PSP29-CS & AA  
Canisters.

1840- START demobilizes from the  
site.

Quintely 12/4/19

Scale: 1 square =

C-8

13

Scale: 1 square =

Rite in the Rain





**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
GROUNDWATER SAMPLE COLLECTION FORM**

**Station ID:** PSP10 **Sample Date:** Sep 11, 2019

**Sample ID:** PSP10-GW **Well No.:** \_\_\_\_\_

**Sample Time:** 16:48 **Collected by:** Leslie Shaver

**Quality Control:**

☐ MS/MSD ☐ Duplicate Duplicate ID: \_\_\_\_\_ Time: \_\_\_\_\_

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Trace Chlorinated VOCs	3	40-mL vials with HCl

**Type of Well:** Temp (PVC)  
**Total Depth of Well:** 10.12 bgs  
**Screen Interval:** 5 - 10 ft  
**Depth to Water:** 8.41 ft  
**Water Column:** 1.71 ft  
**Well Diameter:** 1 in

1-inch well = water column (ft) x 0.041 gal/ft  
2-inch well = water column (ft) x 0.163 gal/ft  
3-inch well = water column (ft) x 0.367 gal/ft  
4-inch well = water column (ft) x 0.653 gal/ft

Water Quality Parameter Measurements			
Parameter	1	2	3
Time (24 hr)			
Water Level (ft)			
pH (std. Units)	6.28		
Sp. Conductivity (uS/cm)	0.426		
Temperature (°F)	30.44		
Turbidity (NTU)			

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
GROUNDWATER SAMPLE COLLECTION FORM**

**Station ID:** PSP11 **Sample Date:** Sep 12, 2019

**Sample ID:** PSP11-GW **Well No.:** \_\_\_\_\_

**Sample Time:** 14:50 **Collected by:** Leslie Shaver

**Quality Control:**

☐ MS/MSD ☐ Duplicate Duplicate ID: \_\_\_\_\_ Time: \_\_\_\_\_

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Trace Chlorinated VOCs	3	40-mL vials with HCl

**Type of Well:** Temp (PVC)  
**Total Depth of Well:** 6.64 bgs  
**Screen Interval:** 5 - 10 ft  
**Depth to Water:** 5.12 ft  
**Water Column:** 1.52 ft  
**Well Diameter:** 1 in

1-inch well = water column (ft) x 0.041 gal/ft  
2-inch well = water column (ft) x 0.163 gal/ft  
3-inch well = water column (ft) x 0.367 gal/ft  
4-inch well = water column (ft) x 0.653 gal/ft

Water Quality Parameter Measurements			
Parameter	1	2	3
Time (24 hr)			
Water Level (ft)			
pH (std. Units)			
Sp. Conductivity (uS/cm)			
Temperature (°F)			
Turbidity (NTU)			

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
GROUNDWATER SAMPLE COLLECTION FORM**

**Station ID:** PSP12 **Sample Date:** Sep 11, 2019

**Sample ID:** PSP12-GW **Well No.:** \_\_\_\_\_

**Sample Time:** 16:21 **Collected by:** Leslie Shaver

**Quality Control:**

☐ MS/MSD ☐ Duplicate Duplicate ID: \_\_\_\_\_ Time: \_\_\_\_\_

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Trace Chlorinated VOCs	3	40-mL vials with HCl

**Type of Well:** Temp (PVC)  
**Total Depth of Well:** 9.86 bgs  
**Screen Interval:** 5 - 10 ft  
**Depth to Water:** 8.51 ft  
**Water Column:** 1.35 ft  
**Well Diameter:** 1 in

1-inch well = water column (ft) x 0.041 gal/ft  
2-inch well = water column (ft) x 0.163 gal/ft  
3-inch well = water column (ft) x 0.367 gal/ft  
4-inch well = water column (ft) x 0.653 gal/ft

Water Quality Parameter Measurements			
Parameter	1	2	3
Time (24 hr)	16:12		
Water Level (ft)			
pH (std. Units)	5.84		
Sp. Conductivity (uS/cm)	0.272		
Temperature (°F)	28.74		
Turbidity (NTU)			

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
GROUNDWATER SAMPLE COLLECTION FORM**

**Station ID:** PSP13 **Sample Date:** Sep 12, 2019

**Sample ID:** PSP13-GW **Well No.:** \_\_\_\_\_

**Sample Time:** 15:15 **Collected by:** Leslie Shaver

**Quality Control:**

☐ MS/MSD ☐ Duplicate Duplicate ID: \_\_\_\_\_ Time: \_\_\_\_\_

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Trace Chlorinated VOCs	3	40-mL vials with HCl

**Type of Well:** Temp (PVC)  
**Total Depth of Well:** 20.08 bgs  
**Screen Interval:** 5 - 10 ft  
**Depth to Water:** 16.96 ft  
**Water Column:** 3.12 ft  
**Well Diameter:** 1 in

1-inch well = water column (ft) x 0.041 gal/ft  
2-inch well = water column (ft) x 0.163 gal/ft  
3-inch well = water column (ft) x 0.367 gal/ft  
4-inch well = water column (ft) x 0.653 gal/ft

Water Quality Parameter Measurements			
Parameter	1	2	3
Time (24 hr)	15:21		
Water Level (ft)			
pH (std. Units)	7		
Sp. Conductivity (uS/cm)	0.288		
Temperature (°F)	28.54		
Turbidity (NTU)			

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
GROUNDWATER SAMPLE COLLECTION FORM**

**Station ID:** PSP17 **Sample Date:** Sep 12, 2019

**Sample ID:** PSP17-GW **Well No.:** \_\_\_\_\_

**Sample Time:** 14:15 **Collected by:** Leslie Shaver

**Quality Control:**

☐ MS/MSD ☐ Duplicate Duplicate ID: \_\_\_\_\_ Time: \_\_\_\_\_

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Trace Chlorinated VOCs	3	40-mL vials with HCl

**Type of Well:** Temp (PVC)  
**Total Depth of Well:** 13.56 bgs  
**Screen Interval:** 5 - 10 ft  
**Depth to Water:** 6.19 ft  
**Water Column:** 7.37 ft  
**Well Diameter:** 1 in

1-inch well = water column (ft) x 0.041 gal/ft  
2-inch well = water column (ft) x 0.163 gal/ft  
3-inch well = water column (ft) x 0.367 gal/ft  
4-inch well = water column (ft) x 0.653 gal/ft

Water Quality Parameter Measurements			
Parameter	1	2	3
Time (24 hr)	14:18		
Water Level (ft)			
pH (std. Units)	6.99		
Sp. Conductivity (uS/cm)	0.373		
Temperature (°F)	28.5		
Turbidity (NTU)			

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
GROUNDWATER SAMPLE COLLECTION FORM**

**Station ID:** PSP24 **Sample Date:** Sep 12, 2019

**Sample ID:** PSP24-GW **Well No.:** \_\_\_\_\_

**Sample Time:** 13:35 **Collected by:** Leslie Shaver

**Quality Control:**

☐ MS/MSD ☒ Duplicate Duplicate ID: PSP24-GW-DUP Time: 13:37

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Trace Chlorinated VOCs	6	40-mL vials with HCl

**Type of Well:** Temp (PVC)  
**Total Depth of Well:** 6.3 bgs  
**Screen Interval:** 5 - 10 ft  
**Depth to Water:** 4.9 ft  
**Water Column:** 1.4 ft  
**Well Diameter:** 1 in

1-inch well = water column (ft) x 0.041 gal/ft  
2-inch well = water column (ft) x 0.163 gal/ft  
3-inch well = water column (ft) x 0.367 gal/ft  
4-inch well = water column (ft) x 0.653 gal/ft

Water Quality Parameter Measurements			
Parameter	1	2	3
Time (24 hr)			
Water Level (ft)			
pH (std. Units)			
Sp. Conductivity (uS/cm)			
Temperature (°F)			
Turbidity (NTU)			

**Comments:**





**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
GROUNDWATER SAMPLE COLLECTION FORM**

**Station ID:** PSP25 **Sample Date:** Sep 12, 2019

**Sample ID:** PSP25-GW **Well No.:** \_\_\_\_\_

**Sample Time:** 09:35 **Collected by:** Amber Falkner

**Quality Control:**

☒ MS/MSD ☐ Duplicate Duplicate ID: \_\_\_\_\_ Time: \_\_\_\_\_

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Trace Chlorinated VOCs	9	40-mL vials with HCl

**Type of Well:** Temp (PVC)  
**Total Depth of Well:** 10.12 bgs  
**Screen Interval:** 5 - 10 ft  
**Depth to Water:** 5.59 ft  
**Water Column:** 4.53 ft  
**Well Diameter:** 1 in

1-inch well = water column (ft) x 0.041 gal/ft  
2-inch well = water column (ft) x 0.163 gal/ft  
3-inch well = water column (ft) x 0.367 gal/ft  
4-inch well = water column (ft) x 0.653 gal/ft

Water Quality Parameter Measurements			
Parameter	1	2	3
Time (24 hr)			
Water Level (ft)			
pH (std. Units)	5.11		
Sp. Conductivity (uS/cm)	0.12		
Temperature (°F)	27.04		
Turbidity (NTU)			

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SURFACE WATER SAMPLE COLLECTION FORM**

**Station ID:** PSP01 **Sample Date:** Sep 10, 2019

**Depth Interval:** NA **Sampler:** Leslie Shaver

**Sample ID:** PSP01-SW **Sample Time:** 09:43

**Quality Control:** ☐ MS/MSD ☒ Duplicate Time: 09:45  
ID: PSP01-SW-DUP

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Trace Chlorinated VOCs	6	40-mL vials with HCl

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SURFACE WATER SAMPLE COLLECTION FORM**

**Station ID:** PSP02 **Sample Date:** Sep 10, 2019

**Depth Interval:** NA **Sampler:** Leslie Shaver

**Sample ID:** PSP02-SW **Sample Time:** 09:26

**Quality Control:** ☐ MS/MSD ☐ Duplicate Time: \_\_\_\_\_  
ID: \_\_\_\_\_

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Trace Chlorinated VOCs	3	40-mL vials with HCl

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SURFACE WATER SAMPLE COLLECTION FORM**

**Station ID:** PSP03 **Sample Date:** Sep 10, 2019

**Depth Interval:** NA **Sampler:** Amber Falkner

**Sample ID:** PSP03-SW **Sample Time:** 09:18

**Quality Control:** ☐ MS/MSD ☐ Duplicate Time: \_\_\_\_\_  
ID: \_\_\_\_\_

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Trace Chlorinated VOCs	3	40-mL vials with HCl

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SURFACE WATER SAMPLE COLLECTION FORM**

**Station ID:** PSP04 **Sample Date:** Sep 10, 2019

**Depth Interval:** NA **Sampler:** Leslie Shaver

**Sample ID:** PSP04-SW **Sample Time:** 09:10

**Quality Control:** ☐ MS/MSD ☐ Duplicate Time: \_\_\_\_\_  
ID: \_\_\_\_\_

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Trace Chlorinated VOCs	3	40-mL vials with HCl

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SURFACE WATER SAMPLE COLLECTION FORM**

**Station ID:** PSP05 **Sample Date:** Sep 10, 2019

**Depth Interval:** NA **Sampler:** John Snyder

**Sample ID:** PSP05-SW **Sample Time:** 10:40

**Quality Control:** ☐ MS/MSD ☐ Duplicate Time: \_\_\_\_\_  
ID: \_\_\_\_\_

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Trace Chlorinated VOCs	3	40-mL vials with HCl

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SURFACE WATER SAMPLE COLLECTION FORM**

**Station ID:** PSP06 **Sample Date:** Sep 10, 2019

**Depth Interval:** NA **Sampler:** Amber Falkner

**Sample ID:** PSP06-SW **Sample Time:** 10:53

**Quality Control:** ☐ MS/MSD ☐ Duplicate Time: \_\_\_\_\_  
ID: \_\_\_\_\_

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Trace Chlorinated VOCs	3	40-mL vials with HCl

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SURFACE WATER SAMPLE COLLECTION FORM**

**Station ID:** PSP07 **Sample Date:** Sep 10, 2019

**Depth Interval:** NA **Sampler:** John Snyder

**Sample ID:** PSP07-SW **Sample Time:** 11:00

**Quality Control:** ☐ MS/MSD ☐ Duplicate Time: \_\_\_\_\_  
ID: \_\_\_\_\_

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Trace Chlorinated VOCs	3	40-mL vials with HCl

**Comments:**





**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SURFACE WATER SAMPLE COLLECTION FORM**

**Station ID:** PSP08 **Sample Date:** Sep 10, 2019

**Depth Interval:** NA **Sampler:** Amber Falkner

**Sample ID:** PSP08-SW **Sample Time:** 09:00

**Quality Control:** ☐ MS/MSD ☐ Duplicate Time: \_\_\_\_\_  
ID: \_\_\_\_\_

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Trace Chlorinated VOCs	3	40-mL vials with HCl

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SURFACE WATER SAMPLE COLLECTION FORM**

**Station ID:** PSP09 **Sample Date:** Sep 10, 2019

**Depth Interval:** NA **Sampler:** Leslie Shaver

**Sample ID:** PSP09-SW **Sample Time:** 08:41

**Quality Control:** ☒ MS/MSD ☐ Duplicate Time: \_\_\_\_\_  
ID: \_\_\_\_\_

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Trace Chlorinated VOCs	9	40-mL vials with HCl

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SURFACE WATER SAMPLE COLLECTION FORM**

**Station ID:** PSP22 **Sample Date:** Sep 10, 2019

**Depth Interval:** NA **Sampler:** Leslie Shaver

**Sample ID:** PSP22-SEEP **Sample Time:** 11:12

**Quality Control:** ☐ MS/MSD ☐ Duplicate Time: \_\_\_\_\_  
ID: \_\_\_\_\_

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Trace Chlorinated VOCs	3	40-mL vials with HCl

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SURFACE SOIL SAMPLE COLLECTION FORM**

**Station ID:** PSP10 **Sample Date:** Sep 11, 2019

**Latitude:** 36.05458 **Longitude:** -79.84054

**Sample ID:** PSP10-SF **Sampler:** Leslie Shaver

**Depth Interval:** 0-6 inches **Sample Time:** 11:55

**Quality Control:**

☐ MS/MSD ☐ Duplicate Sample ID: \_\_\_\_\_ Time: \_\_\_\_\_

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Chlorinated VOCs	1	Terracore Kit (Three 40-mL glass vials and one 2-oz glass jar)

**Physical Description and Observations:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SURFACE SOIL SAMPLE COLLECTION FORM**

**Station ID:** PSP11 **Sample Date:** Sep 11, 2019

**Latitude:** 36.05429 **Longitude:** -79.84012

**Sample ID:** PSP11-SF **Sampler:** Leslie Shaver

**Depth Interval:** 0-6 inches **Sample Time:** 11:35

**Quality Control:**

☐ MS/MSD ☒ Duplicate Sample ID: PSP11-SF-DUP Time: 11:40

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Chlorinated VOCs	2	Terracore Kits (Three 40-mL glass vials and one 2-oz glass jar)

**Physical Description and Observations:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SURFACE SOIL SAMPLE COLLECTION FORM**

**Station ID:** PSP12 **Sample Date:** Sep 11, 2019

**Latitude:** 36.0539 **Longitude:** -79.84002

**Sample ID:** PSP12-SF **Sampler:** Leslie Shaver

**Depth Interval:** 0-6 inches **Sample Time:** 10:55

**Quality Control:**

☐ MS/MSD ☐ Duplicate Sample ID: \_\_\_\_\_ Time: \_\_\_\_\_

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Chlorinated VOCs	1	Terracore Kit (Three 40-mL glass vials and one 2-oz glass jar)

**Physical Description and Observations:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SURFACE SOIL SAMPLE COLLECTION FORM**

**Station ID:** PSP13 **Sample Date:** Sep 11, 2019

**Latitude:** 36.05357 **Longitude:** -79.83951

**Sample ID:** PSP13-SS- **Sampler:** Leslie Shaver

**Depth Interval:** 0-1 foot **Sample Time:** 09:30

**Quality Control:**

☒ MS/MSD ☐ Duplicate Sample ID: \_\_\_\_\_ Time: \_\_\_\_\_

	Analysis	No.	Container
<input checked="" type="checkbox"/>	Chlorinated VOCs	3	Terracore Kits (Three 40-mL glass vials and one 2-oz glass jar)

**Physical Description and Observations:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SOIL GAS SAMPLE COLLECTION FORM**

**Station ID:** PSP10 **Sample ID:** PSP10-SG

**Latitude:** 36.05458 **Longitude:** -79.84054

**Sampler:** John Snyder

**Implant Install Date:** Sep 11, 2019 **Tubing Type:** Teflon

**Total Depth:** 10 feet **Screened Depth:** 1.5-2 feet

**Sand/Glass Beads:** 1-2 feet **Bentonite:** 0-1, 2-10 feet

**Leak Test?** Yes **Pass/Fail?** Pass

**Test Time/Date:** 17:15 / Sep 12, 2019 **Tracer Gas:** Helium

**Gas Detector:** Radiodetector **Pump Type:** Syringe

**Shroud Conc.:** 70% **Implant Conc.:** 0 ppm

**Container ID:** 14674 **Container:** 6L Canister

**Regulator ID:** SGC-54 **Setting:** 200 mL/min

**Split Sample ID:** \_\_\_\_\_ **Split Container ID:** \_\_\_\_\_

START		END	
<b>Date:</b>	Sep 12, 2019	<b>Date:</b>	Sep 12, 2019
<b>Time:</b>	17:21	<b>Time:</b>	17:52
<b>Pressure:</b>	-30	<b>Pressure:</b>	-3

**Comments:**





**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SOIL GAS SAMPLE COLLECTION FORM**

**Station ID:** PSP11 **Sample ID:** PSP11-SG

**Latitude:** 36.05429 **Longitude:** -79.84011

**Sampler:** John Snyder

**Implant Install Date:** Sep 11, 2019 **Tubing Type:** Teflon

**Total Depth:** 15 feet **Screened Depth:** 3.5-4 feet

**Sand/Glass Beads:** 3-4.5 feet **Bentonite:** 0-, 4.5-15 feet

**Leak Test?** Yes **Pass/Fail?** Pass

**Test Time/Date:** 18:02 / Sep 11, 2019 **Tracer Gas:** Helium

**Gas Detector:** Radiodetector **Pump Type:** Syringe

**Shroud Conc.:** 47% **Implant Conc.:** 250 ppm

**Container ID:** 4017 **Container:** 6L Canister

**Regulator ID:** SGC-35 **Setting:** 200 mL/min

**Split Sample ID:** \_\_\_\_\_ **Split Container ID:** \_\_\_\_\_

START		END	
<b>Date:</b>	Sep 12, 2019	<b>Date:</b>	Sep 12, 2019
<b>Time:</b>	18:11	<b>Time:</b>	18:38
<b>Pressure:</b>	-30	<b>Pressure:</b>	-3

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SOIL GAS SAMPLE COLLECTION FORM**

**Station ID:** PSP12 **Sample ID:** PSP12-SG

**Latitude:** 36.0539 **Longitude:** -79.84002

**Sampler:** John Snyder

**Implant Install Date:** Sep 12, 2019 **Tubing Type:** Teflon

**Total Depth:** 10 feet **Screened Depth:** 2.5-3 feet

**Sand/Glass Beads:** 2-3.5 feet **Bentonite:** 0-2, 3.5-10 feet

**Leak Test?** Yes **Pass/Fail?** Pass

**Test Time/Date:** 10:25 / Sep 13, 2019 **Tracer Gas:** Helium

**Gas Detector:** Radiodetector **Pump Type:** Syringe

**Shroud Conc.:** 94% **Implant Conc.:** 0 ppm

**Container ID:** 3910 **Container:** 6L Canister

**Regulator ID:** SGC-63 **Setting:** 200 mL/min

**Split Sample ID:** \_\_\_\_\_ **Split Container ID:** \_\_\_\_\_

START		END	
<b>Date:</b>	Sep 13, 2019	<b>Date:</b>	Sep 13, 2019
<b>Time:</b>	10:32	<b>Time:</b>	11:00
<b>Pressure:</b>	-30	<b>Pressure:</b>	-2

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SOIL GAS SAMPLE COLLECTION FORM**

**Station ID:** PSP13 **Sample ID:** PSP13-SG

**Latitude:** 36.05357 **Longitude:** -79.83951

**Sampler:** John Snyder

**Implant Install Date:** Sep 12, 2019 **Tubing Type:** Teflon

**Total Depth:** 20 feet **Screened Depth:** 5.5-6.0 feet

**Sand/Glass Beads:** 5-6.5 feet **Bentonite:** 0-5, 6.5-20 feet

**Leak Test?** Yes **Pass/Fail?** Pass

**Test Time/Date:** 08:23 / Sep 13, 2019 **Tracer Gas:** Helium

**Gas Detector:** Radiodetector **Pump Type:** Syringe

**Shroud Conc.:** 97% **Implant Conc.:** 0 ppm

**Container ID:** 20982 **Container:** 6L Canister

**Regulator ID:** SGC-58 **Setting:** 200 mL/min

**Split Sample ID:** PSP13-SG-SPLIT **Split Container ID:** 4554

START		END	
<b>Date:</b>	Sep 13, 2019	<b>Date:</b>	Sep 13, 2019
<b>Time:</b>	08:22	<b>Time:</b>	09:30
<b>Pressure:</b>	-29	<b>Pressure:</b>	-4

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SOIL GAS SAMPLE COLLECTION FORM**

**Station ID:** PSP14 **Sample ID:** PSP14-SG

**Latitude:** 36.05531 **Longitude:** -79.84011

**Sampler:** John Snyder

**Implant Install Date:** Sep 12, 2019 **Tubing Type:** Teflon

**Total Depth:** 7.5 feet **Screened Depth:** 7-7.5 feet

**Sand/Glass Beads:** 6-7.5 feet **Bentonite:** 0-6 feet

**Leak Test?** Yes **Pass/Fail?** Pass

**Test Time/Date:** 13:20 / Sep 12, 2019 **Tracer Gas:** Helium

**Gas Detector:** Radiodetector **Pump Type:** Syringe

**Shroud Conc.:** 80% **Implant Conc.:** 1.8%

**Container ID:** 2785 **Container:** 6L Canister

**Regulator ID:** SGC-46 **Setting:** 200 mL/min

**Split Sample ID:** \_\_\_\_\_ **Split Container ID:** \_\_\_\_\_

START		END	
<b>Date:</b>	Sep 12, 2019	<b>Date:</b>	Sep 12, 2019
<b>Time:</b>	13:29	<b>Time:</b>	13:56
<b>Pressure:</b>	-28	<b>Pressure:</b>	-2

**Comments:**





**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SOIL GAS SAMPLE COLLECTION FORM**

**Station ID:** PSP15 **Sample ID:** PSP15-SG

**Latitude:** 36.05497 **Longitude:** -79.83878

**Sampler:** John Snyder

**Implant Install Date:** Sep 12, 2019 **Tubing Type:** Teflon

**Total Depth:** 10 feet **Screened Depth:** 6.5-7 feet

**Sand/Glass Beads:** 6-7.5 feet **Bentonite:** 7.5-10, 0-6 feet

**Leak Test?** Yes **Pass/Fail?** Pass

**Test Time/Date:** 11:55 / Sep 12, 2019 **Tracer Gas:** Helium

**Gas Detector:** Radiodetector **Pump Type:** Syringe

**Shroud Conc.:** 95% **Implant Conc.:** 2100 ppm

**Container ID:** 27825 **Container:** 6L Canister

**Regulator ID:** SGC-51 **Setting:** 200 mL/min

**Split Sample ID:** \_\_\_\_\_ **Split Container ID:** \_\_\_\_\_

START		END	
<b>Date:</b>	Sep 12, 2019	<b>Date:</b>	Sep 12, 2019
<b>Time:</b>	12:04	<b>Time:</b>	12:28
<b>Pressure:</b>	-30	<b>Pressure:</b>	-4

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SOIL GAS SAMPLE COLLECTION FORM**

**Station ID:** PSP16 **Sample ID:** PSP16-SG

**Latitude:** 36.05465 **Longitude:** -79.84152

**Sampler:** John Snyder

**Implant Install Date:** Sep 11, 2019 **Tubing Type:** Teflon

**Total Depth:** 15 feet **Screened Depth:** 14.5-15 feet

**Sand/Glass Beads:** 14-15 feet **Bentonite:** 0-14 feet

**Leak Test?** Yes **Pass/Fail?** Pass

**Test Time/Date:** 16:24 / Sep 12, 2019 **Tracer Gas:** Helium

**Gas Detector:** Radiodetector **Pump Type:** Syringe

**Shroud Conc.:** 38.6% **Implant Conc.:** 1.7%

**Container ID:** 27822 **Container:** 6L Canister

**Regulator ID:** SGC-56 **Setting:** 200 mL/min

**Split Sample ID:** \_\_\_\_\_ **Split Container ID:** \_\_\_\_\_

START		END	
<b>Date:</b>	Sep 12, 2019	<b>Date:</b>	Sep 12, 2019
<b>Time:</b>	16:27	<b>Time:</b>	16:56
<b>Pressure:</b>	-30	<b>Pressure:</b>	-4

**Comments:**



**Sampler:** John Snyder

**Tubing Type:** Teflon

**Screened Depth:** 6.5-7 feet

**Bentonite:** 0-6, 7.5-13.5 feet

### Pass/Fail?

**Tracer Gas:**

**Pump Type:**

**Implant Conc.:**

**Container:**

**Setting:**

Split Container ID:

START		END	
Date:		Date:	
Time:		Time:	
Pressure:		Pressure:	

**Comments:** Could not even purge 60 mL from implant; muddled in; not a viable implant



**Sampler:** John Snyder

**Tubing Type:** Teflon

**Screened Depth:** 8.5-9.0 feet

**Bentonite:** 0-8, 9.5-10 feet

### Pass/Fail?

**Tracer Gas:**

**Pump Type:**

**Implant Conc.:**

**Container:**

**Setting:**

Split Container ID:

START		END	
Date:		Date:	
Time:		Time:	
Pressure:		Pressure:	

**Comments:** Pulled water on implant pull; mud appeared on tubing up to 3' bgs; not a viable location





**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SOIL GAS SAMPLE COLLECTION FORM**

**Station ID:** PSP19 **Sample ID:** PSP19-SG

**Latitude:** 36.05487 **Longitude:** -79.83946

**Sampler:** John Snyder

**Implant Install Date:** Sep 12, 2019 **Tubing Type:** Teflon

**Total Depth:** 10 feet **Screened Depth:** 6.5-7 feet

**Sand/Glass Beads:** 6-7.5 feet **Bentonite:** 7.5-10, 0-6 feet

**Leak Test?** Yes **Pass/Fail?** Pass

**Test Time/Date:** 12:45 / Sep 12, 2019 **Tracer Gas:** Helium

**Gas Detector:** Radiodetector **Pump Type:** Syringe

**Shroud Conc.:** 94% **Implant Conc.:** 0.5%

**Container ID:** 2418 **Container:** 6L Canister

**Regulator ID:** SGC-49 **Setting:** 200 mL/min

**Split Sample ID:** \_\_\_\_\_ **Split Container ID:** \_\_\_\_\_

START		END	
<b>Date:</b>	Sep 12, 2019	<b>Date:</b>	Sep 12, 2019
<b>Time:</b>	12:49	<b>Time:</b>	13:11
<b>Pressure:</b>	-28	<b>Pressure:</b>	-4

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SOIL GAS SAMPLE COLLECTION FORM**

**Station ID:** PSP20 **Sample ID:** PSP20-SG

**Latitude:** 36.05418 **Longitude:** -79.83923

**Sampler:** John Snyder

**Implant Install Date:** Sep 11, 2019 **Tubing Type:** Teflon

**Total Depth:** 10 feet **Screened Depth:** 5.5-6.0 feet

**Sand/Glass Beads:** 5.0-6.5 feet **Bentonite:** 0-5, 6.5-10 feet

**Leak Test?** Yes **Pass/Fail?** Pass

**Test Time/Date:** 15:17 / Sep 12, 2019 **Tracer Gas:** Helium

**Gas Detector:** Radiodetector **Pump Type:** Syringe

**Shroud Conc.:** 96% **Implant Conc.:** 1.8%

**Container ID:** 3588 **Container:** 6L Canister

**Regulator ID:** SGC-55 **Setting:** 200 mL/min

**Split Sample ID:** \_\_\_\_\_ **Split Container ID:** \_\_\_\_\_

START		END	
<b>Date:</b>	Sep 12, 2019	<b>Date:</b>	Sep 12, 2019
<b>Time:</b>	15:23	<b>Time:</b>	15:53
<b>Pressure:</b>	-28	<b>Pressure:</b>	-2

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SOIL GAS SAMPLE COLLECTION FORM**

**Station ID:** PSP21 **Sample ID:** PSP21-SG

**Latitude:** 36.0545 **Longitude:** -79.8384

**Sampler:** John Snyder

**Implant Install Date:** Sep 11, 2019 **Tubing Type:** Teflon

**Total Depth:** 3 feet **Screened Depth:** 2.5-3 feet

**Sand/Glass Beads:** 2-3 feet **Bentonite:** 0-2 feet

**Leak Test?** Yes **Pass/Fail?** Pass

**Test Time/Date:** Sep 11, 2019 **Tracer Gas:** Helium

**Gas Detector:** Radiodetector **Pump Type:** Syringe

**Shroud Conc.:** 98% **Implant Conc.:** 0%

**Container ID:** 571 **Container:** 6L Canister

**Regulator ID:** SGC-48 **Setting:** 30 min

**Split Sample ID:** \_\_\_\_\_ **Split Container ID:** \_\_\_\_\_

START		END	
<b>Date:</b>	Sep 11, 2019	<b>Date:</b>	Sep 11, 2019
<b>Time:</b>	11:07	<b>Time:</b>	11:35
<b>Pressure:</b>	-28	<b>Pressure:</b>	-2

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SOIL GAS SAMPLE COLLECTION FORM**

**Station ID:** PSP24 **Sample ID:** PSP24-SG

**Latitude:** 36.05298 **Longitude:** -79.83845

**Sampler:** John Snyder

**Implant Install Date:** Sep 12, 2019 **Tubing Type:** Teflon

**Total Depth:** 6.5 feet **Screened Depth:** 2.5-3 feet

**Sand/Glass Beads:** 2-3 feet **Bentonite:** 0-2, 3-6.5 feet

**Leak Test?** Yes **Pass/Fail?** Pass

**Test Time/Date:** 09:45 / Sep 13, 2019 **Tracer Gas:** Helium

**Gas Detector:** Radiodetector **Pump Type:** Syringe

**Shroud Conc.:** 98% **Implant Conc.:** 0 ppm

**Container ID:** 4555 **Container:** 6L Canister

**Regulator ID:** SGC-30 **Setting:** 200 mL/min

**Split Sample ID:** \_\_\_\_\_ **Split Container ID:** \_\_\_\_\_

START		END	
<b>Date:</b>	Sep 13, 2019	<b>Date:</b>	Sep 13, 2019
<b>Time:</b>	09:50	<b>Time:</b>	10:16
<b>Pressure:</b>	-28	<b>Pressure:</b>	-4

**Comments:**





**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SOIL GAS SAMPLE COLLECTION FORM**

**Station ID:** PSP25 **Sample ID:** PSP25-SG

**Latitude:** 36.0551 **Longitude:** -79.84169

**Sampler:** John Snyder

**Implant Install Date:** Sep 11, 2019 **Tubing Type:** Teflon

**Total Depth:** 10 feet **Screened Depth:** 1.5-2 feet

**Sand/Glass Beads:** 1-2 feet **Bentonite:** 0-1, 2-10 feet

**Leak Test?** Yes **Pass/Fail?** Pass

**Test Time/Date:** 14:16 / Sep 12, 2019 **Tracer Gas:** Helium

**Gas Detector:** Radiodetector **Pump Type:** Syringe

**Shroud Conc.:** 92.5% **Implant Conc.:** 250 ppm

**Container ID:** 4671 **Container:** 6L Canister

**Regulator ID:** SGC-57 **Setting:** 200 mL/min

**Split Sample ID:** \_\_\_\_\_ **Split Container ID:** \_\_\_\_\_

START		END	
<b>Date:</b>	Sep 12, 2019	<b>Date:</b>	Sep 12, 2019
<b>Time:</b>	14:28	<b>Time:</b>	14:55
<b>Pressure:</b>	-30	<b>Pressure:</b>	-4

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SOIL GAS SAMPLE COLLECTION FORM**

**Station ID:** PSP26 **Sample ID:** PSP26-SG

**Latitude:** 36.05551 **Longitude:** -79.84147

**Sampler:** John Snyder

**Implant Install Date:** Sep 11, 2019 **Tubing Type:** Teflon

**Total Depth:** 8 feet **Screened Depth:** 7.5-8 feet

**Sand/Glass Beads:** 7-8 feet **Bentonite:** 0-7 feet

**Leak Test?** No **Pass/Fail?**

**Test Time/Date:**  **Tracer Gas:**

**Gas Detector:**  **Pump Type:**

**Shroud Conc.:**  **Implant Conc.:**

**Container ID:**  **Container:**

**Regulator ID:**  **Setting:**

**Split Sample ID:**  **Split Container ID:**

START		END	
<b>Date:</b>		<b>Date:</b>	
<b>Time:</b>		<b>Time:</b>	
<b>Pressure:</b>		<b>Pressure:</b>	

**Comments:** Implant not producing soil gas: non-viable; applied vacuum to implant with syringe; no flow



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SOIL GAS SAMPLE COLLECTION FORM**

**Station ID:** PSP27 **Sample ID:** PSP27-SG

**Latitude:** 36.05375 **Longitude:** -79.84008

**Sampler:** John Snyder

**Implant Install Date:** Sep 12, 2019 **Tubing Type:** Teflon

**Total Depth:** 20 feet **Screened Depth:** 9.5-10 feet

**Sand/Glass Beads:** 9-10.5 feet **Bentonite:** 0-9, 10.5-20 feet

**Leak Test?** Yes **Pass/Fail?** Pass

**Test Time/Date:** 07:40 / Sep 13, 2019 **Tracer Gas:** Helium

**Gas Detector:** Radiodetector **Pump Type:** Syringe

**Shroud Conc.:** 94% **Implant Conc.:** 0 ppm

**Container ID:** 3928 **Container:** 6L Canister

**Regulator ID:** SGC-28 **Setting:** 20 mL/min

**Split Sample ID:** \_\_\_\_\_ **Split Container ID:** \_\_\_\_\_

START		END	
<b>Date:</b>	Sep 13, 2019	<b>Date:</b>	Sep 13, 2019
<b>Time:</b>	07:46	<b>Time:</b>	08:11
<b>Pressure:</b>	-29	<b>Pressure:</b>	-4

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
SOIL GAS SAMPLE COLLECTION FORM**

**Station ID:** PSP28 **Sample ID:** PSP28-SG

**Latitude:** 36.05378 **Longitude:** -79.84123

**Sampler:** John Snyder

**Implant Install Date:** Sep 12, 2019 **Tubing Type:** Teflon

**Total Depth:** 23.5 feet **Screened Depth:** 6.5-7 feet

**Sand/Glass Beads:** 6-7.5 feet **Bentonite:** 0-6, 7.5-23.5 feet

**Leak Test?** Yes **Pass/Fail?** Pass

**Test Time/Date:** 06:55 / Sep 13, 2019 **Tracer Gas:** Helium

**Gas Detector:** Radiodetector **Pump Type:** Syringe

**Shroud Conc.:** 94% **Implant Conc.:** 0 ppm

**Container ID:** 4670 **Container:** 6L Canister

**Regulator ID:** SGC-31 **Setting:** 200 mL/min

**Split Sample ID:** \_\_\_\_\_ **Split Container ID:** \_\_\_\_\_

START		END	
<b>Date:</b>	Sep 13, 2019	<b>Date:</b>	Sep 13, 2019
<b>Time:</b>	07:02	<b>Time:</b>	07:26
<b>Pressure:</b>	-29	<b>Pressure:</b>	-1

**Comments:**



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
INDOOR AIR SAMPLE COLLECTION FORM**

**Station ID:** PSP14 **Sample ID:** PSP14-IA

**Latitude:** 36.05531 **Longitude:** -79.84011

**Container ID:** 27709 **Container:** 6-L Summa

**Regulator ID:** FC-47 **Regulator Setting:** 24hr

START		END	
<b>Date:</b>	Dec 3, 2019	<b>Date:</b>	Dec 4, 2019
<b>Time:</b>	10:17	<b>Time:</b>	10:02
<b>Pressure:</b>	-28	<b>Pressure:</b>	-7

**Sampler:** John Snyder





**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
INDOOR AIR SAMPLE COLLECTION FORM**

**Station ID:** PSP20 **Sample ID:** PSP20-IA

**Latitude:** 36.05417 **Longitude:** -79.83924

**Container ID:** 27713 **Container:** 6-L Summa

**Regulator ID:** FC-30 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Dec 3, 2019	<b>Date:</b>	Dec 4, 2019
<b>Time:</b>	08:34	<b>Time:</b>	08:00
<b>Pressure:</b>	-29	<b>Pressure:</b>	-5

**Sampler:** John Snyder



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
CRAWL SPACE SAMPLE COLLECTION FORM**

**Station ID:** PSP14 **Sample ID:** PSP14-CS

**Latitude:** 36.05532 **Longitude:** -79.84011

**Container ID:** 27827 **Container:** 6-L Summa

**Regulator ID:** FC-41 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Dec 3, 2019	<b>Date:</b>	Dec 4, 2019
<b>Time:</b>	10:20	<b>Time:</b>	10:03
<b>Pressure:</b>	-30	<b>Pressure:</b>	-6.5

**Sampler:** John Snyder



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
CRAWL SPACE SAMPLE COLLECTION FORM**

**Station ID:** PSP20 **Sample ID:** PSP20-CS

**Latitude:** 36.05417 **Longitude:** -79.83924

**Container ID:** 20715 **Container:** 6-L Summa

**Regulator ID:** FC-27 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Dec 3, 2019	<b>Date:</b>	Dec 4, 2019
<b>Time:</b>	08:41	<b>Time:</b>	08:04
<b>Pressure:</b>	-28	<b>Pressure:</b>	-6

**Sampler:** John Snyder



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
CRAWL SPACE SAMPLE COLLECTION FORM**

**Station ID:** PSP25 **Sample ID:** PSP25-CS

**Latitude:** 36.05509 **Longitude:** -79.84169

**Container ID:** 27711 **Container:** 6-L Summa

**Regulator ID:** FC-40 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Dec 3, 2019	<b>Date:</b>	Dec 4, 2019
<b>Time:</b>	11:00	<b>Time:</b>	11:03
<b>Pressure:</b>	-30	<b>Pressure:</b>	-6

**Sampler:** John Snyder



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
CRAWL SPACE SAMPLE COLLECTION FORM**

**Station ID:** PSP26 **Sample ID:** PSP26-CS

**Latitude:** 36.0555 **Longitude:** -79.84147

**Container ID:** 20652 **Container:** 6-L Summa

**Regulator ID:** FC-43 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Dec 3, 2019	<b>Date:</b>	Dec 4, 2019
<b>Time:</b>	13:31	<b>Time:</b>	13:03
<b>Pressure:</b>	-30	<b>Pressure:</b>	-5

**Sampler:** John Snyder





**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
CRAWL SPACE SAMPLE COLLECTION FORM**

**Station ID:** PSP29 **Sample ID:** PSP29-CS

**Latitude:** 36.05528 **Longitude:** -79.84113

**Container ID:** 27826 **Container:** 6-L Summa

**Regulator ID:** FC-50 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Dec 3, 2019	<b>Date:</b>	Dec 4, 2019
<b>Time:</b>	18:41	<b>Time:</b>	18:20
<b>Pressure:</b>	-30	<b>Pressure:</b>	-5

**Sampler:** John Snyder



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
CRAWL SPACE SAMPLE COLLECTION FORM**

**Station ID:** PSP30 **Sample ID:** PSP30-CS

**Latitude:** 36.05529 **Longitude:** -79.84129

**Container ID:** 20653 **Container:** 6-L Summa

**Regulator ID:** FC-48 **Regulator Setting:** 24hr

START		END	
<b>Date:</b>	Dec 3, 2019	<b>Date:</b>	Dec 4, 2019
<b>Time:</b>	11:06	<b>Time:</b>	11:05
<b>Pressure:</b>	-30	<b>Pressure:</b>	-5

**Sampler:** John Snyder



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
AMBIENT AIR SAMPLE COLLECTION FORM**

**Station ID:** PSP10 **Sample ID:** PSP10-AA

**Latitude:** 36.05458 **Longitude:** -79.84054

**Container ID:** 14675 **Container:** 6-L Summa

**Regulator ID:** FC-48 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Sep 10, 2019	<b>Date:</b>	Sep 11, 2019
<b>Time:</b>	13:44	<b>Time:</b>	14:42
<b>Pressure:</b>	-28	<b>Pressure:</b>	-5

**Sampler:** Leslie Shaver



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
AMBIENT AIR SAMPLE COLLECTION FORM**

**Station ID:** PSP10 **Sample ID:** PSP10-AA-DUP

**Latitude:** 36.05458 **Longitude:** -79.84054

**Container ID:** 5677 **Container:** 6-L Summa

**Regulator ID:** FC-50 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Sep 10, 2019	<b>Date:</b>	Sep 11, 2019
<b>Time:</b>	13:43	<b>Time:</b>	14:42
<b>Pressure:</b>	-30	<b>Pressure:</b>	-5

**Sampler:** Leslie Shaver



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
AMBIENT AIR SAMPLE COLLECTION FORM**

**Station ID:** PSP11 **Sample ID:** PSP11-AA

**Latitude:** 36.05429 **Longitude:** -79.84011

**Container ID:** 2771 **Container:** 6-L Summa

**Regulator ID:** FC-49 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Sep 9, 2019	<b>Date:</b>	Sep 10, 2019
<b>Time:</b>	14:16	<b>Time:</b>	14:06
<b>Pressure:</b>	-30	<b>Pressure:</b>	-5

**Sampler:** Leslie Shaver





**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
AMBIENT AIR SAMPLE COLLECTION FORM**

**Station ID:** PSP12 **Sample ID:** PSP12-AA

**Latitude:** 36.0539 **Longitude:** -79.84002

**Container ID:** 20970 **Container:** 6-L Summa

**Regulator ID:** FC-46 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Sep 9, 2019	<b>Date:</b>	Sep 10, 2019
<b>Time:</b>	14:23	<b>Time:</b>	15:37
<b>Pressure:</b>	-35	<b>Pressure:</b>	-6

**Sampler:** Leslie Shaver



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
AMBIENT AIR SAMPLE COLLECTION FORM**

**Station ID:** PSP13 **Sample ID:** PSP13-AA

**Latitude:** 36.05357 **Longitude:** -79.83951

**Container ID:** 2782 **Container:** 6-L Summa

**Regulator ID:** FC-41 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Sep 9, 2019	<b>Date:</b>	Sep 10, 2019
<b>Time:</b>	14:38	<b>Time:</b>	15:01
<b>Pressure:</b>	-30	<b>Pressure:</b>	-5

**Sampler:** Leslie Shaver



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
AMBIENT AIR SAMPLE COLLECTION FORM**

**Station ID:** PSP14 **Sample ID:** PSP14-AA

**Latitude:** 36.05532 **Longitude:** -79.84012

**Container ID:** 27714 **Container:** 6-L Summa

**Regulator ID:** FC-38 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Dec 3, 2019	<b>Date:</b>	Dec 4, 2019
<b>Time:</b>	10:22	<b>Time:</b>	10:03
<b>Pressure:</b>	-30	<b>Pressure:</b>	-8

**Sampler:** John Snyder



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
AMBIENT AIR SAMPLE COLLECTION FORM**

**Station ID:** PSP16 **Sample ID:** PSP16-AA

**Latitude:** 36.05465 **Longitude:** -79.84152

**Container ID:** 27879 **Container:** 6-L Summa

**Regulator ID:** FC-38 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Sep 9, 2019	<b>Date:</b>	Sep 10, 2019
<b>Time:</b>	14:30	<b>Time:</b>	15:36
<b>Pressure:</b>	-35	<b>Pressure:</b>	-7

**Sampler:** Leslie Shaver



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
AMBIENT AIR SAMPLE COLLECTION FORM**

**Station ID:** PSP20 **Sample ID:** PSP20-AA

**Latitude:** 36.05416 **Longitude:** -79.83924

**Container ID:** 27715 **Container:** 6-L Summa

**Regulator ID:** FC-22 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Dec 3, 2019	<b>Date:</b>	Dec 4, 2019
<b>Time:</b>	08:43	<b>Time:</b>	08:04
<b>Pressure:</b>	-28	<b>Pressure:</b>	-4

**Sampler:** John Snyder





**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
AMBIENT AIR SAMPLE COLLECTION FORM**

**Station ID:** PSP20 **Sample ID:** PSP20-AA-DUP

**Latitude:** 36.05417 **Longitude:** -79.83924

**Container ID:** 27816 **Container:** 6-L Summa

**Regulator ID:** FC-13 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Dec 3, 2019	<b>Date:</b>	Dec 4, 2019
<b>Time:</b>	08:43	<b>Time:</b>	08:04
<b>Pressure:</b>	-29	<b>Pressure:</b>	-7

**Sampler:** John Snyder



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
AMBIENT AIR SAMPLE COLLECTION FORM**

**Station ID:** PSP21 **Sample ID:** PSP21-AA

**Latitude:** 36.0545 **Longitude:** -79.8384

**Container ID:** 5920 **Container:** 6-L Summa

**Regulator ID:** FC-43 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Sep 9, 2019	<b>Date:</b>	Sep 10, 2019
<b>Time:</b>	14:46	<b>Time:</b>	14:13
<b>Pressure:</b>	-30	<b>Pressure:</b>	-5

**Sampler:** Leslie Shaver



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
AMBIENT AIR SAMPLE COLLECTION FORM**

**Station ID:** PSP22 **Sample ID:** PSP22-AA

**Latitude:** 36.05548 **Longitude:** -79.84038

**Container ID:** 27817 **Container:** 6-L Summa

**Regulator ID:** FC-45 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Dec 3, 2019	<b>Date:</b>	Dec 4, 2019
<b>Time:</b>	10:25	<b>Time:</b>	10:05
<b>Pressure:</b>	-30	<b>Pressure:</b>	-6

**Sampler:** John Snyder



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
AMBIENT AIR SAMPLE COLLECTION FORM**

**Station ID:** PSP24 **Sample ID:** PSP24-AA

**Latitude:** 36.05298 **Longitude:** -79.83845

**Container ID:** 20979 **Container:** 6-L Summa

**Regulator ID:** FC-45 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Sep 9, 2019	<b>Date:</b>	Sep 10, 2019
<b>Time:</b>	13:52	<b>Time:</b>	15:30
<b>Pressure:</b>	-35	<b>Pressure:</b>	-7

**Sampler:** Leslie Shaver



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
AMBIENT AIR SAMPLE COLLECTION FORM**

**Station ID:** PSP25 **Sample ID:** PSP25-AA

**Latitude:** 36.05509 **Longitude:** -79.8417

**Container ID:** 27710 **Container:** 6-L Summa

**Regulator ID:** FC-42 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Dec 3, 2019	<b>Date:</b>	Dec 4, 2019
<b>Time:</b>	11:01	<b>Time:</b>	11:04
<b>Pressure:</b>	-30	<b>Pressure:</b>	-3

**Sampler:** John Snyder



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
AMBIENT AIR SAMPLE COLLECTION FORM**

**Station ID:** PSP26 **Sample ID:** PSP26-AA

**Latitude:** 36.05551 **Longitude:** -79.84147

**Container ID:** 2781 **Container:** 6-L Summa

**Regulator ID:** FC-40 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Sep 10, 2019	<b>Date:</b>	Sep 11, 2019
<b>Time:</b>	13:50	<b>Time:</b>	14:37
<b>Pressure:</b>	-28	<b>Pressure:</b>	-6

**Sampler:** Leslie Shaver





**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
AMBIENT AIR SAMPLE COLLECTION FORM**

**Station ID:** PSP28 **Sample ID:** PSP28-AA

**Latitude:** 36.05378 **Longitude:** -79.84123

**Container ID:** 14677 **Container:** 6-L Summa

**Regulator ID:** FC-47 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Sep 9, 2019	<b>Date:</b>	Sep 10, 2019
<b>Time:</b>	13:58	<b>Time:</b>	15:03
<b>Pressure:</b>	-30	<b>Pressure:</b>	-6

**Sampler:** Leslie Shaver



**PATTERSON STREET SOLVENT PLUME SI  
GREENSBORO, GUILFORD COUNTY, NORTH CAROLINA  
AMBIENT AIR SAMPLE COLLECTION FORM**

**Station ID:** PSP29 **Sample ID:** PSP29-AA

**Latitude:** 36.05528 **Longitude:** -79.84114

**Container ID:** 20980 **Container:** 6-L Summa

**Regulator ID:** FC-19 **Regulator Setting:** 24 hr

START		END	
<b>Date:</b>	Dec 3, 2019	<b>Date:</b>	Dec 4, 2019
<b>Time:</b>	18:42	<b>Time:</b>	18:21
<b>Pressure:</b>	-29	<b>Pressure:</b>	-6

**Sampler:** John Snyder

<b>Boring ID:</b> PSP10	
<b>Monitoring Well ID:</b> PSP10	
<b>Project Number:</b> TT-05-041	<b>Project Name:</b> Patterson Street Solvent Plume
<b>Client:</b> EPA	
<b>Site:</b> Patterson Street	
<b>Borehole Location:</b> PSP10	
<b>Easting:</b> -79.8405	<b>Northing:</b> 36.0545845
<b>Logged By:</b> Leslie Shaver	
<b>Reviewed By:</b> Leslie Shaver	<b>Review Date:</b> 12/18/2019
<b>Drilling Contractor:</b> Cascade Drilling	
<b>Drill Rig Type/Method:</b> Geoprobe-7000 series DPT	
<b>Borehole Diameter (inches):</b> 2.0	
<b>Drill Start Date:</b> 9/11/2019	<b>Drill Start Time:</b> 1145
<b>Drill Finish Date:</b> 9/11/2019	<b>Drill Finish Time:</b> 1200
<b>Total Borehole Depth (feet bgs):</b> 10	
<b>Well Completion Date:</b> 9/11/2019	<b>Well Completion Time:</b> 1200
<b>Screen Interval (feet bgs):</b> 5.0	<b>Total Well Depth (feet bgs):</b> 10.0
<b>Well Diameter: (inches)</b> 1.0	<b>Well Casing Material:</b> PVC

**PROJECT:** Patterson Street Solvent  
Plume  
**SITE:** Patterson Street  
**BORING ID:** PSP10 **MW ID:** PSP10

**DATE:** 9/11/2019  
**LOGGED BY:** Leslie Shaver

Page 2 of 2

Time	Recovered/Driven (in./in.)	Sample Interval	Depth (feet bgs)	Soil Description
1145	48/60	S		Organic rich silty clay, medium brown, dry
			1	
			2	Soil gas implant (1.5-2')
			3	
			4	Course saprolitic, white, gneissic layer, pulverized quartz, dry silty clay, medium brown, dry
			5	moist, medium brown to grey sandy clay
1150	48/60		6	
			7	wet, medium brown to grey sandy clay
			8	
			9	wet, saprolitic, gneiss like bands, black and white
			10	End of Boring
			11	
			12	
			13	
			14	
			15	
			16	
			17	
			18	
			19	
			20	
			21	
			22	
			23	
			24	

## BOREHOLE LOG

<b>Boring ID:</b> PSP11	
<b>Monitoring Well ID:</b> PSP11	
<b>Project Number:</b> TT-05-041	<b>Project Name:</b> Patterson Street Solvent Plume
<b>Client:</b> EPA	
<b>Site:</b> Patterson Street	
<b>Borehole Location:</b> PSP11	
<b>Easting:</b> -79.8401	<b>Northing:</b> 36.0543
<b>Logged By:</b> Leslie Shaver	
<b>Reviewed By:</b> Leslie Shaver	<b>Review Date:</b> 12/18/2019
<b>Drilling Contractor:</b> Cascade Drilling	
<b>Drill Rig Type/Method:</b> Geoprobe-7000 series DPT	
<b>Borehole Diameter (inches):</b> 2.0	
<b>Drill Start Date:</b> 9/11/2019	<b>Drill Start Time:</b> 1115
<b>Drill Finish Date:</b> 9/11/2019	<b>Drill Finish Time:</b> 1140
<b>Total Borehole Depth (feet bgs):</b> 7	
<b>Well Completion Date:</b> 9/11/2019	<b>Well Completion Time:</b> 1130
<b>Screen Interval (feet bgs):</b> 5.0	<b>Total Well Depth (feet bgs):</b> 7.0
<b>Well Diameter: (inches)</b> 1.0	<b>Well Casing Material:</b> PVC

**PROJECT:** Patterson Street Solvent  
Plume  
**SITE:** Patterson Street  
**BORING ID:** PSP11 **MW ID:** PSP11

**DATE:** 9/11/2019  
**LOGGED BY:** Leslie Shaver

Page 2 of 2

Time	Recovered/Driven (in./in.)	Sample Interval	Depth (feet bgs)	Soil Description
1118	36/60	S		Organic rich, silty clay, dark to medium brown, dry
			1	
			2	moist, medium brown silty clay
			3	
			4	wet, medium brown, sandy clay
			5	
1125	48/60		5	wet saprolitic sandy clay, tan and red mottles
			6	
			7	End of Boring
			8	
			9	
			10	
			11	
			12	
			13	
			14	
			15	
			16	
			17	
			18	
			19	
			20	
			21	
			22	
			23	
			24	



## BOREHOLE LOG

<b>Boring ID:</b> PSP11-DUP	
<b>Monitoring Well ID:</b> PSP11	
<b>Project Number:</b> TT-05-041	<b>Project Name:</b> Patterson Street Solvent Plume
<b>Client:</b> EPA	
<b>Site:</b> Patterson Street	
<b>Borehole Location:</b> PSP11-DUP	
<b>Easting:</b> -79.8401	<b>Northing:</b> 36.0543
<b>Logged By:</b> Leslie Shaver	
<b>Reviewed By:</b> Leslie Shaver	<b>Review Date:</b> 12/18/2019
<b>Drilling Contractor:</b> Cascade Deilling	
<b>Drill Rig Type/Method:</b> Geoprobe-7000 series DPT	
<b>Borehole Diameter (inches):</b> 2.0	
<b>Drill Start Date:</b> 9/11/2019	<b>Drill Start Time:</b> 1135
<b>Drill Finish Date:</b> 9/11/2019	<b>Drill Finish Time:</b> 1145
<b>Total Borehole Depth (feet bgs):</b> 5	
<b>Well Completion Date:</b> NA	<b>Well Completion Time:</b> NA
<b>Screen Interval (feet bgs):</b> NA	<b>Total Well Depth (feet bgs):</b> NA
<b>Well Diameter: (inches)</b> NA	<b>Well Casing Material:</b> NA

**PROJECT:** Patterson Street Solvent  
Plume  
**SITE:** Patterson Street  
**BORING ID:** PSP11-DUP

**DATE:** 9/11/2019  
**LOGGED BY:** Leslie Shaver

Page 2 of 2

Time	Recovered/Driven (in./in.)	Sample Interval	Depth (feet bgs)	Soil Description
1135	36/60	S		Organic rich, silty clay, dark to medium reddish brown, dry
			1	
			2	Increasing moisture and sand content with depth red to medium brown sandy silty clay
			3	Soil gas implant set (3-4')
			4	red to medium brown silty sandy clay
			5	Increasing moisture and sand content with depth End of Boring
			6	
			7	
			8	
			9	
			10	
			11	
			12	
			13	
			14	
			15	
			16	
			17	
			18	
			19	
			20	
			21	
			22	
			23	
			24	

## BOREHOLE LOG

<b>Boring ID:</b> PSP12	
<b>Monitoring Well ID:</b> PSP12	
<b>Project Number:</b> TT-05-041	<b>Project Name:</b> Patterson Street Solvent Plume
<b>Client:</b> EPA	
<b>Site:</b> Patterson Street	
<b>Borehole Location:</b> PSP12	
<b>Easting:</b> -79.8400	<b>Northing:</b> 36.0539
<b>Logged By:</b> Leslie Shaver	
<b>Reviewed By:</b> Leslie Shaver	<b>Review Date:</b> 12/18/2019
<b>Drilling Contractor:</b> Cascade Drilling	
<b>Drill Rig Type/Method:</b> Geoprobe-7000 series DPT	
<b>Borehole Diameter (inches):</b> 2.0	
<b>Drill Start Date:</b> 9/11/2019	<b>Drill Start Time:</b> 1045
<b>Drill Finish Date:</b> 9/11/2019	<b>Drill Finish Time:</b> 1055
<b>Total Borehole Depth (feet bgs):</b> 10	
<b>Well Completion Date:</b> 9/11/2019	<b>Well Completion Time:</b> 1100
<b>Screen Interval (feet bgs):</b> 5.0	<b>Total Well Depth (feet bgs):</b> 10.0
<b>Well Diameter: (inches)</b> 1.0	<b>Well Casing Material:</b> PVC

**PROJECT:** Patterson Street Solvent  
Plume  
**SITE:** Patterson Street  
**BORING ID:** PSP12 **MW ID:** PSP12

**DATE:** 9/11/2019  
**LOGGED BY:** Leslie Shaver

Page 2 of 2

Time	Recovered/Driven (in./in.)	Sample Interval	Depth (feet bgs)	Soil Description
1048	54/60	S		dry, organic rich, medium brown, slightly sandy silty clay, grey mottles
			1	
			2	
			3	Dry, red to tan, sandy silty clay; Soil gas implant (2.5-3')
			4	Dry, red, stiff clay
1050	54/60		5	Dry, red silty clay; Soil gas implant (5.5-6')
			6	
			7	Moist, red to medium brown, slightly silty clay
			8	wet, white sand
			9	wet silty sand, saprolitic micaceous schist
			10	End of Boring
			11	
			12	
			13	
			14	
			15	
			16	
			17	
			18	
			19	
			20	
			21	
			22	
			23	
			24	

## BOREHOLE LOG

<b>Boring ID:</b> PSP13	
<b>Monitoring Well ID:</b> PSP13	
<b>Project Number:</b> TT-05-041	<b>Project Name:</b> Patterson Street Solvent Plume
<b>Client:</b> EPA	
<b>Site:</b> Patterson Street	
<b>Borehole Location:</b> PSP13	
<b>Easting:</b> -79.8395	<b>Northing:</b> 36.0536
<b>Logged By:</b> Leslie Shaver	
<b>Reviewed By:</b> Leslie Shaver	<b>Review Date:</b> 12/18/2019
<b>Drilling Contractor:</b> Cascade Drilling	
<b>Drill Rig Type/Method:</b> Geoprobe-7000 series DPT	
<b>Borehole Diameter (inches):</b> 2.0	
<b>Drill Start Date:</b> 9/11/2019	<b>Drill Start Time:</b> 920
<b>Drill Finish Date:</b> 9/12/2019	<b>Drill Finish Time:</b> 1055
<b>Total Borehole Depth (feet bgs):</b> 20	
<b>Well Completion Date:</b> 9/12/2019	<b>Well Completion Time:</b> 1100
<b>Screen Interval (feet bgs):</b> 5.0	<b>Total Well Depth (feet bgs):</b> 20.0
<b>Well Diameter: (inches)</b> 1.0	<b>Well Casing Material:</b> PVC

**PROJECT:** Patterson Street Solvent  
Plume  
**SITE:** Patterson Street  
**BORING ID:** PSP13 **MW ID:** PSP13

**DATE:** 9/11/2019  
**LOGGED BY:** Leslie Shaver

Page 2 of 2

Time	Recovered/Driven (in./in.)	Sample Interval	Depth (feet bgs)	Soil Description
920	60/60	S		dry, stiff red clay, trace gravel
			1	dry, stiff red clay, uniform
			2	
			3	
			4	
			5	
925	60/60		6	Soil gas implant (5.5-6')
			7	
			8	orangish-red clay, increased moisture
			9	moist, saprolitic schist mottled with clay
			10	
1050	60/60		11	
(9/12/2019)			12	
			13	
			14	
			15	
1055	60/60		16	moist, black and white saprolite schist with red clay layers
(9/12/2019)			17	
			18	
			19	
			20	End of Boring
			21	
			22	
			23	
			24	



## BOREHOLE LOG

<b>Boring ID:</b> PSP14	
<b>Monitoring Well ID:</b> NA	
<b>Project Number:</b> TT-05-041	<b>Project Name:</b> Patterson Street Solvent Plume
<b>Client:</b> EPA	
<b>Site:</b> Patterson Street	
<b>Borehole Location:</b> PSP14	
<b>Easting:</b> -79.8401	<b>Northing:</b> 36.0553
<b>Logged By:</b> John Snyder	
<b>Reviewed By:</b> Leslie Shaver	<b>Review Date:</b> 12/18/2019
<b>Drilling Contractor:</b> Cascade Drilling	
<b>Drill Rig Type/Method:</b> Geoprobe-7000 series DPT	
<b>Borehole Diameter (inches):</b> 2.0	
<b>Drill Start Date:</b> 9/12/2019	<b>Drill Start Time:</b> 0835
<b>Drill Finish Date:</b> 9/12/2019	<b>Drill Finish Time:</b> 0845
<b>Total Borehole Depth (feet bgs):</b> 7.5	
<b>Well Completion Date:</b> NA	<b>Well Completion Time:</b> NA
<b>Screen Interval (feet bgs):</b> NA	<b>Total Well Depth (feet bgs):</b> NA
<b>Well Diameter: (inches)</b> NA	<b>Well Casing Material:</b> NA

**PROJECT:** Patterson Street Solvent  
Plume  
**SITE:** Patterson Street  
**BORING ID:** PSP14

**DATE:** 9/12/2019  
**LOGGED BY:** John Snyder

Page 2 of 2

Time	Recovered/Driven (in./in.)		Depth (feet bgs)	Soil Description
835	60/60			Dark organic rich
			1	Wet, light brown to light gray mottled clay
			2	
			3	
			4	
			5	
840	60/60		6	dry saprolite
			7	Soil gas implant (7-7.5')
				End of Boring, refusal
			8	
			9	
			10	
			11	
			12	
			13	
			14	
			15	
			16	
			17	
			18	
			19	
			20	
			21	
			22	
			23	
			24	

## BOREHOLE LOG

<b>Boring ID:</b> PSP15	
<b>Monitoring Well ID:</b> NA	
<b>Project Number:</b> TT-05-041	<b>Project Name:</b> Patterson Street Solvent Plume
<b>Client:</b> EPA	
<b>Site:</b> Patterson Street	
<b>Borehole Location:</b> PSP15	
<b>Easting:</b> -79.8388	<b>Northing:</b> 36.0550
<b>Logged By:</b> John Snyder	
<b>Reviewed By:</b> Leslie Shaver	<b>Review Date:</b> 12/18/2019
<b>Drilling Contractor:</b> Cascade Drilling	
<b>Drill Rig Type/Method:</b> Geoprobe-7000 series DPT	
<b>Borehole Diameter (inches):</b> 2.0	
<b>Drill Start Date:</b> 9/12/2019	<b>Drill Start Time:</b> 0930
<b>Drill Finish Date:</b> 9/12/2019	<b>Drill Finish Time:</b>
<b>Total Borehole Depth (feet bgs):</b> 7	
<b>Well Completion Date:</b> NA	<b>Well Completion Time:</b> NA
<b>Screen Interval (feet bgs):</b> NA	<b>Total Well Depth (feet bgs):</b> NA
<b>Well Diameter: (inches)</b> NA	<b>Well Casing Material:</b> NA

**PROJECT:** Patterson Street Solvent  
Plume  
**SITE:** Patterson Street  
**BORING ID:** PSP15

**DATE:** 9/12/2019  
**LOGGED BY:** John Snyder

Page 2 of 2

Time	Recovered/Driven (in./in.)	Depth (feet bgs)	Soil Description
930	60/60		dry red uniform clay
		1	Wet, light brown to light gray mottled clay
		2	
		3	
		4	Moist, red to yellow mottled clay
		5	
	60/60	6	dry loose clayey sand; Soil gas implant (6.5-7')
		7	End of Boring
		8	
		9	
		10	
		11	
		12	
		13	
		14	
		15	
		16	
		17	
		18	
		19	
		20	
		21	
		22	
		23	
		24	

## BOREHOLE LOG

<b>Boring ID:</b> PSP16	
<b>Monitoring Well ID:</b> NA	
<b>Project Number:</b> TT-05-041	<b>Project Name:</b> Patterson Street Solvent Plume
<b>Client:</b> EPA	
<b>Site:</b> Patterson Street	
<b>Borehole Location:</b> PSP16	
<b>Easting:</b> -79.8415	<b>Northing:</b> 36.0547
<b>Logged By:</b> Leslie Shaver	
<b>Reviewed By:</b> Leslie Shaver	<b>Review Date:</b> 12/18/2019
<b>Drilling Contractor:</b> Cascade Drilling	
<b>Drill Rig Type/Method:</b> Geoprobe-7000 series DPT	
<b>Borehole Diameter (inches):</b> 2.0	
<b>Drill Start Date:</b> 9/11/2019	<b>Drill Start Time:</b> 1415
<b>Drill Finish Date:</b> 9/11/2019	<b>Drill Finish Time:</b> 1430
<b>Total Borehole Depth (feet bgs):</b> 15	
<b>Well Completion Date:</b> NA	<b>Well Completion Time:</b> NA
<b>Screen Interval (feet bgs):</b> NA	<b>Total Well Depth (feet bgs):</b> NA
<b>Well Diameter: (inches)</b> NA	<b>Well Casing Material:</b> NA

**PROJECT:** Patterson Street Solvent  
Plume  
**SITE:** Patterson Street  
**BORING ID:** PSP16

**DATE:** 9/11/2019  
**LOGGED BY:** Leslie.Shaver

Page 2 of 2

Time	Recovered/Driven (in./in.)		Depth (feet bgs)	Soil Description
1415	60/60			
			1	dry, organic rich, dark brown dry red uniform clay
			2	
			3	
			4	
			5	
1420	60/60		6	dry red uniform clay
			7	
			8	
			9	
			10	
1422	60/60		11	dry red clay, micaceous, slightly less stiff
			12	
			13	
			14	
			15	Soil gas implant (14.5-15') End of Boring
			16	
			17	
			18	
			19	
			20	
			21	
			22	
			23	
			24	

## BOREHOLE LOG

<b>Boring ID:</b> PSP17	
<b>Monitoring Well ID:</b> PSP17	
<b>Project Number:</b> TT-05-041	<b>Project Name:</b> Patterson Street Solvent Plume
<b>Client:</b> EPA	
<b>Site:</b> Patterson Street	
<b>Borehole Location:</b> PSP17	
<b>Easting:</b> -79.8409	<b>Northing:</b> 36.0548
<b>Logged By:</b> John Snyder	
<b>Reviewed By:</b> Leslie Shaver	<b>Review Date:</b> 12/18/2019
<b>Drilling Contractor:</b> Cascade Drilling	
<b>Drill Rig Type/Method:</b> Geoprobe-7000 series DPT	
<b>Borehole Diameter (inches):</b> 2.0	
<b>Drill Start Date:</b> 9/12/2019	<b>Drill Start Time:</b> 0818
<b>Drill Finish Date:</b> 9/12/2019	<b>Drill Finish Time:</b> 0830
<b>Total Borehole Depth (feet bgs):</b> 13.5	
<b>Well Completion Date:</b> 9/12/2019	<b>Well Completion Time:</b> 840
<b>Screen Interval (feet bgs):</b> 10.0	<b>Total Well Depth (feet bgs):</b> 13.5
<b>Well Diameter: (inches)</b> 1.0	<b>Well Casing Material:</b> PVC



**PROJECT:** Patterson Street Solvent  
Plume  
**SITE:** Patterson Street  
**BORING ID:** PSP17 **MW ID:** PSP17

**DATE:** 9/12/2019  
**LOGGED BY:** John Snyder

Page 2 of 2

Time	Recovered/Driven (in./in.)	Depth (feet bgs)	Soil Description
818	60/60		dry light brown sandy clay with gravel
		1	dry brown clay with gravel
		2	uniform light brown clay
		3	
		4	moist light brown clay
		5	
825	60/60	6	moist light brown coarse sand
		7	moist light brown sandy clay
			Soil gas implant set (7')
		8	
		9	
		10	
830	60/60	11	light brown moist coarse sand with clay
		12	
		13	
		14	End of Boring, refusal
		15	
		16	
		17	
		18	
		19	
		20	
		21	
		22	
		23	
		24	

## BOREHOLE LOG

<b>Boring ID:</b> PSP18	
<b>Monitoring Well ID:</b> NA	
<b>Project Number:</b> TT-05-041	<b>Project Name:</b> Patterson Street Solvent Plume
<b>Client:</b> EPA	
<b>Site:</b> Patterson Street	
<b>Borehole Location:</b> PSP18	
<b>Easting:</b>	<b>Northing:</b>
<b>Logged By:</b> Leslie Shaver	
<b>Reviewed By:</b> Leslie Shaver	<b>Review Date:</b> 12/18/2019
<b>Drilling Contractor:</b> Cascade Drilling	
<b>Drill Rig Type/Method:</b> Geoprobe-7000 series DPT	
<b>Borehole Diameter (inches):</b> 2.0	
<b>Drill Start Date:</b> 9/11/2019	<b>Drill Start Time:</b> 1350
<b>Drill Finish Date:</b> 9/11/2019	<b>Drill Finish Time:</b> 1400
<b>Total Borehole Depth (feet bgs):</b> 10	
<b>Well Completion Date:</b> NA	<b>Well Completion Time:</b> NA
<b>Screen Interval (feet bgs):</b> NA	<b>Total Well Depth (feet bgs):</b> NA
<b>Well Diameter: (inches)</b> NA	<b>Well Casing Material:</b> NA

**PROJECT:** Patterson Street Solvent  
Plume  
**SITE:** Patterson Street  
**BORING ID:** PSP18

**DATE:** 9/11/2019  
**LOGGED BY:** Leslie.Shaver

Page 2 of 2

Time	Recovered/Driven (in./in.)		Depth (feet bgs)	Soil Description
1350	60/60			dry organic rich fine sand
			1	
			2	
			3	dry gray to light brown mottled clayey sand
			4	
			5	light brown clay
1355	60/60		6	brown to dark brown mottled crumbling clayey fine-grained sand
			7	firm brown to light brown clayey sand
			8	
			9	
			10	End of Boring
			11	
			12	
			13	
			14	
			15	
			16	
			17	
			18	
			19	
			20	
			21	
			22	
			23	
			24	

## BOREHOLE LOG

<b>Boring ID:</b> PSP19	
<b>Monitoring Well ID:</b> NA	
<b>Project Number:</b> TT-05-041	<b>Project Name:</b> Patterson Street Solvent Plume
<b>Client:</b> EPA	
<b>Site:</b> Patterson Street	
<b>Borehole Location:</b> PSP19	
<b>Easting:</b> -79.8395	<b>Northing:</b> 36.0549
<b>Logged By:</b> John Snyder	
<b>Reviewed By:</b> Leslie Shaver	<b>Review Date:</b> 12/18/2019
<b>Drilling Contractor:</b> Cascade Drilling	
<b>Drill Rig Type/Method:</b> Geoprobe-7000 series DPT	
<b>Borehole Diameter (inches):</b> 2.0	
<b>Drill Start Date:</b> 9/12/2019	<b>Drill Start Time:</b> 0910
<b>Drill Finish Date:</b> 9/12/2019	<b>Drill Finish Time:</b> 0915
<b>Total Borehole Depth (feet bgs):</b> 10	
<b>Well Completion Date:</b> NA	<b>Well Completion Time:</b> NA
<b>Screen Interval (feet bgs):</b> NA	<b>Total Well Depth (feet bgs):</b> NA
<b>Well Diameter: (inches)</b> NA	<b>Well Casing Material:</b> NA

**PROJECT:** Patterson Street Solvent  
Plume  
**SITE:** Patterson Street  
**BORING ID:** PSP19

**DATE:** 9/12/2019

**LOGGED BY:** John Snyder

Page 2 of 2

Time	Recovered/Driven (in./in.)		Depth (feet bgs)	Soil Description
910	60/60			dry brown loam
			1	
			2	dry light brown to brown mottled clay with sand
			3	
			4	brown to light grey mottled clayey sand
			5	
915	60/60		6	brown to light grey mottled clayey sand
			7	Soil gas implant set (6.5-7')
			8	moist dark brown gravely clay
			9	
			10	End of Boring
			11	
			12	
			13	
			14	
			15	
			16	
			17	
			18	
			19	
			20	
			21	
			22	
			23	
			24	

## BOREHOLE LOG

<b>Boring ID:</b> PSP20	
<b>Monitoring Well ID:</b> NA	
<b>Project Number:</b> TT-05-041	<b>Project Name:</b> Patterson Street Solvent Plume
<b>Client:</b> EPA	
<b>Site:</b> Patterson Street	
<b>Borehole Location:</b> PSP20	
<b>Easting:</b> -79.8392	<b>Northing:</b> 36.0542
<b>Logged By:</b> Leslie Shaver	
<b>Reviewed By:</b> Leslie Shaver	<b>Review Date:</b> 12/18/2019
<b>Drilling Contractor:</b> Cascade Drilling	
<b>Drill Rig Type/Method:</b> Geoprobe-7000 series DPT	
<b>Borehole Diameter (inches):</b> 2.0	
<b>Drill Start Date:</b> 9/11/2019	<b>Drill Start Time:</b> 1020
<b>Drill Finish Date:</b> 9/11/2019	<b>Drill Finish Time:</b> 1025
<b>Total Borehole Depth (feet bgs):</b> 10	
<b>Well Completion Date:</b> NA	<b>Well Completion Time:</b> NA
<b>Screen Interval (feet bgs):</b> NA	<b>Total Well Depth (feet bgs):</b> NA
<b>Well Diameter: (inches)</b> NA	<b>Well Casing Material:</b> NA

**PROJECT:** Patterson Street Solvent  
Plume  
**SITE:** Patterson Street  
**BORING ID:** PSP20

**DATE:** 9/11/2019

**LOGGED BY:** Leslie Shaver

Page 2 of 2

Time	Recovered/Driven (in./in.)		Depth (feet bgs)	Soil Description
1020	60/60			moist mottled tan to light gray sandy silty clay
			1	
			2	moist mottled tan and light gray sandy silty clay, decreasing sand content and increasing clay content from above
			3	
			4	dry tan and grey mottled sandy clay
			5	slightly moist tan and gray mottled sandy silty clay; soil gas implant set (5.5-6')
1025	60/60		6	
			7	
			8	moist tan and grey mottled sandy silty clay, increasing clay content and decreasing sand content with depth
			9	
			10	dark grey and red mottled silty clay
				End of Boring
			11	
			12	
			13	
			14	
			15	
			16	
			17	
			18	
			19	
			20	
			21	
			22	
			23	
			24	



## BOREHOLE LOG

<b>Boring ID:</b> PSP21	
<b>Monitoring Well ID:</b> NA	
<b>Project Number:</b> TT-05-041	<b>Project Name:</b> Patterson Street Solvent Plume
<b>Client:</b> EPA	
<b>Site:</b> Patterson Street	
<b>Borehole Location:</b> PSP21	
<b>Easting:</b> -79.8384	<b>Northing:</b> 36.0545
<b>Logged By:</b> Leslie Shaver	
<b>Reviewed By:</b> Leslie Shaver	<b>Review Date:</b> 12/18/2019
<b>Drilling Contractor:</b> Cascade Drilling	
<b>Drill Rig Type/Method:</b> Geoprobe-7000 series DPT	
<b>Borehole Diameter (inches):</b> 2.0	
<b>Drill Start Date:</b> 9/11/2019	<b>Drill Start Time:</b> 0955
<b>Drill Finish Date:</b> 9/11/2019	<b>Drill Finish Time:</b> 1000
<b>Total Borehole Depth (feet bgs):</b> 5	
<b>Well Completion Date:</b> NA	<b>Well Completion Time:</b> NA
<b>Screen Interval (feet bgs):</b> NA	<b>Total Well Depth (feet bgs):</b> NA
<b>Well Diameter: (inches)</b> NA	<b>Well Casing Material:</b> NA

**PROJECT:** Patterson Street Solvent  
Plume  
**SITE:** Patterson Street  
**BORING ID:** PSP21

**DATE:** 9/11/2019  
**LOGGED BY:** Leslie Shaver

Page 2 of 2

Time	Recovered/Driven (in./in.)		Depth (feet bgs)	Soil Description
955	60/60			dry red clayey sand with some organic material at surface
			1	
			2	Soil gas implant set (2.5-3')
			3	moist red clayey sand with less sand from above, moisture increasing with depth
			4	
			5	tan silty clay grading from lighter to darker brown
			6	End of Boring
			7	
			8	
			9	
			10	
			11	
			12	
			13	
			14	
			15	
			16	
			17	
			18	
			19	
			20	
			21	
			22	
			23	
			24	

## BOREHOLE LOG

<b>Boring ID:</b> PSP23	
<b>Monitoring Well ID:</b> PSP23	
<b>Project Number:</b> TT-05-041	<b>Project Name:</b> Patterson Street Solvent Plume
<b>Client:</b> EPA	
<b>Site:</b> Patterson Street	
<b>Borehole Location:</b> PSP23	
<b>Logged By:</b> Leslie Shaver	
<b>Reviewed By:</b> Leslie Shaver	<b>Review Date:</b> 12/18/2019
<b>Drilling Contractor:</b> Cascade Drilling	
<b>Drill Rig Type/Method:</b> Geoprobe-7000 series DPT	
<b>Borehole Diameter (inches):</b> 2.0	
<b>Drill Start Date:</b> 9/12/2019	<b>Drill Start Time:</b> 1309
<b>Drill Finish Date:</b> 9/12/2019	<b>Drill Finish Time:</b> 1315
<b>Total Borehole Depth (feet bgs):</b> 7	
<b>Well Completion Date:</b> 9/12/2019	<b>Well Completion Time:</b> 1325
<b>Screen Interval (feet bgs):</b> 5.0	<b>Total Well Depth (feet bgs):</b> 7.0
<b>Well Diameter: (inches)</b> 1.0	<b>Well Casing Material:</b> PVC

**PROJECT:** Patterson Street Solvent  
Plume  
**SITE:** Patterson Street  
**BORING ID:** PSP23 **MW ID:** PSP23

**DATE:** 9/12/2019  
**LOGGED BY:** Leslie Shaver

Page 2 of 2

Time	Recovered/Driven (in./in.)	Depth (feet bgs)	Soil Description
1309	48/60		dry light brown, organic rich, clayey silt
		1	dry medium brown silty clay with red mottles
		2	
		3	Soil gas implant set (2.5-3')
		4	slightly moist medium brown silty clay
		5	moist medium brown silty sandy clay, loose
1315	48/60	6	gray clay with red clay mottles
		7	gray very sandy clay ending in saprolite, pulverized weathered bedrock
			End of Boring, refusal
		8	
		9	
		10	
		11	
		12	
		13	
		14	
		15	
		16	
		17	
		18	
		19	
		20	
		21	
		22	
		23	
		24	

## BOREHOLE LOG

<b>Boring ID:</b> PSP24	
<b>Monitoring Well ID:</b> PSP24	
<b>Project Number:</b> TT-05-041	<b>Project Name:</b> Patterson Street Solvent Plume
<b>Client:</b> EPA	
<b>Site:</b> Patterson Street	
<b>Borehole Location:</b> PSP24	
<b>Easting:</b> -79.8385	<b>Northing:</b> 36.0530
<b>Logged By:</b> John Snyder	
<b>Reviewed By:</b> Leslie Shaver	<b>Review Date:</b> 12/18/2019
<b>Drilling Contractor:</b> Cascade Drilling	
<b>Drill Rig Type/Method:</b> Geoprobe-7000 series DPT	
<b>Borehole Diameter (inches):</b> 2.0	
<b>Drill Start Date:</b> 9/11/2019	<b>Drill Start Time:</b> 0840
<b>Drill Finish Date:</b> 9/11/2019	<b>Drill Finish Time:</b> 0850
<b>Total Borehole Depth (feet bgs):</b> 6.5	
<b>Well Completion Date:</b> 9/12/2019	<b>Well Completion Time:</b> 855
<b>Screen Interval (feet bgs):</b> 5.0	<b>Total Well Depth (feet bgs):</b> 6.5
<b>Well Diameter: (inches)</b> 1.0	<b>Well Casing Material:</b> PVC

**PROJECT:** Patterson Street Solvent  
Plume  
**SITE:** Patterson Street  
**BORING ID:** PSP24 **MW ID:** PSP24

**DATE:** 9/11/2019  
**LOGGED BY:** John Snyder

Page 2 of 2

Time	Recovered/Driven (in./in.)		Depth (feet bgs)	Soil Description
840	36/60			dry, light brown silty sand with organic material
			1	
			2	uniform moist brown sand
			3	moist to very moist light brown clay; Soil gas implant set (2.5-3')
			4	
			5	
845	24/24		6	dry light grey sand
			6	dry light brown sand
			7	End of Boring, refusal
			8	
			9	
			10	
			11	
			12	
			13	
			14	
			15	
			16	
			17	
			18	
			19	
			20	
			21	
			22	
			23	
			24	

## BOREHOLE LOG

<b>Boring ID:</b> PSP25	
<b>Monitoring Well ID:</b> PSP25	
<b>Project Number:</b> TT-05-041	<b>Project Name:</b> Patterson Street Solvent Plume
<b>Client:</b> EPA	
<b>Site:</b> Patterson Street	
<b>Borehole Location:</b> PSP24	
<b>Easting:</b> -79.8417	<b>Northing:</b> 36.0551
<b>Logged By:</b> John Snyder	
<b>Reviewed By:</b> Leslie Shaver	<b>Review Date:</b> 12/18/2019
<b>Drilling Contractor:</b> Cascade Drilling	
<b>Drill Rig Type/Method:</b> Geoprobe-7000 series DPT	
<b>Borehole Diameter (inches):</b> 2.0	
<b>Drill Start Date:</b> 9/11/2019	<b>Drill Start Time:</b> 1510
<b>Drill Finish Date:</b> 9/11/2019	<b>Drill Finish Time:</b> 1520
<b>Total Borehole Depth (feet bgs):</b> 10	
<b>Well Completion Date:</b> 9/12/2019	<b>Well Completion Time:</b> 1530
<b>Screen Interval (feet bgs):</b> 5.0	<b>Total Well Depth (feet bgs):</b> 10.0
<b>Well Diameter: (inches)</b> 1.0	<b>Well Casing Material:</b> PVC



**PROJECT:** Patterson Street Solvent  
Plume  
**SITE:** Patterson Street  
**BORING ID:** PSP25 **MW ID:** PSP25

**DATE:** 9/11/2019

**LOGGED BY:** John Snyder

Page 2 of 2

Time	Recovered/Driven (in./in.)		Depth (feet bgs)	Soil Description
1510	45/60			dark brown organic rich loam
			1	dry light brown fine sand
			2	Soil gas implant set (1.5-2')
			3	moist dark brown sandy clay
			4	
			5	
1515	45/60		6	saturated light gray sandy clay
			7	
			8	moist dark brown weathered saprolite
			9	
			10	End of Boring
			11	
			12	
			13	
			14	
			15	
			16	
			17	
			18	
			19	
			20	
			21	
			22	
			23	
			24	

## BOREHOLE LOG

<b>Boring ID:</b> PSP26	
<b>Monitoring Well ID:</b> NA	
<b>Project Number:</b> TT-05-041	<b>Project Name:</b> Patterson Street Solvent Plume
<b>Client:</b> EPA	
<b>Site:</b> Patterson Street	
<b>Borehole Location:</b> PSP26	
<b>Easting:</b> -79.8415	<b>Northing:</b> 36.0555
<b>Logged By:</b> John Snyder	
<b>Reviewed By:</b> Leslie Shaver	<b>Review Date:</b> 12/18/2019
<b>Drilling Contractor:</b> Cascade Drilling	
<b>Drill Rig Type/Method:</b> Geoprobe-7000 series DPT	
<b>Borehole Diameter (inches):</b> 2.0	
<b>Drill Start Date:</b> 9/11/2019	<b>Drill Start Time:</b> 1535
<b>Drill Finish Date:</b> 9/11/2019	<b>Drill Finish Time:</b> 1545
<b>Total Borehole Depth (feet bgs):</b> 8	
<b>Well Completion Date:</b> NA	<b>Well Completion Time:</b> NA
<b>Screen Interval (feet bgs):</b> NA	<b>Total Well Depth (feet bgs):</b> NA
<b>Well Diameter: (inches)</b> NA	<b>Well Casing Material:</b> NA

**PROJECT:** Patterson Street Solvent  
Plume  
**SITE:** Patterson Street  
**BORING ID:** PSP26

**DATE:** 9/11/2019  
**LOGGED BY:** John Snyder

Page 2 of 2

Time	Recovered/Driven (in./in.)		Depth (feet bgs)	Soil Description
1535	60/60			dry uniform fine grained sand
			1	
			2	
			3	gray uniform silty clay
			4	
			5	
1540	60/60		6	saprolite
			7	
			8	Soil gas implant set (7.5-8')
				End of Boring, refusal
			9	
			10	
			11	
			12	
			13	
			14	
			15	
			16	
			17	
			18	
			19	
			20	
			21	
			22	
			23	
			24	

## BOREHOLE LOG

<b>Boring ID:</b> PSP27	
<b>Monitoring Well ID:</b> PSP27	
<b>Project Number:</b> TT-05-041	<b>Project Name:</b> Patterson Street Solvent Plume
<b>Client:</b> EPA	
<b>Site:</b> Patterson Street	
<b>Borehole Location:</b> PSP27	
<b>Easting:</b> -79.8400	<b>Northing:</b> 36.0537
<b>Logged By:</b> John Snyder	
<b>Reviewed By:</b> Leslie Shaver	<b>Review Date:</b> 12/18/2019
<b>Drilling Contractor:</b> Cascade Drilling	
<b>Drill Rig Type/Method:</b> Geoprobe-7000 series DPT	
<b>Borehole Diameter (inches):</b> 2.0	
<b>Drill Start Date:</b> 9/12/2019	<b>Drill Start Time:</b> 1025
<b>Drill Finish Date:</b> 9/12/2019	<b>Drill Finish Time:</b> 1040
<b>Total Borehole Depth (feet bgs):</b> 20	
<b>Well Completion Date:</b> 9/12/2019	<b>Well Completion Time:</b> 1045
<b>Screen Interval (feet bgs):</b> 10.0	<b>Total Well Depth (feet bgs):</b> 20.0
<b>Well Diameter: (inches)</b> 1.0	<b>Well Casing Material:</b> PVC

**PROJECT:** Patterson Street Solvent  
Plume  
**SITE:** Patterson Street  
**BORING ID:** PSP27 **MW ID:** PSP27

**DATE:** 9/11/2019  
**LOGGED BY:** John Snyder  
**Page** 2 **of** 2

Time	Recovered/Driven (in./in.)		Depth (feet bgs)	Soil Description
1025	60/60			dry uniform red clay
			1	
			2	
			3	
			4	
			5	
1028	60/60		6	dry uniform red clay
			7	
			8	dry red and light brown mottled clay
			9	Soil gas implant set (9.5-10')
			10	
1032	60/60		11	dry red and light brown mottled clay
			12	dry brown clay with saprolite
			13	
			14	
			15	
1035	60/60		16	damp white fine grained sand
			17	saturated clay with saprolite
			18	saturated white coarse sand with saprolite
			19	
			20	End of Boring
			21	
			22	
			23	
			24	

## BOREHOLE LOG

<b>Boring ID:</b> PSP28	
<b>Monitoring Well ID:</b> NA	
<b>Project Number:</b> TT-05-041	<b>Project Name:</b> Patterson Street Solvent Plume
<b>Client:</b> EPA	
<b>Site:</b> Patterson Street	
<b>Borehole Location:</b> PSP28	
<b>Easting:</b> -79.8415	<b>Northing:</b> 36.0555
<b>Logged By:</b> Leslie Shaver	
<b>Reviewed By:</b> Leslie Shaver	<b>Review Date:</b> 12/18/2019
<b>Drilling Contractor:</b> Cascade Drilling	
<b>Drill Rig Type/Method:</b> Geoprobe-7000 series DPT	
<b>Borehole Diameter (inches):</b> 2.0	
<b>Drill Start Date:</b> 9/11/2019	<b>Drill Start Time:</b> 1535
<b>Drill Finish Date:</b> 9/11/2019	<b>Drill Finish Time:</b> 1545
<b>Total Borehole Depth (feet bgs):</b> 24	
<b>Well Completion Date:</b> 9/12/2019	<b>Well Completion Time:</b> 1550
<b>Screen Interval (feet bgs):</b> 10.0	<b>Total Well Depth (feet bgs):</b> 24.0
<b>Well Diameter: (inches)</b> 1.0	<b>Well Casing Material:</b> PVC

**PROJECT:** Patterson Street Solvent  
Plume  
**SITE:** Patterson Street  
**BORING ID:** PSP28

**DATE:** 9/12/2019  
**LOGGED BY:** Leslie Shaver

Page 2 of 2

Time	Recovered/Driven (in./in.)	Depth (feet bgs)	Soil Description
1115	48/60		Dry, tight, red clay
		1	
		2	
		3	
		4	Slightly sandy, dry, tight, red clay
1117	60/60	5	
		6	Soil gas implant set (6.5-7')
		7	
		8	Dry, red, sandy clay
		9	
		10	Dry, tan, micaceous sandy clay
		11	
		12	
		13	
		14	
	60/60	15	Dry, tan, micaceous sandy clay with increasing moisture
		16	
		17	
		18	
		19	
	48/48	20	
		21	Saprolitic, tan and white, micaceous schist
		22	
		23	
		24	End of boring

## **APPENDIX D**

### **SITE INSPECTION PHOTOGRAPHIC LOG**

(12 Pages)





**OFFICIAL PHOTOGRAPH NO. 1**  
**U.S. ENVIRONMENTAL PROTECTION AGENCY**

<b>TDD Number:</b>	TT-05-041	<b>Project:</b>	Patterson Street Solvent Plume
<b>Orientation:</b>	West	<b>Date:</b>	September 9, 2019
<b>Photographer:</b>	Amber Falkner, Tetra Tech, Inc. (Tetra Tech)	<b>Witness:</b>	Quinn Kelley, Tetra Tech
<b>Subject:</b>	Tetra Tech uses the thermal imaging camera (provided by the U.S. Environmental Protection Agency [EPA] Laboratory Services and Applied Sciences Division) to identify groundwater seeps into the bedrock unnamed tributary. Seeps appear as dark blue on the thermal imaging camera; colder than the surface water temperature.		



**OFFICIAL PHOTOGRAPH NO. 2**  
**U.S. ENVIRONMENTAL PROTECTION AGENCY**

<b>TDD Number:</b>	TT-05-041	<b>Project:</b>	Patterson Street Solvent Plume
<b>Orientation:</b>	North	<b>Date:</b>	September 10, 2019
<b>Photographer:</b>	Quinn Kelley, Tetra Tech	<b>Witness:</b>	Amber Falkner, Tetra Tech
<b>Subject:</b>	Tetra Tech collects a surface water sample at location PSP06 along the urban ditch unnamed tributary.		





**OFFICIAL PHOTOGRAPH NO. 3**  
**U.S. ENVIRONMENTAL PROTECTION AGENCY**

<b>TDD Number:</b>	TT-05-041	<b>Project:</b>	Patterson Street Solvent Plume
<b>Orientation:</b>	Not Applicable	<b>Date:</b>	September 9, 2019
<b>Photographer:</b>	Quinn Kelley, Tetra Tech	<b>Witness:</b>	Leslie Shaver, Tetra Tech

**Subject:** Tetra Tech prepares the air sample canisters for deployment throughout the study area neighborhood.



**OFFICIAL PHOTOGRAPH NO. 4**  
**U.S. ENVIRONMENTAL PROTECTION AGENCY**


<b>TDD Number:</b>	TT-05-041	<b>Project:</b>	Patterson Street Solvent Plume
<b>Orientation:</b>	Northeast	<b>Date:</b>	September 9, 2019
<b>Photographer:</b>	Quinn Kelley, Tetra Tech	<b>Witness:</b>	Amber Falkner, Tetra Tech
<b>Subject:</b>	Tetra Tech deploys ambient air sample at location PSP13.		





**OFFICIAL PHOTOGRAPH NO. 5**  
**U.S. ENVIRONMENTAL PROTECTION AGENCY**

<b>TDD Number:</b>	TT-05-041	<b>Project:</b>	Patterson Street Solvent Plume
<b>Orientation:</b>	South	<b>Date:</b>	September 12, 2019
<b>Photographer:</b>	Quinn Kelley, Tetra Tech	<b>Witness:</b>	John Snyder, Tetra Tech
<b>Subject:</b>	Tetra Tech oversees the drillers to collect soil gas at location PSP19.		



**OFFICIAL PHOTOGRAPH NO. 6**  
**U.S. ENVIRONMENTAL PROTECTION AGENCY**

**TDD Number:** TT-05-041                      **Project:** Patterson Street Solvent Plume

**Orientation:** Northeast                      **Date:** September 11, 2019

**Photographer:** Quinn Kelley, Tetra Tech                      **Witness:** Amber Falkner, Tetra Tech

**Subject:** The Tetra Tech geologist logs the soil core from location PSP13. A soil gas and surface soil sample were collected from this location.





**OFFICIAL PHOTOGRAPH NO. 7**  
**U.S. ENVIRONMENTAL PROTECTION AGENCY**

<b>TDD Number:</b>	TT-05-041	<b>Project:</b>	Patterson Street Solvent Plume
<b>Orientation:</b>	North	<b>Date:</b>	September 11, 2019
<b>Photographer:</b>	Quinn Kelley, Tetra Tech	<b>Witness:</b>	Amber Falkner, Tetra Tech
<b>Subject:</b>	Tetra Tech collects surface soil sample with a Terracore kit for volatile organic compound analysis at location PSP11.		



**OFFICIAL PHOTOGRAPH NO. 8**  
**U.S. ENVIRONMENTAL PROTECTION AGENCY**

<b>TDD Number:</b>	TT-05-041	<b>Project:</b>	Patterson Street Solvent Plume
<b>Orientation:</b>	East	<b>Date:</b>	September 11, 2019
<b>Photographer:</b>	Quinn Kelley, Tetra Tech	<b>Witness:</b>	Amber Falkner, Tetra Tech
<b>Subject:</b>	Tetra Tech collects a groundwater sample at location PSP10.		





**OFFICIAL PHOTOGRAPH NO. 9**  
**U.S. ENVIRONMENTAL PROTECTION AGENCY**

<b>TDD Number:</b>	TT-05-041	<b>Project:</b>	Patterson Street Solvent Plume
<b>Orientation:</b>	Not Applicable	<b>Date:</b>	September 10, 2019
<b>Photographer:</b>	Quinn Kelley, Tetra Tech	<b>Witness:</b>	Amber Falkner, Tetra Tech

**Subject:** Seep that originates the urban ditch unnamed tributary (circular clearing at the center of the photograph). Surface water and ambient air samples were collected at this location (PSP22).



**OFFICIAL PHOTOGRAPH NO. 10**  
**U.S. ENVIRONMENTAL PROTECTION AGENCY**

<b>TDD Number:</b>	TT-05-041	<b>Project:</b>	Patterson Street Solvent Plume
<b>Orientation:</b>	Not Applicable	<b>Date:</b>	September 10, 2019
<b>Photographer:</b>	Quinn Kelley, Tetra Tech	<b>Witness:</b>	Amber Falkner, Tetra Tech
<b>Subject:</b>	Tetra Tech installs the pore water sampler at location PSP22.		





**OFFICIAL PHOTOGRAPH NO. 11**  
**U.S. ENVIRONMENTAL PROTECTION AGENCY**

<b>TDD Number:</b>	TT-05-041	<b>Project:</b>	Patterson Street Solvent Plume
<b>Orientation:</b>	Not Applicable	<b>Date:</b>	September 10, 2019
<b>Photographer:</b>	Quinn Kelley, Tetra Tech	<b>Witness:</b>	Amber Falkner, Tetra Tech
<b>Subject:</b>	The pore water sampler did not produce any water; therefore, a pore water sample was not collected at this location (PSP22).		





**OFFICIAL PHOTOGRAPH NO. 12**  
**U.S. ENVIRONMENTAL PROTECTION AGENCY**

<b>TDD Number:</b>	TT-05-041	<b>Project:</b>	Patterson Street Solvent Plume
<b>Orientation:</b>	Northeast	<b>Date:</b>	September 13, 2019
<b>Photographer:</b>	Quinn Kelley, Tetra Tech	<b>Witness:</b>	Amber Falkner, Tetra Tech
<b>Subject:</b>	Tetra Tech collects split soil gas samples at location PSP13.		

**APPENDIX E**  
**SURFACE WATER PHOTOGRAPHIC LOG**  
(10 Pages)





**Legend**

- Surface Water Sample
- Surface Water
- Direction of Flow
- Culvert

0 25 50 Feet

Notes:  
PSP - Patterson Street Solvent Plume Site  
Temperatures displayed on thermal image are in degrees Fahrenheit.

Map Source:  
Bing Maps Aerial Imagery, 2015.



The surface water samples collected at PSP01 contained elevated concentrations of 1,1-dichloroethene (DCE) (up to 28 micrograms per liter [µg/L]), cis-1,2-DCE (up to 1.8 µg/L), tetrachloroethene (PCE) (up to 5.9 µg/L), trichloroethene (TCE) (up to 6.4 µg/L), and vinyl chloride (up to 0.54 µg/L). Using a thermal imaging camera, Tetra Tech, Inc. (Tetra Tech) observed evidence of a seep.

**United States Environmental Protection Agency Region 4**



**Surface Water Location PSP01**

<b>TDD Name:</b>	Patterson Street Solvent Plume Site	
<b>TDD No.:</b>	TT-05-041	
<b>City:</b>	<b>County:</b>	<b>State:</b>
Greensboro	Guilford	North Carolina

**TETRA TECH**

**Date:** 1/20/2020  
**Analyst:** dale.vonbusch





**Legend**

- Surface Water Sample
- Surface Water
- Direction of Flow

0 25 50 Feet

Notes:  
PSP - Patterson Street Solvent Plume Site  
Temperatures displayed on thermal image are in degrees Fahrenheit.

Map Source:  
Bing Maps Aerial Imagery, 2015.



The surface water sample collected at PSP02 contained elevated concentrations of 1,1-DCE (6.8 µg/L), cis-1,2-DCE (5.4 µg/L), PCE (16 µg/L), and TCE (7.4 µg/L). Using a thermal imaging camera, Tetra Tech observed evidence of a seep.

**United States Environmental Protection Agency Region 4**

**Surface Water Location PSP02**

<b>TDD Name:</b>	Patterson Street Solvent Plume Site	
<b>TDD No.:</b>	TT-05-041	
<b>City:</b>	<b>County:</b>	<b>State:</b>
Greensboro	Guilford	North Carolina

**TETRA TECH**

**Date:** 1/20/2020  
**Analyst:** dale.vonbusch





The surface water sample collected at PSP03 contained elevated concentrations of 1,1-DCE (9.6 µg/L), cis-1,2-DCE (12 µg/L), PCE (88 µg/L), TCE (33 µg/L), and vinyl chloride (0.84 µg/L).


- Legend**
- Surface Water Sample
  - Surface Water
  - Direction of Flow



0 25 50 Feet

Notes:  
PSP - Patterson Street Solvent Plume Site

Map Source:  
Bing Maps Aerial Imagery, 2015.



**United States  
Environmental Protection Agency  
Region 4**

Surface Water Location PSP03

<b>TDD Name:</b>	Patterson Street Solvent Plume Site	
<b>TDD No.:</b>	TT-05-041	
<b>City:</b>	<b>County:</b>	<b>State:</b>
Greensboro	Guilford	North Carolina

**TETRA TECH**

**Date:**  
1/20/2020

**Analyst:**  
dale.vonbusch






- Legend**
- Surface Water Sample
  - Surface Water
  - Direction of Flow
  - Culvert




0 25 50 Feet

Notes:  
PSP - Patterson Street Solvent Plume Site

Map Source:  
Bing Maps Aerial Imagery, 2015.





**United States  
Environmental Protection Agency  
Region 4**

**Surface Water Location PSP04**


**TDD Name:** Patterson Street Solvent Plume Site

**TDD No.:** TT-05-041

**City:** Greensboro

**County:** Guilford

**State:** North Carolina

**TETRA TECH**




**Date:** 1/20/2020  
**Analyst:** dale.vonbusch





The surface water sample collected at PSP05 contained elevated concentrations of 1,1-DCE (8.0 µg/L), cis-1,2-DCE (5.3 µg/L), PCE (8.6 µg/L), and TCE (6.2 µg/L).

## Legend


-  Surface Water Sample
-  Surface Water
-  Direction of Flow



0 25 50 Feet

Notes:  
PSP - Patterson Street Solvent Plume Site

Map Source:  
Bing Maps Aerial Imagery, 2015.



United States  
Environmental Protection Agency  
Region 4

## Surface Water Location PSP05

**TDD Name:** Patterson Street Solvent Plume Site

**TDD No.:** TT-05-041

**City:** Greensboro **County:** Guilford **State:** North Carolina




**TETRA TECH**

**Date:** 1/20/2020  
**Analyst:** dale.vonbusch






- Legend**
- Surface Water Sample
  - Surface Water
  - Direction of Flow
  - Culvert



Notes:  
PSP - Patterson Street Solvent Plume Site

Map Source:  
Bing Maps Aerial Imagery, 2015.



**United States  
Environmental Protection Agency  
Region 4**

**Surface Water Location PSP06**

**TDD Name:** Patterson Street Solvent Plume Site

**TDD No.:** TT-05-041

**City:** Greensboro **County:** Guilford **State:** North Carolina

**Date:** 1/20/2020  
**Analyst:** dale.vonbusch

**TETRA TECH**





The surface water sample collected at PSP07 contained elevated concentrations of 1,1-DCE (7.4 µg/L), cis-1,2-DCE (6.6 µg/L), PCE (7.5 µg/L), and TCE (7.1 µg/L).


- Legend**
- Surface Water Sample
  - Surface Water
  - Direction of Flow
  - Culvert



0 25 50 Feet

Notes:  
PSP - Patterson Street Solvent Plume Site

Map Source:  
Bing Maps Aerial Imagery, 2015.



United States  
Environmental Protection Agency  
Region 4

Surface Water Location PSP07

**TDD Name:** Patterson Street Solvent Plume Site  
**TDD No.:** TT-05-041  
**City:** Greensboro **County:** Guilford **State:** North Carolina




TETRA TECH

**Date:**  
1/20/2020  
**Analyst:**  
dale.vonbusch





The surface water sample collected at PSP08 contained elevated concentrations of 1,1-DCE (28 µg/L), cis-1,2-DCE (17 µg/L), PCE (44 µg/L), TCE (24 µg/L), and vinyl chloride (1.2 µg/L). Using a thermal imaging camera, Tetra Tech observed evidence of a seep.



**Legend**

- Surface Water Sample
- Surface Water
- Direction of Flow
- Culvert

0 25 50 Feet

Notes:  
PSP - Patterson Street Solvent Plume Site  
Temperatures displayed on thermal image are in degrees Fahrenheit.

Map Source:  
Bing Maps Aerial Imagery, 2015.

**United States Environmental Protection Agency Region 4**


**Surface Water Location PSP08**

<b>TDD Name:</b>	Patterson Street Solvent Plume Site	
<b>TDD No.:</b>	TT-05-041	
<b>City:</b>	<b>County:</b>	<b>State:</b>
Greensboro	Guilford	North Carolina

**TETRA TECH**

**Date:** 1/20/2020  
**Analyst:** dale.vonbusch





The surface water sample collected at PSP09 contained elevated concentrations of 1,1-DCE (24 µg/L), cis-1,2-DCE (15 µg/L), PCE (36 µg/L), TCE (20 µg/L), and vinyl chloride (1.1 µg/L).


- Legend**
- Surface Water Sample
  - Surface Water
  - Direction of Flow
  - Culvert



0 25 50 Feet

Notes:  
PSP - Patterson Street Solvent Plume Site

Map Source:  
Bing Maps Aerial Imagery, 2015.



United States  
Environmental Protection Agency  
Region 4


Surface Water Location PSP09

<b>TDD Name:</b>	Patterson Street Solvent Plume Site	
<b>TDD No.:</b>	TT-05-041	
<b>City:</b>	<b>County:</b>	<b>State:</b>
Greensboro	Guilford	North Carolina

**Date:**  
1/20/2020

**Analyst:**  
dale.vonbusch






- Legend**
- Surface Water Sample
  - Surface Water
  - Direction of Flow
  - Culvert



0 25 50 Feet

Notes:  
PSP - Patterson Street Solvent Plume Site  
Temperatures displayed on thermal image are in degrees Fahrenheit.

Map Source:  
Bing Maps Aerial Imagery, 2015.



**United States Environmental Protection Agency Region 4**

**Surface Water Location PSP22**


**TDD Name:** Patterson Street Solvent Plume Site  
**TDD No.:** TT-05-041  
**City:** Greensboro **County:** Guilford **State:** North Carolina


**TETRA TECH**

**Date:** 1/20/2020  
**Analyst:** dale.vonbusch



**APPENDIX F**  
**REVIEW OF FIELD QUALITY CONTROL SAMPLES**  
(Seven Pages)

Review of Field Quality Control Samples			
<b>Date:</b>	December 16, 2019	<b>Project No.:</b>	TT-05-041
		<b>Project Name:</b>	Patterson Street Solvent Plume
<b>Name:</b>	Jessica Vickers		
<b>Signature:</b>			
<p>The following is a summary of the review performed by Tetra Tech for the Regional Laboratory analytical data packages created for samples collected September 10 through 12, 2019 at the Patterson Street Solvent Plume site. This review was performed on the following field quality control (QC) samples: trip blank samples, equipment rinsate blanks samples, and field duplicate samples. This review was performed because the U.S. Environmental Protection Agency, Region 4, Science and Ecosystem Support Division, Office of Quality Assurance does not review these types of field QC samples as part of their validation effort. This policy was stated during a data validation webinar held on February 17, 2011. The webinar was attended by personnel from all 10 EPA Regions as well as personnel from various agencies that utilize the EPA CLP and Regional Laboratories for analytical support.</p> <p><b>Trip Blank and Equipment Rinsate Blank Samples:</b> Equipment rinsate blank collection frequencies (one per twenty samples) were met. One equipment rinsate sample (associated with soil samples) were collected and analyzed for select volatile organic compounds (VOCs). No VOCs were detected at or above the minimum reporting limits (MRL) in the equipment rinsate blank. Trip blank collection frequencies (one per shipment of VOC samples) were met. Two water and one soil trip blank were collected and analyzed for select VOCs. No VOCs were detected at or above the MRL in the trip blanks.</p> <p><b>Field Duplicate Samples:</b> Field duplicate collection frequencies (one per twenty samples per matrix) were met for all matrices. One field duplicate sample each for groundwater (PSP24-GW-DUP), surface water (PSP01-SW-DUP), and surface soil (PSP11-SF-DUP) were collected and analyzed for VOCs. The acceptance criteria were less than or equal to 50 percent relative percent difference (RPD) for soils and less than or equal to 25 percent for groundwater and surface water, or an absolute difference between the two results less than or equal to the MRL if one of the two results of the pair is below its MRL or non-detect (in which case the MRL is used for the calculation). These criteria were met for all three field duplicate samples collected and analyzed.</p>			

Review of Field Quality Control Samples			
<b>Date:</b>	December 16, 2019	<b>Project No.:</b>	TT-05-041
		<b>Project Name:</b>	Patterson Street Solvent Plume
<b>Name:</b>	Jessica Vickers		
<b>Signature:</b>			
<p>The following is a summary of the review performed by Tetra Tech for the Regional Laboratory analytical data packages created for samples collected September 10 through 13, 2019 at the Patterson Street Solvent Plume site. This review was performed on the field duplicate/split samples. This review was performed because the U.S. Environmental Protection Agency, Region 4, Science and Ecosystem Support Division, Office of Quality Assurance does not review these types of field QC samples as part of their validation effort. This policy was stated during a data validation webinar held on February 17, 2011. The webinar was attended by personnel from all 10 EPA Regions as well as personnel from various agencies that utilize the EPA CLP and Regional Laboratories for analytical support.</p> <p><b>Field Duplicate Samples:</b> Field duplicate/split collection frequencies (one per twenty samples per matrix) were met for all matrices. One field duplicate/split sample each for ambient air (PSP10-AA-DUP) and soil gas (PSP13-SG-SPLIT) were collected and analyzed for volatile organic compounds (VOCs). The acceptance criteria were less than or equal to 25 percent relative percent difference (RPD), or an absolute difference between the two results less than or equal to the MRL if one of the two results of the pair is below its MRL or non-detect (in which case the MRL is used for the calculation).</p> <p>These criteria were met for the soil gas split sample collected and analyzed. For the ambient air field duplicate sample pair PSP10-AA and PSP10-AA-DUP, the RPD value for VOC tetrachloroethene was greater than 25 percent. The tetrachloroethene results for both samples were qualified as estimated (J).</p> <p>The attached laboratory sample result forms have been hand-annotated in blue ink, where appropriate, to indicate any additional qualifications that were required due to the exceedances discussed above.</p>			

**LABORATORY SAMPLE RESULTS FORMS FOR  
FIELD DUPLICATE SAMPLE PAIRS**

(Two Pages)



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Sallie Hale

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP10-AA**

**Lab ID: E193801-01**

**Station ID: PSP10**

**Matrix: Air**

**Date Collected: 9/11/19 14:42**

CAS Number	Analyte	Results	Qualifiers	Units	MRL	Prepared	Analyzed	Method
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.55		ug/m3	0.23	9/16/19 11:32	9/17/19 18:20	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.36		ug/m3	0.21	9/16/19 11:32	9/17/19 18:20	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.90	J	ug/m3	0.36	9/16/19 11:32	9/17/19 18:20	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.21	U	ug/m3	0.21	9/16/19 11:32	9/17/19 18:20	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.63		ug/m3	0.29	9/16/19 11:32	9/17/19 18:20	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	9/16/19 11:32	9/17/19 18:20	EPA TO-15

*gaw*  
12/16/19



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Sallie Hale

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP10-AA-DUP**

**Lab ID: E193801-02**


**Station ID: PSP10**

**Matrix: Air**


**Date Collected: 9/11/19 14:42**

CAS Number	Analyte	Results	Qualifiers	Units	MRL	Prepared	Analyzed	Method
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.54		ug/m3	0.23	9/16/19 11:36	9/17/19 20:03	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.34		ug/m3	0.21	9/16/19 11:36	9/17/19 20:03	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	1.2	J	ug/m3	0.37	9/16/19 11:36	9/17/19 20:03	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.40		ug/m3	0.21	9/16/19 11:36	9/17/19 20:03	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.66		ug/m3	0.29	9/16/19 11:36	9/17/19 20:03	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	9/16/19 11:36	9/17/19 20:03	EPA TO-15

*gaw*  
12/14/19

Review of Field Quality Control Samples			
<b>Date:</b>	December 18, 2019	<b>Project No.:</b>	TT-05-041
		<b>Project Name:</b>	Patterson Street Solvent Plume
<b>Name:</b>	Jessica Vickers		
<b>Signature:</b>			
<p>The following is a summary of the review performed by Tetra Tech for the Regional Laboratory analytical data packages created for samples collected December 4, 2019 at the Patterson Street Solvent Plume site. This review was performed on the field duplicate samples. This review was performed because the U.S. Environmental Protection Agency, Region 4, Science and Ecosystem Support Division, Office of Quality Assurance does not review these types of field QC samples as part of their validation effort. This policy was stated during a data validation webinar held on February 17, 2011. The webinar was attended by personnel from all 10 EPA Regions as well as personnel from various agencies that utilize the EPA CLP and Regional Laboratories for analytical support.</p> <p><b>Field Duplicate Samples:</b> Field duplicate collection frequencies (one per twenty samples per matrix) were met. One field duplicate sample air (PSP20-AA-DUP) was collected and analyzed for volatile organic compounds (VOCs). The acceptance criteria were less than or equal to 25 percent relative percent difference (RPD), or an absolute difference between the two results less than or equal to the MRL if one of the two results of the pair is below its MRL or non-detect (in which case the MRL is used for the calculation). These criteria were met for the air field duplicate sample pair.</p>			



Review of Field Quality Control Samples			
<b>Date:</b>	January 7, 2020	<b>Project No.:</b>	TT-05-041
		<b>Project Name:</b>	Patterson Street Solvent Plume
<b>Name:</b>	Jessica Vickers		
<b>Signature:</b>			
<p>The following is a summary of the review performed by Tetra Tech for the Regional Laboratory analytical data packages created for samples collected December 3, 2019 at the Patterson Street Solvent Plume site. This review was performed on the trip blank sample. This review was performed because the U.S. Environmental Protection Agency, Region 4, Science and Ecosystem Support Division, Office of Quality Assurance does not review these types of field QC samples as part of their validation effort. This policy was stated during a data validation webinar held on February 17, 2011. The webinar was attended by personnel from all 10 EPA Regions as well as personnel from various agencies that utilize the EPA CLP and Regional Laboratories for analytical support.</p> <p><b>Trip Blank Sample:</b> Trip blank collection frequencies (one per shipment of volatile organic compounds [VOC] samples) were met. The trip blank was collected and analyzed for select VOCs. No VOCs were detected at or above the minimum reporting limits in the trip blanks.</p>			

**ATTACHMENT 1**

**EPA LABORATORY SERVICES AND APPLIED SCIENCES DIVISION (LSASD)  
ANALYTICAL DATA PACKAGES**

(112 Sheets)



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

November 19, 2019

4LSASD-LSB

**MEMORANDUM**

**SUBJECT:** FINAL Analytical Report  
Project: 19-0323, Patterson Street Solvent Plume

**FROM:** Kristin Trapp  
OCS Analyst

**THRU:** Jeffrey Hendel, Chief  
LSB Organic Chemistry Section

**TO:** Cathy Amoroso

**This data report is being reissued. Some or all of these results were previously reported. Please substitute the corrected results for those results previously reported. Please refer to the Report Narrative for more details.**

Attached are the final results for the analytical groups listed below. This report shall not be reproduced except in full without approval of the Region 4 laboratory. These analyses were performed in accordance with the Laboratory Services Branch's Laboratory Operations and Quality Assurance Manual (LSB LOQAM) found at [www.epa.gov/region4/sesd/asbsop](http://www.epa.gov/region4/sesd/asbsop). Any unique project data quality objectives specified in writing by the data requestor have also been incorporated into the data unless otherwise noted in the Report Narrative. Chemistry data have been verified based on the LSB LOQAM specifications and have been qualified by this laboratory if the applicable quality control criteria were not met. Verification is defined in Chapter 5 of the LSB LOQAM. For a listing of specific data qualifiers and explanations, please refer to the Data Qualifier Definitions included in this report. The reported results are accurate within the limits of the method(s) and are representative only of the samples as received by the laboratory.

Analyses Included in this report:	Method Used:	Accreditations:
<b>Physical Properties (PHYSP)</b>		
Physical Properties	EPA 200.2 (Soil)	ISO
<b>Volatile Organics (VOA)</b>		
Volatile organic compounds	EPA 8260C (Soil)	ISO
Volatile organic compounds	EPA 8260C (Water)	ISO



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
Region 4 Laboratory Services and Applied Science Division  
980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

**Report Narrative for Project: 19-0323**

11/19/19 KT VOA Soil and Water: This data has been reissued to include only those analytes requested by the project leader. This report replaces E193705, E193707 PHYS VOA FINAL 10 15 19 1802.pdf.

---

**Sample Disposal Policy**

Due to limited space for long term sample storage, LSB's policy is to dispose of samples on a periodic schedule. Air samples collected in summa canisters will be disposed of 30 days following the issuance of this report. All other sample media including original samples, sample extracts and or digestates will be disposed of, in accordance with applicable regulations, 60 days from the date of this report.

This sample disposal policy does not apply to criminal samples which are held until the laboratory is notified by the criminal investigators that case development and litigation are complete.

These samples may be held in the laboratory's custody for a longer period of time. If samples require storage beyond the 60-day period, please contact the Sample Control Coordinator by e-mail at [R4SampleCustody@epa.gov](mailto:R4SampleCustody@epa.gov).

cc: Nardina Turner





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

### SAMPLES INCLUDED IN THIS REPORT

#### Project: 19-0323, Patterson Street Solvent Plume

Sample ID	Laboratory ID	Matrix	Date Collected	Date Received
PSP-TB-01	E193705-01	Trip Blank - Soil	9/11/19 17:35	9/12/19 10:25
PSP-TB-02	E193705-02	Trip Blank - Water	9/11/19 17:30	9/12/19 10:25
PSP01-SW	E193705-03	Surface Water	9/10/19 09:44	9/12/19 10:25
PSP01-SW-DUP	E193705-04	Surface Water	9/10/19 09:45	9/12/19 10:25
PSP02-SW	E193705-05	Surface Water	9/10/19 09:26	9/12/19 10:25
PSP03-SW	E193705-06	Surface Water	9/10/19 09:18	9/12/19 10:25
PSP04-SW	E193705-07	Surface Water	9/10/19 09:10	9/12/19 10:25
PSP05-SW	E193705-08	Surface Water	9/10/19 10:40	9/12/19 10:25
PSP06-SW	E193705-09	Surface Water	9/10/19 10:53	9/12/19 10:25
PSP07-SW	E193705-10	Surface Water	9/10/19 11:00	9/12/19 10:25
PSP08-SW	E193705-11	Surface Water	9/10/19 09:00	9/12/19 10:25
PSP09-SW	E193705-12	Surface Water	9/10/19 08:41	9/12/19 10:25
PSP10-GW	E193705-13	Groundwater	9/11/19 16:48	9/12/19 10:25
PSP10-SF	E193705-14	Surface Soil	9/11/19 11:55	9/12/19 10:25
PSP11-SF	E193705-15	Surface Soil	9/11/19 11:25	9/12/19 10:25
PSP11-SF-DUP	E193705-16	Surface Soil	9/11/19 11:40	9/12/19 10:25
PSP12-GW	E193705-17	Groundwater	9/11/19 16:21	9/12/19 10:25
PSP12-SF	E193705-18	Surface Soil	9/11/19 10:55	9/12/19 10:25
PSP13-SF	E193705-19	Surface Soil	9/11/19 09:30	9/12/19 10:25
PSP22-SEEP	E193705-20	Surface Water	9/10/19 11:12	9/12/19 10:25
PSP-EB-01	E193707-01	Equipment Rinse Blank	9/12/19 17:14	9/13/19 9:50
PSP-TB-03	E193707-02	Trip Blank - Water	9/12/19 17:15	9/13/19 9:50
PSP11-GW	E193707-03	Groundwater	9/12/19 14:50	9/13/19 9:50
PSP13-GW	E193707-04	Groundwater	9/12/19 15:15	9/13/19 9:50
PSP17-GW	E193707-05	Groundwater	9/12/19 14:15	9/13/19 9:50
PSP24-GW	E193707-06	Groundwater	9/12/19 13:35	9/13/19 9:50
PSP24-GW-DUP	E193707-07	Groundwater	9/12/19 13:37	9/13/19 9:50
PSP25-GW	E193707-08	Groundwater	9/12/19 09:35	9/13/19 9:50



## UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

### DATA QUALIFIER DEFINITIONS

U	The analyte was not detected at or above the reporting limit.
J	The identification of the analyte is acceptable; the reported value is an estimate.
Q-2	Result greater than MDL but less than MRL.
QI-1	Internal standard was outside of method control limits.

### ACRONYMS AND ABBREVIATIONS

CAS	Chemical Abstracts Service  Note: Analytes with no known CAS identifiers have been assigned codes beginning with "E", the EPA ID as assigned by the EPA Substance Registry System ( <a href="http://www.epa.gov/srs">www.epa.gov/srs</a> ), or beginning with "R4-", a unique identifier assigned by the EPA Region 4 laboratory.
MDL	Method Detection Limit - The minimum concentration of a substance (an analyte) that can be measured and reported with a 99% confidence that the analyte concentration is greater than zero.
MRL	Minimum Reporting Limit - Analyte concentration that corresponds to the lowest demonstrated level of acceptable quantitation. The MRL is sample-specific and accounts for preparation weights and volumes, dilutions, and moisture content of soil/sediments.
TIC	Tentatively Identified Compound - An analyte identified based on a match with the instrument software's mass spectral library. A calibration standard has not been analyzed to confirm the compound's identification or the estimated concentration reported.

### ACCREDITATIONS:

ISO	ASB is accredited by ISO/IEC 17025, including an amplification for forensic accreditation through ANSI-ASQ National Accreditation Board.  Refer to the certificate and scope of accreditation AT-1644 at: <a href="http://www.epa.gov/aboutepa/about-region-4s-science-and-ecosystem-support-division-sesd">http://www.epa.gov/aboutepa/about-region-4s-science-and-ecosystem-support-division-sesd</a>
NR	The EPA Region 4 Laboratory has not requested accreditation for this test.



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP-TB-01**

**Lab ID: E193705-01**

**Station ID:**

**Matrix: Trip Blank - Soil**

**Date Collected: 9/11/19 17:35**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.95	U	ug/kg dry	0.95	9/12/19 14:38	9/16/19 16:18	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	0.95	U	ug/kg dry	0.95	9/12/19 14:38	9/16/19 16:18	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.95	U	ug/kg dry	0.95	9/12/19 14:38	9/16/19 16:18	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.95	U	ug/kg dry	0.95	9/12/19 14:38	9/16/19 16:18	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	0.95	U	ug/kg dry	0.95	9/12/19 14:38	9/16/19 16:18	EPA 8260C
75-01-4	Vinyl chloride	0.95	U	ug/kg dry	0.95	9/12/19 14:38	9/16/19 16:18	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Physical Properties

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID:** PSP-TB-01

**Lab ID:** E193705-01

**Station ID:**

**Matrix:** Trip Blank - Soil

**Date Collected:** 9/11/19 17:35

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
E1642941	% Solids	100		%	0.0	10/08/19 14:30	10/09/19 8:40	EPA 200.2





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID:** PSP-TB-02

**Lab ID:** E193705-02

**Station ID:**

**Matrix:** Trip Blank - Water

**Date Collected:** 9/11/19 17:30

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 16:13	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 16:13	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 16:13	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 16:13	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 16:13	EPA 8260C
75-01-4	Vinyl chloride	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 16:13	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP01-SW**

**Lab ID: E193705-03**

**Station ID: PSP01**

**Matrix: Surface Water**

**Date Collected: 9/10/19 9:44**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	27		ug/L	0.50	9/16/19 15:18	9/16/19 18:24	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	1.8		ug/L	0.50	9/16/19 15:18	9/16/19 18:24	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	5.9		ug/L	0.50	9/16/19 15:18	9/16/19 18:24	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 18:24	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	6.3		ug/L	0.50	9/16/19 15:18	9/16/19 18:24	EPA 8260C
75-01-4	Vinyl chloride	0.52		ug/L	0.50	9/16/19 15:18	9/16/19 18:24	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP01-SW-DUP**

**Lab ID: E193705-04**

**Station ID: PSP01**

**Matrix: Surface Water**

**Date Collected: 9/10/19 9:45**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	28		ug/L	0.50	9/16/19 15:18	9/16/19 18:50	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	1.8		ug/L	0.50	9/16/19 15:18	9/16/19 18:50	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	5.8		ug/L	0.50	9/16/19 15:18	9/16/19 18:50	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 18:50	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	6.4		ug/L	0.50	9/16/19 15:18	9/16/19 18:50	EPA 8260C
75-01-4	Vinyl chloride	0.54		ug/L	0.50	9/16/19 15:18	9/16/19 18:50	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP02-SW**

**Lab ID: E193705-05**

**Station ID: PSP02**

**Matrix: Surface Water**

**Date Collected: 9/10/19 9:26**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	6.8		ug/L	0.50	9/16/19 15:18	9/16/19 19:16	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	5.4		ug/L	0.50	9/16/19 15:18	9/16/19 19:16	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	16		ug/L	0.50	9/16/19 15:18	9/16/19 19:16	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 19:16	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	7.4		ug/L	0.50	9/16/19 15:18	9/16/19 19:16	EPA 8260C
75-01-4	Vinyl chloride	0.26	J, Q-2	ug/L	0.50	9/16/19 15:18	9/16/19 19:16	EPA 8260C





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP03-SW**

**Lab ID: E193705-06**

**Station ID: PSP03**

**Matrix: Surface Water**

**Date Collected: 9/10/19 9:18**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	9.6		ug/L	0.50	9/16/19 15:18	9/17/19 0:05	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	12		ug/L	0.50	9/16/19 15:18	9/17/19 0:05	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	88		ug/L	0.50	9/16/19 15:18	9/17/19 0:05	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/17/19 0:05	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	33		ug/L	0.50	9/16/19 15:18	9/17/19 0:05	EPA 8260C
75-01-4	Vinyl chloride	0.84		ug/L	0.50	9/16/19 15:18	9/17/19 0:05	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP04-SW**

**Lab ID: E193705-07**

**Station ID: PSP04**

**Matrix: Surface Water**

**Date Collected: 9/10/19 9:10**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	40		ug/L	0.50	9/16/19 15:18	9/16/19 19:43	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	20		ug/L	0.50	9/16/19 15:18	9/16/19 19:43	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	49		ug/L	0.50	9/16/19 15:18	9/16/19 19:43	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 19:43	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	31		ug/L	0.50	9/16/19 15:18	9/16/19 19:43	EPA 8260C
75-01-4	Vinyl chloride	1.3		ug/L	0.50	9/16/19 15:18	9/16/19 19:43	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP05-SW**

**Lab ID: E193705-08**

**Station ID: PSP05**

**Matrix: Surface Water**

**Date Collected: 9/10/19 10:40**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	8.0		ug/L	0.50	9/16/19 15:18	9/16/19 20:09	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	5.3		ug/L	0.50	9/16/19 15:18	9/16/19 20:09	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	8.6		ug/L	0.50	9/16/19 15:18	9/16/19 20:09	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 20:09	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	6.2		ug/L	0.50	9/16/19 15:18	9/16/19 20:09	EPA 8260C
75-01-4	Vinyl chloride	0.27	J, Q-2	ug/L	0.50	9/16/19 15:18	9/16/19 20:09	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP06-SW**

**Lab ID: E193705-09**

**Station ID: PSP06**

**Matrix: Surface Water**

**Date Collected: 9/10/19 10:53**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	6.9		ug/L	0.50	9/16/19 15:18	9/16/19 20:35	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	6.0		ug/L	0.50	9/16/19 15:18	9/16/19 20:35	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	6.6		ug/L	0.50	9/16/19 15:18	9/16/19 20:35	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 20:35	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	6.2		ug/L	0.50	9/16/19 15:18	9/16/19 20:35	EPA 8260C
75-01-4	Vinyl chloride	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 20:35	EPA 8260C





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP07-SW**

**Lab ID: E193705-10**

**Station ID: PSP07**

**Matrix: Surface Water**

**Date Collected: 9/10/19 11:00**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	7.4		ug/L	0.50	9/16/19 15:18	9/16/19 21:01	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	6.6		ug/L	0.50	9/16/19 15:18	9/16/19 21:01	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	7.5		ug/L	0.50	9/16/19 15:18	9/16/19 21:01	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 21:01	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	7.1		ug/L	0.50	9/16/19 15:18	9/16/19 21:01	EPA 8260C
75-01-4	Vinyl chloride	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 21:01	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP08-SW**

**Lab ID: E193705-11**

**Station ID: PSP08**

**Matrix: Surface Water**

**Date Collected: 9/10/19 9:00**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	28		ug/L	0.50	9/16/19 15:18	9/16/19 21:28	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	17		ug/L	0.50	9/16/19 15:18	9/16/19 21:28	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	44		ug/L	0.50	9/16/19 15:18	9/16/19 21:28	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 21:28	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	24		ug/L	0.50	9/16/19 15:18	9/16/19 21:28	EPA 8260C
75-01-4	Vinyl chloride	1.2		ug/L	0.50	9/16/19 15:18	9/16/19 21:28	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP09-SW**

**Lab ID: E193705-12**

**Station ID: PSP09**

**Matrix: Surface Water**

**Date Collected: 9/10/19 8:41**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	24		ug/L	0.50	9/16/19 15:18	9/16/19 16:39	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	15		ug/L	0.50	9/16/19 15:18	9/16/19 16:39	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	36		ug/L	0.50	9/16/19 15:18	9/16/19 16:39	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 16:39	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	20		ug/L	0.50	9/16/19 15:18	9/16/19 16:39	EPA 8260C
75-01-4	Vinyl chloride	1.1		ug/L	0.50	9/16/19 15:18	9/16/19 16:39	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP10-GW**

**Lab ID: E193705-13**

**Station ID: PSP10**

**Matrix: Groundwater**

**Date Collected: 9/11/19 16:48**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.13	J, Q-2	ug/L	0.50	9/16/19 15:18	9/16/19 21:54	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 21:54	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 21:54	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 21:54	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	0.14	J, Q-2	ug/L	0.50	9/16/19 15:18	9/16/19 21:54	EPA 8260C
75-01-4	Vinyl chloride	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 21:54	EPA 8260C





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP10-SF**

**Lab ID: E193705-14**

**Station ID: PSP10**

**Matrix: Surface Soil**

**Date Collected: 9/11/19 11:55**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.79	U, J, QI-1	ug/kg dry	0.79	9/12/19 14:41	9/16/19 18:34	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	0.79	U, J, QI-1	ug/kg dry	0.79	9/12/19 14:41	9/16/19 18:34	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.79	U, J, QI-1	ug/kg dry	0.79	9/12/19 14:41	9/16/19 18:34	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.79	U, J, QI-1	ug/kg dry	0.79	9/12/19 14:41	9/16/19 18:34	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	0.79	U, J, QI-1	ug/kg dry	0.79	9/12/19 14:41	9/16/19 18:34	EPA 8260C
75-01-4	Vinyl chloride	0.79	U, J, QI-1	ug/kg dry	0.79	9/12/19 14:41	9/16/19 18:34	EPA 8260C



# UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Physical Properties

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP10-SF**

**Lab ID: E193705-14**

**Station ID: PSP10**

**Matrix: Surface Soil**

**Date Collected: 9/11/19 11:55**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
E1642941	% Solids	85		%	0.0	10/08/19 14:30	10/09/19 8:40	EPA 200.2



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP11-SF**

**Lab ID: E193705-15**

**Station ID: PSP11**

**Matrix: Surface Soil**

**Date Collected: 9/11/19 11:25**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.92	U	ug/kg dry	0.92	9/12/19 14:44	9/16/19 19:01	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	0.92	U	ug/kg dry	0.92	9/12/19 14:44	9/16/19 19:01	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.92	U	ug/kg dry	0.92	9/12/19 14:44	9/16/19 19:01	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.92	U	ug/kg dry	0.92	9/12/19 14:44	9/16/19 19:01	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	0.92	U	ug/kg dry	0.92	9/12/19 14:44	9/16/19 19:01	EPA 8260C
75-01-4	Vinyl chloride	0.92	U	ug/kg dry	0.92	9/12/19 14:44	9/16/19 19:01	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Physical Properties

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID:** PSP11-SF

**Lab ID:** E193705-15

**Station ID:** PSP11

**Matrix:** Surface Soil

**Date Collected:** 9/11/19 11:25

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
E1642941	% Solids	82		%	0.0	10/08/19 14:30	10/09/19 8:40	EPA 200.2





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP11-SF-DUP**

**Lab ID: E193705-16**

**Station ID: PSP11**

**Matrix: Surface Soil**

**Date Collected: 9/11/19 11:40**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.85	U	ug/kg dry	0.85	9/12/19 14:48	9/16/19 19:28	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	0.85	U	ug/kg dry	0.85	9/12/19 14:48	9/16/19 19:28	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.85	U	ug/kg dry	0.85	9/12/19 14:48	9/16/19 19:28	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.85	U	ug/kg dry	0.85	9/12/19 14:48	9/16/19 19:28	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	0.85	U	ug/kg dry	0.85	9/12/19 14:48	9/16/19 19:28	EPA 8260C
75-01-4	Vinyl chloride	0.85	U	ug/kg dry	0.85	9/12/19 14:48	9/16/19 19:28	EPA 8260C



# UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Physical Properties

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID:** PSP11-SF-DUP

**Lab ID:** E193705-16

**Station ID:** PSP11

**Matrix:** Surface Soil

**Date Collected:** 9/11/19 11:40

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
E1642941	% Solids	85		%	0.0	10/08/19 14:30	10/09/19 8:40	EPA 200.2



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP12-GW**

**Lab ID: E193705-17**

**Station ID: PSP12**

**Matrix: Groundwater**

**Date Collected: 9/11/19 16:21**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 22:20	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 22:20	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.29	J, Q-2	ug/L	0.50	9/16/19 15:18	9/16/19 22:20	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 22:20	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	0.18	J, Q-2	ug/L	0.50	9/16/19 15:18	9/16/19 22:20	EPA 8260C
75-01-4	Vinyl chloride	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 22:20	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP12-SF**

**Lab ID: E193705-18**

**Station ID: PSP12**

**Matrix: Surface Soil**

**Date Collected: 9/11/19 10:55**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.80	U	ug/kg dry	0.80	9/12/19 14:52	9/16/19 19:55	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	0.80	U	ug/kg dry	0.80	9/12/19 14:52	9/16/19 19:55	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.80	U	ug/kg dry	0.80	9/12/19 14:52	9/16/19 19:55	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.80	U	ug/kg dry	0.80	9/12/19 14:52	9/16/19 19:55	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	0.80	U	ug/kg dry	0.80	9/12/19 14:52	9/16/19 19:55	EPA 8260C
75-01-4	Vinyl chloride	0.80	U	ug/kg dry	0.80	9/12/19 14:52	9/16/19 19:55	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Physical Properties

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID:** PSP12-SF

**Lab ID:** E193705-18

**Station ID:** PSP12

**Matrix:** Surface Soil

**Date Collected:** 9/11/19 10:55

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
E1642941	% Solids	93		%	0.0	10/08/19 14:30	10/09/19 8:40	EPA 200.2





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP13-SF**

**Lab ID: E193705-19**

**Station ID: PSP13**

**Matrix: Surface Soil**

**Date Collected: 9/11/19 9:30**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.87	U	ug/kg dry	0.87	9/12/19 14:57	9/16/19 16:45	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	0.87	U	ug/kg dry	0.87	9/12/19 14:57	9/16/19 16:45	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.87	U	ug/kg dry	0.87	9/12/19 14:57	9/16/19 16:45	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.87	U	ug/kg dry	0.87	9/12/19 14:57	9/16/19 16:45	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	0.87	U	ug/kg dry	0.87	9/12/19 14:57	9/16/19 16:45	EPA 8260C
75-01-4	Vinyl chloride	0.87	U	ug/kg dry	0.87	9/12/19 14:57	9/16/19 16:45	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Physical Properties

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID:** PSP13-SF

**Lab ID:** E193705-19

**Station ID:** PSP13

**Matrix:** Surface Soil

**Date Collected:** 9/11/19 9:30

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
E1642941	% Solids	84		%	0.0	10/08/19 14:30	10/09/19 8:40	EPA 200.2



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP22-SEEP**

**Lab ID: E193705-20**

**Station ID: PSP22**

**Matrix: Surface Water**

**Date Collected: 9/10/19 11:12**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.25	J, Q-2	ug/L	0.50	9/16/19 15:18	9/16/19 22:46	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	2.8		ug/L	0.50	9/16/19 15:18	9/16/19 22:46	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	3.0		ug/L	0.50	9/16/19 15:18	9/16/19 22:46	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 22:46	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	2.1		ug/L	0.50	9/16/19 15:18	9/16/19 22:46	EPA 8260C
75-01-4	Vinyl chloride	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 22:46	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID:** PSP-EB-01

**Lab ID:** E193707-01

**Station ID:**

**Matrix:** Equipment Rinse Blank

**Date Collected:** 9/12/19 17:14

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 15:08	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 15:08	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 15:08	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 15:08	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 15:08	EPA 8260C
75-01-4	Vinyl chloride	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 15:08	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID:** PSP-TB-03

**Lab ID:** E193707-02

**Station ID:**

**Matrix:** Trip Blank - Water

**Date Collected:** 9/12/19 17:15

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 15:35	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 15:35	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 15:35	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 15:35	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 15:35	EPA 8260C
75-01-4	Vinyl chloride	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 15:35	EPA 8260C





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP11-GW**

**Lab ID: E193707-03**

**Station ID: PSP11**

**Matrix: Groundwater**

**Date Collected: 9/12/19 14:50**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 23:13	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 23:13	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 23:13	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 23:13	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 23:13	EPA 8260C
75-01-4	Vinyl chloride	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 23:13	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP13-GW**

**Lab ID: E193707-04**

**Station ID: PSP13**

**Matrix: Groundwater**

**Date Collected: 9/12/19 15:15**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 23:39	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 23:39	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 23:39	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 23:39	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 23:39	EPA 8260C
75-01-4	Vinyl chloride	0.50	U	ug/L	0.50	9/16/19 15:18	9/16/19 23:39	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP17-GW**

**Lab ID: E193707-05**

**Station ID: PSP17**

**Matrix: Groundwater**

**Date Collected: 9/12/19 14:15**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	110		ug/L	5.0	9/18/19 11:38	9/18/19 18:38	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	140		ug/L	5.0	9/18/19 11:38	9/18/19 18:38	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	460		ug/L	5.0	9/18/19 11:38	9/18/19 18:38	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	5.0	U	ug/L	5.0	9/18/19 11:38	9/18/19 18:38	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	640		ug/L	5.0	9/18/19 11:38	9/18/19 18:38	EPA 8260C
75-01-4	Vinyl chloride	5.0	U	ug/L	5.0	9/18/19 11:38	9/18/19 18:38	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP24-GW**

**Lab ID: E193707-06**

**Station ID: PSP24**

**Matrix: Groundwater**

**Date Collected: 9/12/19 13:35**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 16:01	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 16:01	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 16:01	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 16:01	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 16:01	EPA 8260C
75-01-4	Vinyl chloride	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 16:01	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID:** PSP24-GW-DUP

**Lab ID:** E193707-07

**Station ID:** PSP24

**Matrix:** Groundwater

**Date Collected:** 9/12/19 13:37

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 16:27	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 16:27	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 16:27	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 16:27	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 16:27	EPA 8260C
75-01-4	Vinyl chloride	0.50	U	ug/L	0.50	9/18/19 11:38	9/18/19 16:27	EPA 8260C





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP25-GW**

**Lab ID: E193707-08**

**Station ID: PSP25**

**Matrix: Groundwater**

**Date Collected: 9/12/19 9:35**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	220		ug/L	2.5	9/18/19 11:38	9/18/19 18:12	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	74		ug/L	2.5	9/18/19 11:38	9/18/19 18:12	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	140		ug/L	2.5	9/18/19 11:38	9/18/19 18:12	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	2.5	U	ug/L	2.5	9/18/19 11:38	9/18/19 18:12	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	120		ug/L	2.5	9/18/19 11:38	9/18/19 18:12	EPA 8260C
75-01-4	Vinyl chloride	2.5	U	ug/L	2.5	9/18/19 11:38	9/18/19 18:12	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

**Volatile Organics (VOA) - Quality Control**

**US-EPA, Region 4, LSASD**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	--------------------	-------	----------------	------------------	------	----------------	-----	--------------	-------

**Batch 1909024 - V 5035 VOA Soil and Waste Prep**

**Blank (1909024-BLK1)**

Prepared: 09/14/19 Analyzed: 09/16/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	U	1.0	ug/kg wet							U
cis-1,2-Dichloroethene	U	1.0	"							U
Tetrachloroethene (Tetrachloroethylene)	U	1.0	"							U
trans-1,2-Dichloroethene	U	1.0	"							U
Trichloroethene (Trichloroethylene)	U	1.0	"							U
Vinyl chloride	U	1.0	"							U

**Blank (1909024-BLK2)**

Prepared: 09/12/19 Analyzed: 09/16/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	U	1.0	ug/kg wet							U
cis-1,2-Dichloroethene	U	1.0	"							U
Tetrachloroethene (Tetrachloroethylene)	U	1.0	"							U
trans-1,2-Dichloroethene	U	1.0	"							U
Trichloroethene (Trichloroethylene)	U	1.0	"							U
Vinyl chloride	U	1.0	"							U

**LCS (1909024-BS1)**

Prepared: 09/14/19 Analyzed: 09/16/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	19.460		ug/kg	20.000		97.3	78.3-131
cis-1,2-Dichloroethene	22.560		"	20.000		113	84.2-122
Tetrachloroethene (Tetrachloroethylene)	20.020		"	20.000		100	80.8-125
trans-1,2-Dichloroethene	22.390		"	20.000		112	83.4-123
Trichloroethene (Trichloroethylene)	22.050		"	20.000		110	82.6-128
Vinyl chloride	21.610		"	20.000		108	62.8-145

**Matrix Spike (1909024-MS1)**

Source: E193705-19

Prepared: 09/12/19 Analyzed: 09/16/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	25.930		ug/kg	20.000	0.0000	130	33.1-141
cis-1,2-Dichloroethene	23.960		"	20.000	0.0000	120	36.8-126
Tetrachloroethene (Tetrachloroethylene)	16.690		"	20.000	0.0000	83.4	41-116
trans-1,2-Dichloroethene	25.350		"	20.000	0.0000	127	31.2-129
Trichloroethene (Trichloroethylene)	24.180		"	20.000	0.0000	121	23-125
Vinyl chloride	23.900		"	20.000	0.0000	120	25.4-146



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

**Volatile Organics (VOA) - Quality Control**

**US-EPA, Region 4, LSASD**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	--------------------	-------	----------------	------------------	------	----------------	-----	--------------	-------

**Batch 1909024 - V 5035 VOA Soil and Waste Prep**

**Matrix Spike Dup (1909024-MSD1)**

Source: E193705-19

Prepared: 09/12/19 Analyzed: 09/16/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	28.870		ug/kg	20.000	0.0000	144	33.1-141	10.7	42.2	QM-2
cis-1,2-Dichloroethene	24.440		"	20.000	0.0000	122	36.8-126	1.98	49	
Tetrachloroethene (Tetrachloroethylene)	22.650		"	20.000	0.0000	113	41-116	30.3	51.7	
trans-1,2-Dichloroethene	17.300		"	20.000	0.0000	86.5	31.2-129	37.7	47.3	
Trichloroethene (Trichloroethylene)	25.090		"	20.000	0.0000	125	23-125	3.69	47.1	
Vinyl chloride	26.480		"	20.000	0.0000	132	25.4-146	10.2	33.1	

**MRL Verification (1909024-PS1)**

Prepared: 09/14/19 Analyzed: 09/16/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	0.99000		ug/kg	1.0000		99.0	58.3-151			MRL-3
cis-1,2-Dichloroethene	0.95000		"	1.0000		95.0	64.2-142			MRL-3
Tetrachloroethene (Tetrachloroethylene)	1.0300		"	1.0000		103	60.8-145			MRL-3
trans-1,2-Dichloroethene	0.83000		"	1.0000		83.0	63.4-143			MRL-3
Trichloroethene (Trichloroethylene)	0.99000		"	1.0000		99.0	62.6-148			MRL-3
Vinyl chloride	0.96000		"	1.0000		96.0	42.8-165			MRL-3

**Batch 1909029 - V 5030B VOA Wtr Prep**

**Blank (1909029-BLK1)**

Prepared & Analyzed: 09/16/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	U	0.50	ug/L							U
cis-1,2-Dichloroethene	U	0.50	"							U
Tetrachloroethene (Tetrachloroethylene)	U	0.50	"							U
trans-1,2-Dichloroethene	U	0.50	"							U
Trichloroethene (Trichloroethylene)	U	0.50	"							U
Vinyl chloride	U	0.50	"							U

**LCS (1909029-BS1)**

Prepared & Analyzed: 09/16/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	19.750		ug/L	20.000		98.8	85.4-116			
cis-1,2-Dichloroethene	19.160		"	20.000		95.8	87.6-115			
Tetrachloroethene (Tetrachloroethylene)	19.430		"	20.000		97.2	85.1-113			
trans-1,2-Dichloroethene	19.070		"	20.000		95.4	86.6-114			
Trichloroethene (Trichloroethylene)	18.840		"	20.000		94.2	87.8-114			
Vinyl chloride	19.000		"	20.000		95.0	78.8-115			



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

**Volatile Organics (VOA) - Quality Control**

**US-EPA, Region 4, LSASD**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	--------------------	-------	----------------	------------------	------	----------------	-----	--------------	-------

**Batch 1909029 - V 5030B VOA Wtr Prep**

**Matrix Spike (1909029-MS1)**

Source: E193705-12

Prepared & Analyzed: 09/16/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	34.840		ug/L	10.233	24.040	106	87.5-133
cis-1,2-Dichloroethene	25.620		"	10.233	14.800	106	85.3-127
Tetrachloroethene (Tetrachloroethylene)	46.760		"	10.233	35.610	109	66.4-149
trans-1,2-Dichloroethene	10.610		"	10.233	0.0000	104	86.8-128
Trichloroethene (Trichloroethylene)	29.920		"	10.233	19.780	99.1	87.2-128
Vinyl chloride	12.150		"	10.233	1.0900	108	84.5-135

**Matrix Spike Dup (1909029-MSD1)**

Source: E193705-12

Prepared & Analyzed: 09/16/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	36.550		ug/L	10.233	24.040	122	87.5-133	4.79	12.8
cis-1,2-Dichloroethene	26.720		"	10.233	14.800	116	85.3-127	4.20	10.8
Tetrachloroethene (Tetrachloroethylene)	44.630		"	10.233	35.610	88.1	66.4-149	4.66	13.4
trans-1,2-Dichloroethene	10.790		"	10.233	0.0000	105	86.8-128	1.68	11
Trichloroethene (Trichloroethylene)	29.960		"	10.233	19.780	99.5	87.2-128	0.134	15
Vinyl chloride	12.440		"	10.233	1.0900	111	84.5-135	2.36	14.1

**MRL Verification (1909029-PS1)**

Prepared & Analyzed: 09/16/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	2.1200		ug/L	2.0000		106	65.4-136
cis-1,2-Dichloroethene	1.9700		"	2.0000		98.5	67.6-135
Tetrachloroethene (Tetrachloroethylene)	1.8900		"	2.0000		94.5	65.1-133
trans-1,2-Dichloroethene	1.9500		"	2.0000		97.5	66.6-134
Trichloroethene (Trichloroethylene)	1.9200		"	2.0000		96.0	67.8-134
Vinyl chloride	2.2100		"	2.0000		110	58.8-135

**Batch 1909041 - V 5030B VOA Wtr Prep**

**Blank (1909041-BLK1)**

Prepared & Analyzed: 09/18/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	U	0.50	ug/L						U
cis-1,2-Dichloroethene	U	0.50	"						U
Tetrachloroethene (Tetrachloroethylene)	U	0.50	"						U
trans-1,2-Dichloroethene	U	0.50	"						U
Trichloroethene (Trichloroethylene)	U	0.50	"						U
Vinyl chloride	U	0.50	"						U



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

**Volatile Organics (VOA) - Quality Control**

**US-EPA, Region 4, LSASD**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	--------------------	-------	----------------	------------------	------	----------------	-----	--------------	-------

**Batch 1909041 - V 5030B VOA Wtr Prep**

**LCS (1909041-BS1)**

Prepared & Analyzed: 09/18/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	20.960		ug/L	20.000		105	85.4-116			
cis-1,2-Dichloroethene	21.030		"	20.000		105	87.6-115			
Tetrachloroethene (Tetrachloroethylene)	19.620		"	20.000		98.1	85.1-113			
trans-1,2-Dichloroethene	20.370		"	20.000		102	86.6-114			
Trichloroethene (Trichloroethylene)	18.050		"	20.000		90.2	87.8-114			
Vinyl chloride	19.450		"	20.000		97.2	78.8-115			

**Matrix Spike (1909041-MS1)**

Source: E193707-07

Prepared & Analyzed: 09/18/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	11.960		ug/L	10.233	0.0000	117	87.5-133			
cis-1,2-Dichloroethene	10.940		"	10.233	0.0000	107	85.3-127			
Tetrachloroethene (Tetrachloroethylene)	11.470		"	10.233	0.0000	112	66.4-149			
trans-1,2-Dichloroethene	10.930		"	10.233	0.0000	107	86.8-128			
Trichloroethene (Trichloroethylene)	9.9400		"	10.233	0.0000	97.1	87.2-128			
Vinyl chloride	10.670		"	10.233	0.0000	104	84.5-135			

**Matrix Spike Dup (1909041-MSD1)**

Source: E193707-07

Prepared & Analyzed: 09/18/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	11.500		ug/L	10.233	0.0000	112	87.5-133	3.92	12.8	
cis-1,2-Dichloroethene	10.610		"	10.233	0.0000	104	85.3-127	3.06	10.8	
Tetrachloroethene (Tetrachloroethylene)	11.470		"	10.233	0.0000	112	66.4-149	0.00	13.4	
trans-1,2-Dichloroethene	11.020		"	10.233	0.0000	108	86.8-128	0.820	11	
Trichloroethene (Trichloroethylene)	10.190		"	10.233	0.0000	99.6	87.2-128	2.48	15	
Vinyl chloride	10.080		"	10.233	0.0000	98.5	84.5-135	5.69	14.1	

**MRL Verification (1909041-PS1)**

Prepared & Analyzed: 09/18/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	0.54000		ug/L	0.50000		108	65.4-136			MRL-2
cis-1,2-Dichloroethene	0.45000		"	0.50000		90.0	67.6-135			MRL-2
Tetrachloroethene (Tetrachloroethylene)	0.52000		"	0.50000		104	65.1-133			MRL-2
trans-1,2-Dichloroethene	0.48000		"	0.50000		96.0	66.6-134			MRL-2
Trichloroethene (Trichloroethylene)	0.53000		"	0.50000		106	67.8-134			MRL-2
Vinyl chloride	0.54000		"	0.50000		108	58.8-135			MRL-2





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
Region 4 Laboratory Services and Applied Science Division  
980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

**Physical Properties (PHYSP) - Quality Control**  
**US-EPA, Region 4, LSASD**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 1910028 - M % Solids										
Duplicate (1910028-DUP1)		Source: E193705-19			Prepared: 10/08/19 Analyzed: 10/09/19					
EPA 200.2										
% Solids	84.114	0.0	%		84.145			0.0368	10	



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Kristin Trapp

**Notes and Definitions for QC Samples**

U	The analyte was not detected at or above the reporting limit.
MRL-2	MRL verification for Non-Potable Water matrix
MRL-3	MRL verification for Soil matrix
QM-2	Matrix Spike Recovery greater than method control limits



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

**December 17, 2019**

**MEMORANDUM**

**SUBJECT:** FINAL Analytical Report  
 Project: 19-0323, Patterson Street Solvent Plume

**FROM:** Jeffrey Hendel  
 LSB Organic Chemistry Section Chief

**THRU:** Sandra Aker, Chief  
 Laboratory Services Branch

**TO:** Cathy Amoroso

This report is being reissued to correct sample descriptive information that was not accepted by the Region 4 Data Archival and ReTrieval (D.A.R.T.) system. Some or all of these results were previously reported. Please substitute the corrected results for those results previously reported. Please refer to the Report Narrative for more details.

Attached are the final results for the analytical groups listed below. This report shall not be reproduced except in full without approval of the Region 4 laboratory. These analyses were performed in accordance with the Laboratory Services Branch's Laboratory Operations and Quality Assurance Manual (LSB LOQAM) found at [www.epa.gov/region4/sesd/asbsop](http://www.epa.gov/region4/sesd/asbsop). Any unique project data quality objectives specified in writing by the data requestor have also been incorporated into the data unless otherwise noted in the Report Narrative. Chemistry data have been verified based on the LSB LOQAM specifications and have been qualified by this laboratory if the applicable quality control criteria were not met. Verification is defined in Chapter 5 of the LSB LOQAM. For a listing of specific data qualifiers and explanations, please refer to the Data Qualifier Definitions included in this report. The reported results are accurate within the limits of the method(s) and are representative only of the samples as received by the laboratory.

Analyses Included in this report:

Method Used:

Accreditations:

**Volatile Organics (VOA)**

Volatile organic compounds

EPA TO-15 (Air)

ISO



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
Region 4 Laboratory Services and Applied Science Division  
980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

**Report Narrative for Project: 19-0323**

11/19/19 KT VOA Soil and Water: This data has been reissued to include only those analytes requested by the project leader. This report replaces E193705, E193707 PHYS VOA FINAL 10 15 19 1802.pdf.

---

**Report Narrative for Work Order: E193801**

This report is being re-released since sample station IDs have been updated as requested by the project lead. No analytical results were affected. This report replaces Project 19-0323, E193801 VOA 10 01 19 0955.

---

**Sample Disposal Policy**

Due to limited space for long term sample storage, LSB's policy is to dispose of samples on a periodic schedule. Air samples collected in summa canisters will be disposed of 30 days following the issuance of this report. All other sample media including original samples, sample extracts and or digestates will be disposed of, in accordance with applicable regulations, 60 days from the date of this report.

This sample disposal policy does not apply to criminal samples which are held until the laboratory is notified by the criminal investigators that case development and litigation are complete.

These samples may be held in the laboratory's custody for a longer period of time. If samples require storage beyond the 60-day period, please contact the Sample Control Coordinator by e-mail at [R4SampleCustody@epa.gov](mailto:R4SampleCustody@epa.gov).

cc: Nardina Turner



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

### SAMPLES INCLUDED IN THIS REPORT

#### Project: 19-0323, Patterson Street Solvent Plume

Sample ID	Laboratory ID	Matrix	Date Collected	Date Received
PSP10-AA	E193801-01	Ambient Air	9/11/19 14:42	9/13/19 16:28
PSP10-AA-DUP	E193801-02	Ambient Air	9/11/19 14:42	9/13/19 16:28
PSP10-SG	E193801-03	Soil Gas	9/12/19 17:52	9/13/19 16:28
PSP11-AA	E193801-04	Ambient Air	9/10/19 14:06	9/13/19 16:28
PSP11-SG	E193801-05	Soil Gas	9/12/19 18:38	9/13/19 16:28
PSP12-AA	E193801-06	Ambient Air	9/10/19 15:37	9/13/19 16:28
PSP12-SG	E193801-07	Soil Gas	9/13/19 11:00	9/13/19 16:28
PSP13-AA	E193801-08	Ambient Air	9/10/19 15:01	9/13/19 16:28
PSP13-SG	E193801-09	Soil Gas	9/13/19 09:30	9/13/19 16:28
PSP13-SG-SPLIT	E193801-10	Soil Gas	9/13/19 09:30	9/13/19 16:28
PSP14-SG	E193801-11	Soil Gas	9/12/19 13:56	9/13/19 16:28
PSP15-SG	E193801-12	Soil Gas	9/12/19 12:28	9/13/19 16:28
PSP16-AA	E193801-13	Ambient Air	9/10/19 15:36	9/13/19 16:28
PSP16-SG	E193801-14	Soil Gas	9/12/19 16:56	9/13/19 16:28
PSP19-SG	E193801-15	Soil Gas	9/12/19 13:11	9/13/19 16:28
PSP20-SG	E193801-16	Soil Gas	9/12/19 15:53	9/13/19 16:28
PSP21-AA	E193801-17	Ambient Air	9/10/19 14:13	9/13/19 16:28
PSP21-SG	E193801-18	Soil Gas	9/12/19 11:35	9/13/19 16:28
PSP24-AA	E193801-19	Ambient Air	9/10/19 15:30	9/13/19 16:28
PSP24-SG	E193801-20	Soil Gas	9/13/19 10:16	9/13/19 16:28
PSP25-SG	E193801-21	Soil Gas	9/12/19 14:55	9/13/19 16:28
PSP26-AA	E193801-22	Ambient Air	9/11/19 14:47	9/13/19 16:28
PSP27-SG	E193801-23	Soil Gas	9/13/19 08:11	9/13/19 16:28
PSP28-AA	E193801-24	Ambient Air	9/10/19 15:03	9/13/19 16:28
PSP28-SG	E193801-25	Soil Gas	9/13/19 07:26	9/13/19 16:28





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

### DATA QUALIFIER DEFINITIONS

U	The analyte was not detected at or above the reporting limit.
D-4	MRL elevated due to interferences.
J	The identification of the analyte is acceptable; the reported value is an estimate.
Q-2	Result greater than MDL but less than MRL.
QI-1	Internal standard was outside of method control limits.

### ACRONYMS AND ABBREVIATIONS

CAS	Chemical Abstracts Service  Note: Analytes with no known CAS identifiers have been assigned codes beginning with "E", the EPA ID as assigned by the EPA Substance Registry System ( <a href="http://www.epa.gov/srs">www.epa.gov/srs</a> ), or beginning with "R4-", a unique identifier assigned by the EPA Region 4 laboratory.
MDL	Method Detection Limit - The minimum concentration of a substance (an analyte) that can be measured and reported with a 99% confidence that the analyte concentration is greater than zero.
MRL	Minimum Reporting Limit - Analyte concentration that corresponds to the lowest demonstrated level of acceptable quantitation. The MRL is sample-specific and accounts for preparation weights and volumes, dilutions, and moisture content of soil/sediments.
TIC	Tentatively Identified Compound - An analyte identified based on a match with the instrument software's mass spectral library. A calibration standard has not been analyzed to confirm the compound's identification or the estimated concentration reported.

#### ACCREDITATIONS:

ISO	ASB is accredited by ISO/IEC 17025, including an amplification for forensic accreditation through ANSI-ASQ National Accreditation Board.  Refer to the certificate and scope of accreditation AT-1644 at: <a href="http://www.epa.gov/aboutepa/about-region-4s-science-and-ecosystem-support-division-sesd">http://www.epa.gov/aboutepa/about-region-4s-science-and-ecosystem-support-division-sesd</a>
NR	The EPA Region 4 Laboratory has not requested accreditation for this test.



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP10-AA**

**Lab ID: E193801-01**

**Station ID: PSP10**

**Matrix: Ambient Air**

**Date Collected: 9/11/19 14:42**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.55		ug/m3	0.23	9/16/19 11:32	9/17/19 18:20	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.36		ug/m3	0.21	9/16/19 11:32	9/17/19 18:20	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.90		ug/m3	0.36	9/16/19 11:32	9/17/19 18:20	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.21	U	ug/m3	0.21	9/16/19 11:32	9/17/19 18:20	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.63		ug/m3	0.29	9/16/19 11:32	9/17/19 18:20	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	9/16/19 11:32	9/17/19 18:20	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP10-AA-DUP**

**Lab ID: E193801-02**

**Station ID: PSP10**

**Matrix: Ambient Air**

**Date Collected: 9/11/19 14:42**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.54		ug/m3	0.23	9/16/19 11:36	9/17/19 20:03	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.34		ug/m3	0.21	9/16/19 11:36	9/17/19 20:03	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	1.2		ug/m3	0.37	9/16/19 11:36	9/17/19 20:03	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.40		ug/m3	0.21	9/16/19 11:36	9/17/19 20:03	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.66		ug/m3	0.29	9/16/19 11:36	9/17/19 20:03	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	9/16/19 11:36	9/17/19 20:03	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP10-SG**

**Lab ID: E193801-03**

**Station ID: PSP10**

**Matrix: Soil Gas**

**Date Collected: 9/12/19 17:52**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.13	J, Q-2	ug/m3	0.22	9/16/19 9:49	9/21/19 8:44	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.20	U	ug/m3	0.20	9/16/19 9:49	9/21/19 8:44	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	2.1		ug/m3	0.34	9/16/19 9:49	9/21/19 8:44	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.20	U	ug/m3	0.20	9/16/19 9:49	9/21/19 8:44	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.64		ug/m3	0.27	9/16/19 9:49	9/21/19 8:44	EPA TO-15
75-01-4	Vinyl chloride	0.13	U	ug/m3	0.13	9/16/19 9:49	9/21/19 8:44	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP11-AA**

**Lab ID: E193801-04**

**Station ID: PSP11**

**Matrix: Ambient Air**

**Date Collected: 9/10/19 14:06**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.20	J, Q-2	ug/m3	0.24	9/16/19 11:39	9/17/19 20:54	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.13	J, Q-2	ug/m3	0.22	9/16/19 11:39	9/17/19 20:54	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.38		ug/m3	0.37	9/16/19 11:39	9/17/19 20:54	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.22	U	ug/m3	0.22	9/16/19 11:39	9/17/19 20:54	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.21	J, Q-2	ug/m3	0.30	9/16/19 11:39	9/17/19 20:54	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	9/16/19 11:39	9/17/19 20:54	EPA TO-15





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP11-SG**

**Lab ID: E193801-05**

**Station ID: PSP11**

**Matrix: Soil Gas**

**Date Collected: 9/12/19 18:38**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.31		ug/m3	0.22	9/16/19 12:11	9/21/19 9:35	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.12	J, Q-2	ug/m3	0.20	9/16/19 12:11	9/21/19 9:35	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	1.0		ug/m3	0.35	9/16/19 12:11	9/21/19 9:35	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.20	U	ug/m3	0.20	9/16/19 12:11	9/21/19 9:35	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.36		ug/m3	0.28	9/16/19 12:11	9/21/19 9:35	EPA TO-15
75-01-4	Vinyl chloride	0.13	U	ug/m3	0.13	9/16/19 12:11	9/21/19 9:35	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP12-AA**

**Lab ID: E193801-06**

**Station ID: PSP12**

**Matrix: Ambient Air**

**Date Collected: 9/10/19 15:37**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	1.0		ug/m3	0.23	9/16/19 11:42	9/17/19 19:11	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.59		ug/m3	0.21	9/16/19 11:42	9/17/19 19:11	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	1.5		ug/m3	0.36	9/16/19 11:42	9/17/19 19:11	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.21	U	ug/m3	0.21	9/16/19 11:42	9/17/19 19:11	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.92		ug/m3	0.28	9/16/19 11:42	9/17/19 19:11	EPA TO-15
75-01-4	Vinyl chloride	0.13	U	ug/m3	0.13	9/16/19 11:42	9/17/19 19:11	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP12-SG**

**Lab ID: E193801-07**

**Station ID: PSP12**

**Matrix: Soil Gas**

**Date Collected: 9/13/19 11:00**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.21	U	ug/m3	0.21	9/16/19 12:14	9/21/19 10:27	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.19	U	ug/m3	0.19	9/16/19 12:14	9/21/19 10:27	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	9.5		ug/m3	0.33	9/16/19 12:14	9/21/19 10:27	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.19	U	ug/m3	0.19	9/16/19 12:14	9/21/19 10:27	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.26	U	ug/m3	0.26	9/16/19 12:14	9/21/19 10:27	EPA TO-15
75-01-4	Vinyl chloride	0.13	U	ug/m3	0.13	9/16/19 12:14	9/21/19 10:27	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP13-AA**

**Lab ID: E193801-08**

**Station ID: PSP13**

**Matrix: Ambient Air**

**Date Collected: 9/10/19 15:01**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.34		ug/m3	0.24	9/16/19 11:46	9/17/19 22:36	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.20	J, Q-2	ug/m3	0.22	9/16/19 11:46	9/17/19 22:36	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.67		ug/m3	0.38	9/16/19 11:46	9/17/19 22:36	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.22	U	ug/m3	0.22	9/16/19 11:46	9/17/19 22:36	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.35		ug/m3	0.30	9/16/19 11:46	9/17/19 22:36	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	9/16/19 11:46	9/17/19 22:36	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP13-SG**

**Lab ID: E193801-09**

**Station ID: PSP13**

**Matrix: Soil Gas**

**Date Collected: 9/13/19 9:30**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.39		ug/m3	0.24	9/16/19 12:17	9/21/19 11:18	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.097	J, Q-2	ug/m3	0.22	9/16/19 12:17	9/21/19 11:18	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.64		ug/m3	0.37	9/16/19 12:17	9/21/19 11:18	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.22	U	ug/m3	0.22	9/16/19 12:17	9/21/19 11:18	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.33		ug/m3	0.29	9/16/19 12:17	9/21/19 11:18	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	9/16/19 12:17	9/21/19 11:18	EPA TO-15





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP13-SG-SPLIT**

**Lab ID: E193801-10**

**Station ID: PSP13**

**Matrix: Soil Gas**

**Date Collected: 9/13/19 9:30**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.39		ug/m3	0.24	9/16/19 12:20	9/18/19 23:15	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.13	J, Q-2	ug/m3	0.22	9/16/19 12:20	9/18/19 23:15	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.66		ug/m3	0.37	9/16/19 12:20	9/18/19 23:15	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.22	U	ug/m3	0.22	9/16/19 12:20	9/18/19 23:15	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.36		ug/m3	0.29	9/16/19 12:20	9/18/19 23:15	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	9/16/19 12:20	9/18/19 23:15	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP14-SG**

**Lab ID: E193801-11**

**Station ID: PSP14**

**Matrix: Soil Gas**

**Date Collected: 9/12/19 13:56**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	700		ug/m3	2.3	9/16/19 12:23	9/18/19 21:35	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	740		ug/m3	2.1	9/16/19 12:23	9/18/19 21:35	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	3600		ug/m3	3.5	9/16/19 12:23	9/18/19 21:35	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	11		ug/m3	2.1	9/16/19 12:23	9/18/19 21:35	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	3300		ug/m3	2.8	9/16/19 12:23	9/18/19 21:35	EPA TO-15
75-01-4	Vinyl chloride	35		ug/m3	1.3	9/16/19 12:23	9/18/19 21:35	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

Project: 19-0323, Patterson Street Solvent Plume

Sample ID: PSP15-SG

Lab ID: E193801-12

Station ID: PSP15

Matrix: Soil Gas

Date Collected: 9/12/19 12:28

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	1.2	U, D-4	ug/m3	1.2	9/16/19 12:26	9/18/19 14:25	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.20	U	ug/m3	0.20	9/16/19 12:26	9/18/19 14:25	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	3.5		ug/m3	0.35	9/16/19 12:26	9/18/19 14:25	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.20	U	ug/m3	0.20	9/16/19 12:26	9/18/19 14:25	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.37		ug/m3	0.28	9/16/19 12:26	9/18/19 14:25	EPA TO-15
75-01-4	Vinyl chloride	0.72		ug/m3	0.13	9/16/19 12:26	9/18/19 14:25	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP16-AA**

**Lab ID: E193801-13**

**Station ID: PSP16**

**Matrix: Ambient Air**

**Date Collected: 9/10/19 15:36**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.23	U	ug/m3	0.23	9/16/19 11:48	9/17/19 23:28	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.21	U	ug/m3	0.21	9/16/19 11:48	9/17/19 23:28	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.21	J, Q-2	ug/m3	0.36	9/16/19 11:48	9/17/19 23:28	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.21	U	ug/m3	0.21	9/16/19 11:48	9/17/19 23:28	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.099	J, Q-2	ug/m3	0.29	9/16/19 11:48	9/17/19 23:28	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	9/16/19 11:48	9/17/19 23:28	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP16-SG**

**Lab ID: E193801-14**

**Station ID: PSP16**

**Matrix: Soil Gas**

**Date Collected: 9/12/19 16:56**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	3.0		ug/m3	0.23	9/16/19 12:29	9/18/19 20:07	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.21	U	ug/m3	0.21	9/16/19 12:29	9/18/19 20:07	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	190		ug/m3	0.35	9/16/19 12:29	9/18/19 20:07	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.21	U	ug/m3	0.21	9/16/19 12:29	9/18/19 20:07	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.42		ug/m3	0.28	9/16/19 12:29	9/18/19 20:07	EPA TO-15
75-01-4	Vinyl chloride	12		ug/m3	0.13	9/16/19 12:29	9/18/19 20:07	EPA TO-15





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP19-SG**

**Lab ID: E193801-15**

**Station ID: PSP19**

**Matrix: Soil Gas**

**Date Collected: 9/12/19 13:11**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	3.6	U, D-4	ug/m3	3.6	9/16/19 12:31	9/19/19 0:06	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.23	U	ug/m3	0.23	9/16/19 12:31	9/19/19 0:06	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	3.8		ug/m3	0.39	9/16/19 12:31	9/19/19 0:06	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.23	U	ug/m3	0.23	9/16/19 12:31	9/19/19 0:06	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	1.1		ug/m3	0.31	9/16/19 12:31	9/19/19 0:06	EPA TO-15
75-01-4	Vinyl chloride	4.1		ug/m3	0.15	9/16/19 12:31	9/19/19 0:06	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP20-SG**

**Lab ID: E193801-16**

**Station ID: PSP20**

**Matrix: Soil Gas**

**Date Collected: 9/12/19 15:53**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	150		ug/m3	0.22	9/16/19 12:34	9/18/19 20:51	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	17		ug/m3	0.21	9/16/19 12:34	9/18/19 20:51	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	340		ug/m3	0.35	9/16/19 12:34	9/18/19 20:51	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	4.5		ug/m3	0.21	9/16/19 12:34	9/18/19 20:51	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	330		ug/m3	0.28	9/16/19 12:34	9/18/19 20:51	EPA TO-15
75-01-4	Vinyl chloride	3.1		ug/m3	0.13	9/16/19 12:34	9/18/19 20:51	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP21-AA**

**Lab ID: E193801-17**

**Station ID: PSP21**

**Matrix: Ambient Air**

**Date Collected: 9/10/19 14:13**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.56		ug/m3	0.24	9/16/19 11:52	9/18/19 0:19	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.40		ug/m3	0.22	9/16/19 11:52	9/18/19 0:19	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	3.1		ug/m3	0.38	9/16/19 11:52	9/18/19 0:19	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.22	U	ug/m3	0.22	9/16/19 11:52	9/18/19 0:19	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	1.2		ug/m3	0.30	9/16/19 11:52	9/18/19 0:19	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	9/16/19 11:52	9/18/19 0:19	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP21-SG**

**Lab ID: E193801-18**

**Station ID: PSP21**

**Matrix: Soil Gas**

**Date Collected: 9/12/19 11:35**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.14	J, Q-2	ug/m3	0.22	9/16/19 12:37	9/20/19 8:38	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.20	U	ug/m3	0.20	9/16/19 12:37	9/20/19 8:38	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	7.4		ug/m3	0.35	9/16/19 12:37	9/20/19 8:38	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.20	U	ug/m3	0.20	9/16/19 12:37	9/20/19 8:38	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.25	J, Q-2	ug/m3	0.27	9/16/19 12:37	9/20/19 8:38	EPA TO-15
75-01-4	Vinyl chloride	0.59		ug/m3	0.13	9/16/19 12:37	9/20/19 8:38	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP24-AA**

**Lab ID: E193801-19**

**Station ID: PSP24**

**Matrix: Ambient Air**

**Date Collected: 9/10/19 15:30**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.27		ug/m3	0.23	9/16/19 11:54	9/18/19 1:10	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.16	J, Q-2	ug/m3	0.21	9/16/19 11:54	9/18/19 1:10	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.86		ug/m3	0.36	9/16/19 11:54	9/18/19 1:10	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.21	U	ug/m3	0.21	9/16/19 11:54	9/18/19 1:10	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.31		ug/m3	0.28	9/16/19 11:54	9/18/19 1:10	EPA TO-15
75-01-4	Vinyl chloride	0.13	U	ug/m3	0.13	9/16/19 11:54	9/18/19 1:10	EPA TO-15





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP24-SG**

**Lab ID: E193801-20**

**Station ID: PSP24**

**Matrix: Soil Gas**

**Date Collected: 9/13/19 10:16**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.23	U	ug/m3	0.23	9/16/19 12:40	9/19/19 9:40	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.22	U	ug/m3	0.22	9/16/19 12:40	9/19/19 9:40	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.96		ug/m3	0.37	9/16/19 12:40	9/19/19 9:40	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.22	U	ug/m3	0.22	9/16/19 12:40	9/19/19 9:40	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.27	J, Q-2	ug/m3	0.29	9/16/19 12:40	9/19/19 9:40	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	9/16/19 12:40	9/19/19 9:40	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP25-SG**

**Lab ID: E193801-21**

**Station ID: PSP25**

**Matrix: Soil Gas**

**Date Collected: 9/12/19 14:55**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	11		ug/m3	2.3	9/16/19 12:43	9/18/19 21:04	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	1.9	J, QI-1	ug/m3	0.21	9/16/19 12:43	9/21/19 13:52	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	1200		ug/m3	3.6	9/16/19 12:43	9/18/19 21:04	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.46	J, QI-1	ug/m3	0.21	9/16/19 12:43	9/21/19 13:52	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	19		ug/m3	2.9	9/16/19 12:43	9/18/19 21:04	EPA TO-15
75-01-4	Vinyl chloride	0.14	U, J, QI-1	ug/m3	0.14	9/16/19 12:43	9/21/19 13:52	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP26-AA**

**Lab ID: E193801-22**

**Station ID: PSP26**

**Matrix: Ambient Air**

**Date Collected: 9/11/19 14:47**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.60		ug/m3	0.23	9/16/19 11:57	9/18/19 2:02	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.22		ug/m3	0.21	9/16/19 11:57	9/18/19 2:02	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.65		ug/m3	0.36	9/16/19 11:57	9/18/19 2:02	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.21	U	ug/m3	0.21	9/16/19 11:57	9/18/19 2:02	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.52		ug/m3	0.29	9/16/19 11:57	9/18/19 2:02	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	9/16/19 11:57	9/18/19 2:02	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP27-SG**

**Lab ID: E193801-23**

**Station ID: PSP27**

**Matrix: Soil Gas**

**Date Collected: 9/13/19 8:11**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	32		ug/m3	0.23	9/16/19 12:46	9/20/19 9:29	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.21	U	ug/m3	0.21	9/16/19 12:46	9/20/19 9:29	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	21		ug/m3	0.35	9/16/19 12:46	9/20/19 9:29	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.21	U	ug/m3	0.21	9/16/19 12:46	9/20/19 9:29	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	3.1		ug/m3	0.28	9/16/19 12:46	9/20/19 9:29	EPA TO-15
75-01-4	Vinyl chloride	0.13	U	ug/m3	0.13	9/16/19 12:46	9/20/19 9:29	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP28-AA**

**Lab ID: E193801-24**

**Station ID: PSP28**

**Matrix: Ambient Air**

**Date Collected: 9/10/19 15:03**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	3.7		ug/m3	0.24	9/16/19 12:00	9/18/19 2:53	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	2.1		ug/m3	0.22	9/16/19 12:00	9/18/19 2:53	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	6.6		ug/m3	0.38	9/16/19 12:00	9/18/19 2:53	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.22	U	ug/m3	0.22	9/16/19 12:00	9/18/19 2:53	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	3.3		ug/m3	0.30	9/16/19 12:00	9/18/19 2:53	EPA TO-15
75-01-4	Vinyl chloride	0.16		ug/m3	0.14	9/16/19 12:00	9/18/19 2:53	EPA TO-15





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

## Volatile Organics

**Project: 19-0323, Patterson Street Solvent Plume**

**Sample ID: PSP28-SG**

**Lab ID: E193801-25**

**Station ID: PSP28**

**Matrix: Soil Gas**

**Date Collected: 9/13/19 7:26**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	1.1		ug/m3	0.23	9/16/19 12:48	9/19/19 10:27	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.21	U	ug/m3	0.21	9/16/19 12:48	9/19/19 10:27	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	6.0		ug/m3	0.36	9/16/19 12:48	9/19/19 10:27	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.21	U	ug/m3	0.21	9/16/19 12:48	9/19/19 10:27	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.33		ug/m3	0.29	9/16/19 12:48	9/19/19 10:27	EPA TO-15
75-01-4	Vinyl chloride	0.17		ug/m3	0.14	9/16/19 12:48	9/19/19 10:27	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

**Volatile Organics (VOA) - Quality Control**

**US-EPA, Region 4, LSASD**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	--------------------	-------	----------------	------------------	------	----------------	-----	--------------	-------

**Batch 1909033 - V TO-15 Air Canister**

**Blank (1909033-BLK1)**

Prepared: 09/16/19 Analyzed: 09/17/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	U	0.095	ug/m3							U
cis-1,2-Dichloroethene	U	0.087	"							U
Tetrachloroethene (Tetrachloroethylene)	U	0.15	"							U
trans-1,2-Dichloroethene	U	0.087	"							U
Trichloroethene (Trichloroethylene)	U	0.12	"							U
Vinyl chloride	U	0.056	"							U

**LCS (1909033-BS1)**

Prepared: 09/03/19 Analyzed: 09/17/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	2.4693		ppbv	2.4000	103	70-140		
cis-1,2-Dichloroethene	2.1872		"	2.2000	99.4	70-136		
Tetrachloroethene (Tetrachloroethylene)	2.2343		"	2.2000	102	68-148		
trans-1,2-Dichloroethene	2.1855		"	2.2000	99.3	73-136		
Trichloroethene (Trichloroethylene)	2.3183		"	2.2000	105	69-137		
Vinyl chloride	2.1332		"	2.2000	97.0	62-151		

**LCS Dup (1909033-BSD1)**

Prepared: 09/03/19 Analyzed: 09/17/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	2.4976		ppbv	2.4000	104	70-140	1.14	25
cis-1,2-Dichloroethene	2.1711		"	2.2000	98.7	70-136	0.739	25
Tetrachloroethene (Tetrachloroethylene)	2.2341		"	2.2000	102	68-148	0.0121	25
trans-1,2-Dichloroethene	2.2556		"	2.2000	103	73-136	3.16	25
Trichloroethene (Trichloroethylene)	2.2971		"	2.2000	104	69-137	0.920	25
Vinyl chloride	2.1267		"	2.2000	96.7	62-151	0.306	25

**Duplicate (1909033-DUP1)**

Source: E193801-04

Prepared: 09/16/19 Analyzed: 09/17/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	0.21801	0.24	ug/m3	0.20137		7.94	25	Q-2, J
cis-1,2-Dichloroethene	0.11460	0.22	"	0.13302		14.9	25	Q-2, J
Tetrachloroethene (Tetrachloroethylene)	0.39103	0.37	"	0.38340		1.97	25	
trans-1,2-Dichloroethene	U	0.22	"	U			25	U
Trichloroethene (Trichloroethylene)	0.23867	0.30	"	0.21156		12.0	25	Q-2, J
Vinyl chloride	U	0.14	"	U			25	U



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

**Volatile Organics (VOA) - Quality Control**

**US-EPA, Region 4, LSASD**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	--------------------	-------	----------------	------------------	------	----------------	-----	--------------	-------

**Batch 1909033 - V TO-15 Air Canister**

**MRL Verification (1909033-PS3)**

Prepared: 09/03/19 Analyzed: 09/17/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	0.024480		ppbv	0.024000		102	50-160			MRL-5
cis-1,2-Dichloroethene	0.026750		"	0.022000		122	50-156			MRL-5
Tetrachloroethene (Tetrachloroethylene)	0.021670		"	0.022000		98.5	50-150			MRL-5
trans-1,2-Dichloroethene	0.019190		"	0.022000		87.2	53-156			MRL-5
Trichloroethene (Trichloroethylene)	0.018680		"	0.022000		84.9	50-150			MRL-5
Vinyl chloride	0.018610		"	0.022000		84.6	50-150			MRL-5

**Batch 1909034 - V TO-15 Air Canister**

**Blank (1909034-BLK1)**

Prepared: 09/16/19 Analyzed: 09/18/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	U	0.095	ug/m3							U
cis-1,2-Dichloroethene	U	0.087	"							U
Tetrachloroethene (Tetrachloroethylene)	U	0.15	"							U
trans-1,2-Dichloroethene	U	0.087	"							U
Trichloroethene (Trichloroethylene)	U	0.12	"							U
Vinyl chloride	U	0.056	"							U

**Blank (1909034-BLK2)**

Prepared: 09/16/19 Analyzed: 09/18/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	U	0.95	ug/m3							U
cis-1,2-Dichloroethene	U	0.87	"							U
Tetrachloroethene (Tetrachloroethylene)	U	1.5	"							U
trans-1,2-Dichloroethene	U	0.87	"							U
Trichloroethene (Trichloroethylene)	U	1.2	"							U
Vinyl chloride	U	0.56	"							U

**LCS (1909034-BS1)**

Prepared: 09/03/19 Analyzed: 09/18/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	2.4951		ppbv	2.4000		104	70-140			
cis-1,2-Dichloroethene	2.1405		"	2.2000		97.3	70-136			
Tetrachloroethene (Tetrachloroethylene)	2.2931		"	2.2000		104	68-148			
trans-1,2-Dichloroethene	2.2160		"	2.2000		101	73-136			
Trichloroethene (Trichloroethylene)	2.3405		"	2.2000		106	69-137			
Vinyl chloride	2.1136		"	2.2000		96.1	62-151			



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
Region 4 Laboratory Services and Applied Science Division  
980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

**Volatile Organics (VOA) - Quality Control**

**US-EPA, Region 4, LSASD**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	--------------------	-------	----------------	------------------	------	----------------	-----	--------------	-------

**Batch 1909034 - V TO-15 Air Canister**

**LCS Dup (1909034-BSD1)**

Prepared: 09/03/19 Analyzed: 09/18/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	2.5021		ppbv	2.4000		104	70-140	0.280	25	
cis-1,2-Dichloroethene	2.1863		"	2.2000		99.4	70-136	2.12	25	
Tetrachloroethene (Tetrachloroethylene)	2.2616		"	2.2000		103	68-148	1.38	25	
trans-1,2-Dichloroethene	2.2106		"	2.2000		100	73-136	0.244	25	
Trichloroethene (Trichloroethylene)	2.3227		"	2.2000		106	69-137	0.762	25	
Vinyl chloride	2.1345		"	2.2000		97.0	62-151	0.984	25	

**Duplicate (1909034-DUP1)**

Source: E193801-23RE1

Prepared: 09/16/19 Analyzed: 09/18/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	27.505	2.3	ug/m3	28.883		4.89	25			
cis-1,2-Dichloroethene	U	2.1	"	U			25			U
Tetrachloroethene (Tetrachloroethylene)	20.432	3.5	"	20.662		1.12	25			
trans-1,2-Dichloroethene	U	2.1	"	U			25			U
Trichloroethene (Trichloroethylene)	2.8583	2.8	"	2.8672		0.311	25			
Vinyl chloride	U	1.3	"	U			25			U

**MRL Verification (1909034-PS3)**

Prepared: 09/03/19 Analyzed: 09/18/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	0.023440		ppbv	0.024000		97.7	50-160			MRL-5
cis-1,2-Dichloroethene	0.016850		"	0.022000		76.6	50-156			MRL-5
Tetrachloroethene (Tetrachloroethylene)	0.022000		"	0.022000		100	50-150			MRL-5
trans-1,2-Dichloroethene	0.021610		"	0.022000		98.2	53-156			MRL-5
Trichloroethene (Trichloroethylene)	0.022170		"	0.022000		101	50-150			MRL-5
Vinyl chloride	0.020320		"	0.022000		92.4	50-150			MRL-5

**Batch 1909040 - V TO-15 Air Canister**

**Blank (1909040-BLK1)**

Prepared: 09/16/19 Analyzed: 09/18/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	U	0.095	ug/m3							U
cis-1,2-Dichloroethene	U	0.087	"							U
Tetrachloroethene (Tetrachloroethylene)	U	0.15	"							U
trans-1,2-Dichloroethene	U	0.087	"							U
Trichloroethene (Trichloroethylene)	U	0.12	"							U
Vinyl chloride	U	0.056	"							U



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

**Volatile Organics (VOA) - Quality Control**

**US-EPA, Region 4, LSASD**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	-----------------	-------	-------------	---------------	------	-------------	-----	-----------	-------

**Batch 1909040 - V TO-15 Air Canister**

**Blank (1909040-BLK2)**

Prepared: 09/16/19 Analyzed: 09/18/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	U	0.95	ug/m3							U
cis-1,2-Dichloroethene	U	0.87	"							U
Tetrachloroethene (Tetrachloroethylene)	U	1.5	"							U
trans-1,2-Dichloroethene	U	0.87	"							U
Trichloroethene (Trichloroethylene)	U	1.2	"							U
Vinyl chloride	U	0.56	"							U

**LCS (1909040-BS1)**

Prepared: 09/03/19 Analyzed: 09/18/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	2.6773	ppbv	2.4000	112	70-140
cis-1,2-Dichloroethene	2.3034	"	2.2000	105	70-136
Tetrachloroethene (Tetrachloroethylene)	2.2538	"	2.2000	102	68-148
trans-1,2-Dichloroethene	2.3452	"	2.2000	107	73-136
Trichloroethene (Trichloroethylene)	2.3444	"	2.2000	107	69-137
Vinyl chloride	2.5797	"	2.2000	117	62-151

**LCS Dup (1909040-BSD1)**

Prepared: 09/03/19 Analyzed: 09/18/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	2.6506	ppbv	2.4000	110	70-140	0.999	25
cis-1,2-Dichloroethene	2.2866	"	2.2000	104	70-136	0.731	25
Tetrachloroethene (Tetrachloroethylene)	2.2768	"	2.2000	103	68-148	1.02	25
trans-1,2-Dichloroethene	2.3228	"	2.2000	106	73-136	0.959	25
Trichloroethene (Trichloroethylene)	2.3570	"	2.2000	107	69-137	0.533	25
Vinyl chloride	2.6478	"	2.2000	120	62-151	2.60	25

**Duplicate (1909040-DUP1)**

Source: E193801-11RE1

Prepared: 09/16/19 Analyzed: 09/18/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	734.64	2.3	ug/m3	704.42	4.20	25
cis-1,2-Dichloroethene	762.00	2.1	"	744.68	2.30	25
Tetrachloroethene (Tetrachloroethylene)	3558.8	3.5	"	3568.3	0.269	25
trans-1,2-Dichloroethene	11.573	2.1	"	11.481	0.798	25
Trichloroethene (Trichloroethylene)	3303.4	2.8	"	3301.3	0.0615	25
Vinyl chloride	33.748	1.3	"	34.580	2.43	25





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

**Volatile Organics (VOA) - Quality Control**

**US-EPA, Region 4, LSASD**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	--------------------	-------	----------------	------------------	------	----------------	-----	--------------	-------

**Batch 1909040 - V TO-15 Air Canister**

**MRL Verification (1909040-PS2)**

Prepared: 09/03/19 Analyzed: 09/18/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	0.032090		ppbv	0.024000		134	50-160			MRL-5
cis-1,2-Dichloroethene	0.027960		"	0.022000		127	50-156			MRL-5
Tetrachloroethene (Tetrachloroethylene)	0.028110		"	0.022000		128	50-150			MRL-5
trans-1,2-Dichloroethene	0.028180		"	0.022000		128	53-156			MRL-5
Trichloroethene (Trichloroethylene)	0.027460		"	0.022000		125	50-150			MRL-5
Vinyl chloride	0.029940		"	0.022000		136	50-150			MRL-5

**Batch 1909042 - V TO-15 Air Canister**

**Blank (1909042-BLK1)**

Prepared: 09/16/19 Analyzed: 09/19/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	U	0.095	ug/m3							U
cis-1,2-Dichloroethene	U	0.087	"							U
Tetrachloroethene (Tetrachloroethylene)	U	0.15	"							U
trans-1,2-Dichloroethene	U	0.087	"							U
Trichloroethene (Trichloroethylene)	U	0.12	"							U
Vinyl chloride	U	0.056	"							U

**LCS (1909042-BS1)**

Prepared: 09/03/19 Analyzed: 09/19/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	2.4006		ppbv	2.4000		100	70-140			
cis-1,2-Dichloroethene	2.0907		"	2.2000		95.0	70-136			
Tetrachloroethene (Tetrachloroethylene)	2.3607		"	2.2000		107	68-148			
trans-1,2-Dichloroethene	2.1273		"	2.2000		96.7	73-136			
Trichloroethene (Trichloroethylene)	2.3778		"	2.2000		108	69-137			
Vinyl chloride	2.0128		"	2.2000		91.5	62-151			

**LCS Dup (1909042-BSD1)**

Prepared: 09/03/19 Analyzed: 09/19/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	2.4633		ppbv	2.4000		103	70-140	2.58	25	
cis-1,2-Dichloroethene	2.1438		"	2.2000		97.4	70-136	2.51	25	
Tetrachloroethene (Tetrachloroethylene)	2.3667		"	2.2000		108	68-148	0.253	25	
trans-1,2-Dichloroethene	2.1359		"	2.2000		97.1	73-136	0.403	25	
Trichloroethene (Trichloroethylene)	2.3859		"	2.2000		108	69-137	0.338	25	
Vinyl chloride	2.0699		"	2.2000		94.1	62-151	2.80	25	



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

**Volatile Organics (VOA) - Quality Control**

**US-EPA, Region 4, LSASD**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	--------------------	-------	----------------	------------------	------	----------------	-----	--------------	-------

**Batch 1909042 - V TO-15 Air Canister**

**MRL Verification (1909042-PS1)**

Prepared: 09/03/19 Analyzed: 09/19/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	0.022780		ppbv	0.024000		94.9	50-160			MRL-5
cis-1,2-Dichloroethene	0.022250		"	0.022000		101	50-156			MRL-5
Tetrachloroethene (Tetrachloroethylene)	0.026850		"	0.022000		122	50-150			MRL-5
trans-1,2-Dichloroethene	0.022860		"	0.022000		104	53-156			MRL-5
Trichloroethene (Trichloroethylene)	0.022330		"	0.022000		102	50-150			MRL-5
Vinyl chloride	0.020000		"	0.022000		90.9	50-150			MRL-5

**Batch 1909045 - V TO-15 Air Canister**

**Blank (1909045-BLK1)**

Prepared: 09/20/19 Analyzed: 09/21/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	U	0.095	ug/m3							U
cis-1,2-Dichloroethene	U	0.087	"							U
Tetrachloroethene (Tetrachloroethylene)	U	0.15	"							U
trans-1,2-Dichloroethene	U	0.087	"							U
Trichloroethene (Trichloroethylene)	U	0.12	"							U
Vinyl chloride	U	0.056	"							U

**LCS (1909045-BS1)**

Prepared: 09/03/19 Analyzed: 09/21/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	2.4009		ppbv	2.4000		100	70-140			
cis-1,2-Dichloroethene	2.0626		"	2.2000		93.8	70-136			
Tetrachloroethene (Tetrachloroethylene)	2.5006		"	2.2000		114	68-148			
trans-1,2-Dichloroethene	2.0799		"	2.2000		94.5	73-136			
Trichloroethene (Trichloroethylene)	2.3951		"	2.2000		109	69-137			
Vinyl chloride	1.9203		"	2.2000		87.3	62-151			

**LCS Dup (1909045-BSD1)**

Prepared: 09/03/19 Analyzed: 09/21/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	2.4347		ppbv	2.4000		101	70-140	1.40	25	
cis-1,2-Dichloroethene	2.1146		"	2.2000		96.1	70-136	2.49	25	
Tetrachloroethene (Tetrachloroethylene)	2.4461		"	2.2000		111	68-148	2.20	25	
trans-1,2-Dichloroethene	2.1158		"	2.2000		96.2	73-136	1.71	25	
Trichloroethene (Trichloroethylene)	2.4026		"	2.2000		109	69-137	0.309	25	
Vinyl chloride	1.9890		"	2.2000		90.4	62-151	3.52	25	



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

**Volatile Organics (VOA) - Quality Control**

**US-EPA, Region 4, LSASD**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	--------------------	-------	----------------	------------------	------	----------------	-----	--------------	-------

**Batch 1909045 - V TO-15 Air Canister**

**Duplicate (1909045-DUP1)**

**Source: E193801-09**

Prepared: 09/16/19 Analyzed: 09/21/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	0.39098	0.24	ug/m3		0.38901			0.505	25	
cis-1,2-Dichloroethene	0.11265	0.22	"		0.097376			14.5	25	Q-2, J
Tetrachloroethene (Tetrachloroethylene)	0.63201	0.37	"		0.64297			1.72	25	J, QI-1
trans-1,2-Dichloroethene	U	0.22	"		U				25	U
Trichloroethene (Trichloroethylene)	0.33179	0.29	"		0.32658			1.58	25	J, QI-1
Vinyl chloride	U	0.14	"		U				25	U

**MRL Verification (1909045-PS1)**

Prepared: 09/03/19 Analyzed: 09/21/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	0.019980		ppbv	0.024000	83.2	50-160				MRL-5
cis-1,2-Dichloroethene	0.023640		"	0.022000	107	50-156				MRL-5
Tetrachloroethene (Tetrachloroethylene)	0.025310		"	0.022000	115	50-150				MRL-5
trans-1,2-Dichloroethene	0.021020		"	0.022000	95.5	53-156				MRL-5
Trichloroethene (Trichloroethylene)	0.020820		"	0.022000	94.6	50-150				MRL-5
Vinyl chloride	0.019120		"	0.022000	86.9	50-150				MRL-5



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 19-0323

Project: 19-0323, Patterson Street Solvent Plume - Reported by Jeffrey Hendel

**Notes and Definitions for QC Samples**

U	The analyte was not detected at or above the reporting limit.
J	The identification of the analyte is acceptable; the reported value is an estimate.
MRL-5	MRL verification for Air matrix
Q-2	Result greater than MDL but less than MRL.
QI-1	Internal standard was outside of method control limits.



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

**December 16, 2019**

**4LSASD-LSB**

**MEMORANDUM**

**SUBJECT:** FINAL Analytical Report  
 Project: 20-0055, Patterson Street Solvent Plume

**FROM:** Kristin Trapp  
 OCS Analyst

**THRU:** Jeffrey Hendel, Chief  
 LSB Organic Chemistry Section

**TO:** Cathy Amoroso

Attached are the final results for the analytical groups listed below. This report shall not be reproduced except in full without approval of the Region 4 laboratory. These analyses were performed in accordance with the Laboratory Services Branch's Laboratory Operations and Quality Assurance Manual (LSB LOQAM) found at [www.epa.gov/region4/sesd/asbsop](http://www.epa.gov/region4/sesd/asbsop). Any unique project data quality objectives specified in writing by the data requestor have also been incorporated into the data unless otherwise noted in the Report Narrative. Chemistry data have been verified based on the LSB LOQAM specifications and have been qualified by this laboratory if the applicable quality control criteria were not met. Verification is defined in Chapter 5 of the LSB LOQAM. For a listing of specific data qualifiers and explanations, please refer to the Data Qualifier Definitions included in this report. The reported results are accurate within the limits of the method(s) and are representative only of the samples as received by the laboratory.

Analyses Included in this report:

Method Used:

Accreditations:

**Volatile Organics (VOA)**

Volatile organic compounds

EPA TO-15 (Air)

ISO





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
Region 4 Laboratory Services and Applied Science Division  
980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

---

### **Sample Disposal Policy**

Due to limited space for long term sample storage, LSB's policy is to dispose of samples on a periodic schedule. Air samples collected in summa canisters will be disposed of 30 days following the issuance of this report. All other sample media including original samples, sample extracts and or digestates will be disposed of, in accordance with applicable regulations, 60 days from the date of this report.

This sample disposal policy does not apply to criminal samples which are held until the laboratory is notified by the criminal investigators that case development and litigation are complete.

These samples may be held in the laboratory's custody for a longer period of time. If samples require storage beyond the 60-day period, please contact the Sample Control Coordinator by e-mail at [R4SampleCustody@epa.gov](mailto:R4SampleCustody@epa.gov).

cc: Nardina Turner



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

**SAMPLES INCLUDED IN THIS REPORT**

**Project: 20-0055, Patterson Street Solvent Plume**

Sample ID	Laboratory ID	Matrix	Date Collected	Date Received
PSP14-AA	E194902-02	Ambient Air	12/4/19 10:03	12/5/19 11:10
PSP14-CS	E194902-03	Crawlspace Air	12/4/19 10:03	12/5/19 11:10
PSP14-IA	E194902-04	Indoor Air	12/4/19 10:02	12/5/19 11:10
PSP20-AA	E194902-05	Ambient Air	12/4/19 08:04	12/5/19 11:10
PSP20-AA-DUP	E194902-06	Ambient Air	12/4/19 08:04	12/5/19 11:10
PSP20-CS	E194902-07	Crawlspace Air	12/4/19 08:04	12/5/19 11:10
PSP20-IA	E194902-08	Indoor Air	12/4/19 08:00	12/5/19 11:10
PSP22-AA	E194902-09	Ambient Air	12/4/19 10:05	12/5/19 11:10
PSP25-AA	E194902-10	Ambient Air	12/4/19 11:04	12/5/19 11:10
PSP25-CS	E194902-11	Crawlspace Air	12/4/19 11:03	12/5/19 11:10
PSP26-CS	E194902-12	Crawlspace Air	12/4/19 13:03	12/5/19 11:10
PSP29-AA	E194902-13	Ambient Air	12/4/19 18:21	12/5/19 11:10
PSP29-CS	E194902-14	Crawlspace Air	12/4/19 18:20	12/5/19 11:10
PSP30-CS	E194902-15	Crawlspace Air	12/4/19 11:05	12/5/19 11:10



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

### DATA QUALIFIER DEFINITIONS

U	The analyte was not detected at or above the reporting limit.
J	The identification of the analyte is acceptable; the reported value is an estimate.
Q-2	Result greater than MDL but less than MRL.

### ACRONYMS AND ABBREVIATIONS

CAS	Chemical Abstracts Service  Note: Analytes with no known CAS identifiers have been assigned codes beginning with "E", the EPA ID as assigned by the EPA Substance Registry System ( <a href="http://www.epa.gov/srs">www.epa.gov/srs</a> ), or beginning with "R4-", a unique identifier assigned by the EPA Region 4 laboratory.
MDL	Method Detection Limit - The minimum concentration of a substance (an analyte) that can be measured and reported with a 99% confidence that the analyte concentration is greater than zero.
MRL	Minimum Reporting Limit - Analyte concentration that corresponds to the lowest demonstrated level of acceptable quantitation. The MRL is sample-specific and accounts for preparation weights and volumes, dilutions, and moisture content of soil/sediments.
TIC	Tentatively Identified Compound - An analyte identified based on a match with the instrument software's mass spectral library. A calibration standard has not been analyzed to confirm the compound's identification or the estimated concentration reported.

### ACCREDITATIONS:

ISO	ASB is accredited by ISO/IEC 17025, including an amplification for forensic accreditation through ANSI-ASQ National Accreditation Board.  Refer to the certificate and scope of accreditation AT-1644 at: <a href="http://www.epa.gov/aboutepa/about-region-4s-science-and-ecosystem-support-division-sesd">http://www.epa.gov/aboutepa/about-region-4s-science-and-ecosystem-support-division-sesd</a>
NR	The EPA Region 4 Laboratory has not requested accreditation for this test.



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 20-0055, Patterson Street Solvent Plume**

**Sample ID: PSP14-AA**

**Lab ID: E194902-02**

**Station ID: PSP14**

**Matrix: Ambient Air**

**Date Collected: 12/4/19 10:03**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.33		ug/m3	0.22	12/05/19 16:04	12/10/19 6:08	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.11	J, Q-2	ug/m3	0.21	12/05/19 16:04	12/10/19 6:08	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.95		ug/m3	0.35	12/05/19 16:04	12/10/19 6:08	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.21	U	ug/m3	0.21	12/05/19 16:04	12/10/19 6:08	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.83		ug/m3	0.28	12/05/19 16:04	12/10/19 6:08	EPA TO-15
75-01-4	Vinyl chloride	0.13	U	ug/m3	0.13	12/05/19 16:04	12/10/19 6:08	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 20-0055, Patterson Street Solvent Plume**

**Sample ID: PSP14-CS**

**Lab ID: E194902-03**

**Station ID: PSP14**

**Matrix: Crawlspace Air**

**Date Collected: 12/4/19 10:03**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.35		ug/m3	0.23	12/05/19 16:46	12/10/19 16:26	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.11	J, Q-2	ug/m3	0.21	12/05/19 16:46	12/10/19 16:26	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	1.6		ug/m3	0.36	12/05/19 16:46	12/10/19 16:26	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.21	U	ug/m3	0.21	12/05/19 16:46	12/10/19 16:26	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.98		ug/m3	0.29	12/05/19 16:46	12/10/19 16:26	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	12/05/19 16:46	12/10/19 16:26	EPA TO-15





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 20-0055, Patterson Street Solvent Plume**

**Sample ID: PSP14-IA**

**Lab ID: E194902-04**

**Station ID: PSP14**

**Matrix: Indoor Air**

**Date Collected: 12/4/19 10:02**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.41		ug/m3	0.25	12/05/19 16:31	12/10/19 14:44	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.15	J, Q-2	ug/m3	0.23	12/05/19 16:31	12/10/19 14:44	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	1.1		ug/m3	0.39	12/05/19 16:31	12/10/19 14:44	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.23	U	ug/m3	0.23	12/05/19 16:31	12/10/19 14:44	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.93		ug/m3	0.31	12/05/19 16:31	12/10/19 14:44	EPA TO-15
75-01-4	Vinyl chloride	0.15	U	ug/m3	0.15	12/05/19 16:31	12/10/19 14:44	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 20-0055, Patterson Street Solvent Plume**

**Sample ID: PSP20-AA**

**Lab ID: E194902-05**

**Station ID: PSP20**

**Matrix: Ambient Air**

**Date Collected: 12/4/19 8:04**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.25		ug/m3	0.23	12/05/19 16:09	12/10/19 7:00	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.16	J, Q-2	ug/m3	0.21	12/05/19 16:09	12/10/19 7:00	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.77		ug/m3	0.36	12/05/19 16:09	12/10/19 7:00	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.21	U	ug/m3	0.21	12/05/19 16:09	12/10/19 7:00	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.38		ug/m3	0.29	12/05/19 16:09	12/10/19 7:00	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	12/05/19 16:09	12/10/19 7:00	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 20-0055, Patterson Street Solvent Plume**

**Sample ID: PSP20-AA-DUP**

**Lab ID: E194902-06**

**Station ID: PSP20**

**Matrix: Ambient Air**

**Date Collected: 12/4/19 8:04**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.25		ug/m3	0.23	12/05/19 16:14	12/10/19 7:51	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.12	J, Q-2	ug/m3	0.21	12/05/19 16:14	12/10/19 7:51	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.79		ug/m3	0.37	12/05/19 16:14	12/10/19 7:51	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.21	U	ug/m3	0.21	12/05/19 16:14	12/10/19 7:51	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.35		ug/m3	0.29	12/05/19 16:14	12/10/19 7:51	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	12/05/19 16:14	12/10/19 7:51	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 20-0055, Patterson Street Solvent Plume**

**Sample ID: PSP20-CS**

**Lab ID: E194902-07**

**Station ID: PSP20**

**Matrix: Crawlspace Air**

**Date Collected: 12/4/19 8:04**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.29		ug/m3	0.23	12/05/19 16:52	12/10/19 13:00	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.15	J, Q-2	ug/m3	0.21	12/05/19 16:52	12/10/19 13:00	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	2.8		ug/m3	0.37	12/05/19 16:52	12/10/19 13:00	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.21	U	ug/m3	0.21	12/05/19 16:52	12/10/19 13:00	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.34		ug/m3	0.29	12/05/19 16:52	12/10/19 13:00	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	12/05/19 16:52	12/10/19 13:00	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 20-0055, Patterson Street Solvent Plume**

**Sample ID: PSP20-1A**

**Lab ID: E194902-08**

**Station ID: PSP20**

**Matrix: Indoor Air**

**Date Collected: 12/4/19 8:00**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.36		ug/m3	0.24	12/05/19 16:35	12/10/19 15:35	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.17	J, Q-2	ug/m3	0.22	12/05/19 16:35	12/10/19 15:35	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	1.6		ug/m3	0.38	12/05/19 16:35	12/10/19 15:35	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.22	U	ug/m3	0.22	12/05/19 16:35	12/10/19 15:35	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.38		ug/m3	0.30	12/05/19 16:35	12/10/19 15:35	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	12/05/19 16:35	12/10/19 15:35	EPA TO-15





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 20-0055, Patterson Street Solvent Plume**

**Sample ID: PSP22-AA**

**Lab ID: E194902-09**

**Station ID: PSP22**

**Matrix: Ambient Air**

**Date Collected: 12/4/19 10:05**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.35		ug/m3	0.22	12/05/19 16:19	12/10/19 8:43	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.15	J, Q-2	ug/m3	0.21	12/05/19 16:19	12/10/19 8:43	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.99		ug/m3	0.35	12/05/19 16:19	12/10/19 8:43	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.21	U	ug/m3	0.21	12/05/19 16:19	12/10/19 8:43	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.96		ug/m3	0.28	12/05/19 16:19	12/10/19 8:43	EPA TO-15
75-01-4	Vinyl chloride	0.13	U	ug/m3	0.13	12/05/19 16:19	12/10/19 8:43	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 20-0055, Patterson Street Solvent Plume**

**Sample ID: PSP25-AA**

**Lab ID: E194902-10**

**Station ID: PSP25**

**Matrix: Ambient Air**

**Date Collected: 12/4/19 11:04**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.12	J, Q-2	ug/m3	0.22	12/05/19 16:24	12/10/19 10:26	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.20	U	ug/m3	0.20	12/05/19 16:24	12/10/19 10:26	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.24	J, Q-2	ug/m3	0.34	12/05/19 16:24	12/10/19 10:26	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.20	U	ug/m3	0.20	12/05/19 16:24	12/10/19 10:26	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.18	J, Q-2	ug/m3	0.27	12/05/19 16:24	12/10/19 10:26	EPA TO-15
75-01-4	Vinyl chloride	0.13	U	ug/m3	0.13	12/05/19 16:24	12/10/19 10:26	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 20-0055, Patterson Street Solvent Plume**

**Sample ID: PSP25-CS**

**Lab ID: E194902-11**

**Station ID: PSP25**

**Matrix: Crawlspace Air**

**Date Collected: 12/4/19 11:03**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.23	J, Q-2	ug/m3	0.24	12/05/19 17:00	12/10/19 17:18	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.22	U	ug/m3	0.22	12/05/19 17:00	12/10/19 17:18	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.68		ug/m3	0.37	12/05/19 17:00	12/10/19 17:18	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.084	J, Q-2	ug/m3	0.22	12/05/19 17:00	12/10/19 17:18	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.25	J, Q-2	ug/m3	0.29	12/05/19 17:00	12/10/19 17:18	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	12/05/19 17:00	12/10/19 17:18	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 20-0055, Patterson Street Solvent Plume**

**Sample ID: PSP26-CS**

**Lab ID: E194902-12**

**Station ID: PSP26**

**Matrix: Crawlspace Air**

**Date Collected: 12/4/19 13:03**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.36		ug/m3	0.23	12/05/19 17:06	12/10/19 13:52	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.11	J, Q-2	ug/m3	0.21	12/05/19 17:06	12/10/19 13:52	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.81		ug/m3	0.36	12/05/19 17:06	12/10/19 13:52	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.21	U	ug/m3	0.21	12/05/19 17:06	12/10/19 13:52	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.68		ug/m3	0.29	12/05/19 17:06	12/10/19 13:52	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	12/05/19 17:06	12/10/19 13:52	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 20-0055, Patterson Street Solvent Plume**

**Sample ID: PSP29-AA**

**Lab ID: E194902-13**

**Station ID: PSP29**

**Matrix: Ambient Air**

**Date Collected: 12/4/19 18:21**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.20	J, Q-2	ug/m3	0.24	12/05/19 16:27	12/10/19 11:17	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.22	U	ug/m3	0.22	12/05/19 16:27	12/10/19 11:17	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.46		ug/m3	0.38	12/05/19 16:27	12/10/19 11:17	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.22	U	ug/m3	0.22	12/05/19 16:27	12/10/19 11:17	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.39		ug/m3	0.30	12/05/19 16:27	12/10/19 11:17	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	12/05/19 16:27	12/10/19 11:17	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 20-0055, Patterson Street Solvent Plume**

**Sample ID: PSP29-CS**

**Lab ID: E194902-14**

**Station ID: PSP29**

**Matrix: Crawlspace Air**

**Date Collected: 12/4/19 18:20**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	2.8		ug/m3	0.23	12/05/19 17:12	12/10/19 18:09	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.095	J, Q-2	ug/m3	0.21	12/05/19 17:12	12/10/19 18:09	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	1.8		ug/m3	0.36	12/05/19 17:12	12/10/19 18:09	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.11	J, Q-2	ug/m3	0.21	12/05/19 17:12	12/10/19 18:09	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	1.1		ug/m3	0.29	12/05/19 17:12	12/10/19 18:09	EPA TO-15
75-01-4	Vinyl chloride	0.14	U	ug/m3	0.14	12/05/19 17:12	12/10/19 18:09	EPA TO-15





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 20-0055, Patterson Street Solvent Plume**

**Sample ID: PSP30-CS**

**Lab ID: E194902-15**

**Station ID: PSP30**

**Matrix: Crawlspace Air**

**Date Collected: 12/4/19 11:05**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.23		ug/m3	0.22	12/05/19 17:16	12/10/19 19:01	EPA TO-15
156-59-2	cis-1,2-Dichloroethene	0.20	U	ug/m3	0.20	12/05/19 17:16	12/10/19 19:01	EPA TO-15
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.51		ug/m3	0.35	12/05/19 17:16	12/10/19 19:01	EPA TO-15
156-60-5	trans-1,2-Dichloroethene	0.20	U	ug/m3	0.20	12/05/19 17:16	12/10/19 19:01	EPA TO-15
79-01-6	Trichloroethene (Trichloroethylene)	0.44		ug/m3	0.28	12/05/19 17:16	12/10/19 19:01	EPA TO-15
75-01-4	Vinyl chloride	0.13	U	ug/m3	0.13	12/05/19 17:16	12/10/19 19:01	EPA TO-15



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

**Volatile Organics (VOA) - Quality Control**

**US-EPA, Region 4, LSASD**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	-----------------	-------	-------------	---------------	------	-------------	-----	-----------	-------

**Batch 1912018 - V TO-15 Air Canister**

**Blank (1912018-BLK1)**

Prepared: 12/05/19 Analyzed: 12/10/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	U	0.095	ug/m3							U
cis-1,2-Dichloroethene	U	0.087	"							U
Tetrachloroethene (Tetrachloroethylene)	U	0.15	"							U
trans-1,2-Dichloroethene	U	0.087	"							U
Trichloroethene (Trichloroethylene)	U	0.12	"							U
Vinyl chloride	U	0.056	"							U

**LCS (1912018-BS1)**

Prepared: 12/05/19 Analyzed: 12/09/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	2.2555		ppbv	2.4000	94.0	70-140		
cis-1,2-Dichloroethene	2.0188		"	2.2000	91.8	70-136		
Tetrachloroethene (Tetrachloroethylene)	2.2239		"	2.2000	101	68-148		
trans-1,2-Dichloroethene	2.0445		"	2.2000	92.9	73-136		
Trichloroethene (Trichloroethylene)	2.3271		"	2.2000	106	69-137		
Vinyl chloride	1.7990		"	2.2000	81.8	62-151		

**LCS Dup (1912018-BSD1)**

Prepared: 12/05/19 Analyzed: 12/10/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	2.3597		ppbv	2.4000	98.3	70-140	4.52	25
cis-1,2-Dichloroethene	2.0640		"	2.2000	93.8	70-136	2.21	25
Tetrachloroethene (Tetrachloroethylene)	2.3338		"	2.2000	106	68-148	4.82	25
trans-1,2-Dichloroethene	2.0968		"	2.2000	95.3	73-136	2.52	25
Trichloroethene (Trichloroethylene)	2.3555		"	2.2000	107	69-137	1.22	25
Vinyl chloride	1.9236		"	2.2000	87.4	62-151	6.69	25

**Duplicate (1912018-DUP1)**

Source: E194902-09

Prepared: 12/05/19 Analyzed: 12/10/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	0.38812	0.22	ug/m3	0.35461		9.02	25	
cis-1,2-Dichloroethene	0.15751	0.21	"	0.14778		6.38	25	Q-2, J
Tetrachloroethene (Tetrachloroethylene)	0.96770	0.35	"	0.99476		2.76	25	
trans-1,2-Dichloroethene	U	0.21	"	U			25	U
Trichloroethene (Trichloroethylene)	0.98578	0.28	"	0.95762		2.90	25	
Vinyl chloride	U	0.13	"	U			25	U



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

**Volatile Organics (VOA) - Quality Control**

**US-EPA, Region 4, LSASD**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	--------------------	-------	----------------	------------------	------	----------------	-----	--------------	-------

**Batch 1912018 - V TO-15 Air Canister**

**MRL Verification (1912018-PS1)**

Prepared: 12/05/19 Analyzed: 12/10/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	0.23647		ppbv	0.24000		98.5	50-160			
cis-1,2-Dichloroethene	0.20926		"	0.22000		95.1	50-156			
Tetrachloroethene (Tetrachloroethylene)	0.25850		"	0.22000		118	50-150			
trans-1,2-Dichloroethene	0.21038		"	0.22000		95.6	53-156			
Trichloroethene (Trichloroethylene)	0.23946		"	0.22000		109	50-150			
Vinyl chloride	0.21610		"	0.22000		98.2	50-150			

**MRL Verification (1912018-PS2)**

Prepared: 12/05/19 Analyzed: 12/10/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	0.047480		ppbv	0.048000		98.9	50-160			
cis-1,2-Dichloroethene	0.044820		"	0.044000		102	50-156			
Tetrachloroethene (Tetrachloroethylene)	0.048930		"	0.044000		111	50-150			
trans-1,2-Dichloroethene	0.046440		"	0.044000		106	53-156			
Trichloroethene (Trichloroethylene)	0.047340		"	0.044000		108	50-150			
Vinyl chloride	0.044250		"	0.044000		101	50-150			

**MRL Verification (1912018-PS3)**

Prepared: 12/05/19 Analyzed: 12/10/19

**EPA TO-15**

1,1-Dichloroethene (1,1-Dichloroethylene)	0.023180		ppbv	0.024000		96.6	50-160			MRL-5
cis-1,2-Dichloroethene	0.024810		"	0.022000		113	50-156			MRL-5
Tetrachloroethene (Tetrachloroethylene)	0.024370		"	0.022000		111	50-150			MRL-5
trans-1,2-Dichloroethene	0.022980		"	0.022000		104	53-156			MRL-5
Trichloroethene (Trichloroethylene)	0.023900		"	0.022000		109	50-150			MRL-5
Vinyl chloride	0.023290		"	0.022000		106	50-150			MRL-5



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

**Notes and Definitions for QC Samples**

U	The analyte was not detected at or above the reporting limit.
J	The identification of the analyte is acceptable; the reported value is an estimate.
MRL-5	MRL verification for Air matrix
Q-2	Result greater than MDL but less than MRL.



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

**January 2, 2020**

**4LSASD-LSB**

**MEMORANDUM**

**SUBJECT:** FINAL Analytical Report  
 Project: 20-0055, Patterson Street Solvent Plume

**FROM:** Kristin Trapp  
 OCS Analyst

**THRU:** Jeffrey Hendel, Chief  
 LSB Organic Chemistry Section

**TO:** Cathy Amoroso

Attached are the final results for the analytical groups listed below. This report shall not be reproduced except in full without approval of the Region 4 laboratory. These analyses were performed in accordance with the Laboratory Services Branch's Laboratory Operations and Quality Assurance Manual (LSB LOQAM) found at [www.epa.gov/region4/sesd/asbsop](http://www.epa.gov/region4/sesd/asbsop). Any unique project data quality objectives specified in writing by the data requestor have also been incorporated into the data unless otherwise noted in the Report Narrative. Chemistry data have been verified based on the LSB LOQAM specifications and have been qualified by this laboratory if the applicable quality control criteria were not met. Verification is defined in Chapter 5 of the LSB LOQAM. For a listing of specific data qualifiers and explanations, please refer to the Data Qualifier Definitions included in this report. The reported results are accurate within the limits of the method(s) and are representative only of the samples as received by the laboratory.

Analyses Included in this report:

Method Used:

Accreditations:

**Volatile Organics (VOA)**

Volatile organic compounds

EPA 8260C (Water)

ISO



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

---

**Sample Disposal Policy**

Due to limited space for long term sample storage, LSB's policy is to dispose of samples on a periodic schedule. Air samples collected in summa canisters will be disposed of 30 days following the issuance of this report. All other sample media including original samples, sample extracts and or digestates will be disposed of, in accordance with applicable regulations, 60 days from the date of this report.

This sample disposal policy does not apply to criminal samples which are held until the laboratory is notified by the criminal investigators that case development and litigation are complete.

These samples may be held in the laboratory's custody for a longer period of time. If samples require storage beyond the 60-day period, please contact the Sample Control Coordinator by e-mail at [R4SampleCustody@epa.gov](mailto:R4SampleCustody@epa.gov).

cc: Nardina Turner



**UNITED STATES ENVIRONMENTAL PROTECTION AGENCY**

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

**SAMPLES INCLUDED IN THIS REPORT****Project: 20-0055, Patterson Street Solvent Plume**

Sample ID	Laboratory ID	Matrix	Date Collected	Date Received
PSP-TB-04	E194902-01	Trip Blank - Water	12/3/19 10:00	12/5/19 11:10
PSP31-SW	E194902-16	Surface Water	12/3/19 09:20	12/5/19 11:10
PSP32-SW	E194902-17	Surface Water	12/3/19 09:07	12/5/19 11:10



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

## DATA QUALIFIER DEFINITIONS

U The analyte was not detected at or above the reporting limit.

## ACRONYMS AND ABBREVIATIONS

CAS Chemical Abstracts Service

Note: Analytes with no known CAS identifiers have been assigned codes beginning with "E", the EPA ID as assigned by the EPA Substance Registry System ([www.epa.gov/srs](http://www.epa.gov/srs)), or beginning with "R4-", a unique identifier assigned by the EPA Region 4 laboratory.

MDL Method Detection Limit - The minimum concentration of a substance (an analyte) that can be measured and reported with a 99% confidence that the analyte concentration is greater than zero.

MRL Minimum Reporting Limit - Analyte concentration that corresponds to the lowest demonstrated level of acceptable quantitation. The MRL is sample-specific and accounts for preparation weights and volumes, dilutions, and moisture content of soil/sediments.

TIC Tentatively Identified Compound - An analyte identified based on a match with the instrument software's mass spectral library. A calibration standard has not been analyzed to confirm the compound's identification or the estimated concentration reported.

### ACCREDITATIONS:

ISO ASB is accredited by ISO/IEC 17025, including an amplification for forensic accreditation through ANSI-ASQ National Accreditation Board.

Refer to the certificate and scope of accreditation AT-1644 at:  
<http://www.epa.gov/aboutepa/about-region-4s-science-and-ecosystem-support-division-sesd>

NR The EPA Region 4 Laboratory has not requested accreditation for this test.



## UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

**Volatile Organics****Project: 20-0055, Patterson Street Solvent Plume****Sample ID: PSP-TB-04****Lab ID: E194902-01****Station ID:****Matrix: Trip Blank - Water****Date Collected: 12/3/19 10:00**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.50	U	ug/L	0.50	12/09/19 9:42	12/09/19 13:05	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	0.50	U	ug/L	0.50	12/09/19 9:42	12/09/19 13:05	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.50	U	ug/L	0.50	12/09/19 9:42	12/09/19 13:05	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	12/09/19 9:42	12/09/19 13:05	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	0.50	U	ug/L	0.50	12/09/19 9:42	12/09/19 13:05	EPA 8260C
75-01-4	Vinyl chloride	0.50	U	ug/L	0.50	12/09/19 9:42	12/09/19 13:05	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 20-0055, Patterson Street Solvent Plume**

**Sample ID: PSP31-SW**

**Lab ID: E194902-16**

**Station ID: PSP31**

**Matrix: Surface Water**

**Date Collected: 12/3/19 9:20**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.50	U	ug/L	0.50	12/09/19 9:42	12/09/19 14:25	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	0.50	U	ug/L	0.50	12/09/19 9:42	12/09/19 14:25	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.50	U	ug/L	0.50	12/09/19 9:42	12/09/19 14:25	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	12/09/19 9:42	12/09/19 14:25	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	0.50	U	ug/L	0.50	12/09/19 9:42	12/09/19 14:25	EPA 8260C
75-01-4	Vinyl chloride	0.50	U	ug/L	0.50	12/09/19 9:42	12/09/19 14:25	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

## Volatile Organics

**Project: 20-0055, Patterson Street Solvent Plume**

**Sample ID: PSP32-SW**

**Lab ID: E194902-17**

**Station ID: PSP32**

**Matrix: Surface Water**

**Date Collected: 12/3/19 9:07**

<i>CAS Number</i>	<i>Analyte</i>	<i>Results</i>	<i>Qualifiers</i>	<i>Units</i>	<i>MRL</i>	<i>Prepared</i>	<i>Analyzed</i>	<i>Method</i>
75-35-4	1,1-Dichloroethene (1,1-Dichloroethylene)	0.50	U	ug/L	0.50	12/09/19 9:42	12/09/19 16:11	EPA 8260C
156-59-2	cis-1,2-Dichloroethene	0.50	U	ug/L	0.50	12/09/19 9:42	12/09/19 16:11	EPA 8260C
127-18-4	Tetrachloroethene (Tetrachloroethylene)	0.50	U	ug/L	0.50	12/09/19 9:42	12/09/19 16:11	EPA 8260C
156-60-5	trans-1,2-Dichloroethene	0.50	U	ug/L	0.50	12/09/19 9:42	12/09/19 16:11	EPA 8260C
79-01-6	Trichloroethene (Trichloroethylene)	0.50	U	ug/L	0.50	12/09/19 9:42	12/09/19 16:11	EPA 8260C
75-01-4	Vinyl chloride	0.50	U	ug/L	0.50	12/09/19 9:42	12/09/19 16:11	EPA 8260C



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

**Volatile Organics (VOA) - Quality Control**

**US-EPA, Region 4, LSASD**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	--------------------	-------	----------------	------------------	------	----------------	-----	--------------	-------

**Batch 1912017 - V 5030B VOA Wtr Prep**

**Blank (1912017-BLK1)**

Prepared & Analyzed: 12/09/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	U	0.50	ug/L							U
cis-1,2-Dichloroethene	U	0.50	"							U
Tetrachloroethene (Tetrachloroethylene)	U	0.50	"							U
trans-1,2-Dichloroethene	U	0.50	"							U
Trichloroethene (Trichloroethylene)	U	0.50	"							U
Vinyl chloride	U	0.50	"							U

**LCS (1912017-BS1)**

Prepared & Analyzed: 12/09/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	20.740		ug/L	20.000	104	85.4-116
cis-1,2-Dichloroethene	21.650		"	20.000	108	87.6-115
Tetrachloroethene (Tetrachloroethylene)	21.100		"	20.000	106	85.1-113
trans-1,2-Dichloroethene	21.790		"	20.000	109	86.6-114
Trichloroethene (Trichloroethylene)	21.320		"	20.000	107	87.8-114
Vinyl chloride	21.830		"	20.000	109	78.8-115

**Matrix Spike (1912017-MS1)**

Source: E194902-16

Prepared & Analyzed: 12/09/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	12.450		ug/L	10.233	0.0000	122	87.5-133
cis-1,2-Dichloroethene	12.310		"	10.233	0.0000	120	85.3-127
Tetrachloroethene (Tetrachloroethylene)	11.560		"	10.233	0.0000	113	66.4-149
trans-1,2-Dichloroethene	12.250		"	10.233	0.0000	120	86.8-128
Trichloroethene (Trichloroethylene)	11.670		"	10.233	0.0000	114	87.2-128
Vinyl chloride	13.770		"	10.233	0.0000	135	84.5-135

**Matrix Spike Dup (1912017-MSD1)**

Source: E194902-16

Prepared & Analyzed: 12/09/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	12.480		ug/L	10.233	0.0000	122	87.5-133	0.241	12.8	
cis-1,2-Dichloroethene	11.730		"	10.233	0.0000	115	85.3-127	4.83	10.8	
Tetrachloroethene (Tetrachloroethylene)	11.640		"	10.233	0.0000	114	66.4-149	0.690	13.4	
trans-1,2-Dichloroethene	12.340		"	10.233	0.0000	121	86.8-128	0.732	11	
Trichloroethene (Trichloroethylene)	11.660		"	10.233	0.0000	114	87.2-128	0.0857	15	
Vinyl chloride	14.050		"	10.233	0.0000	137	84.5-135	2.01	14.1	QM-2





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
 Region 4 Laboratory Services and Applied Science Division  
 980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

**Volatile Organics (VOA) - Quality Control**

**US-EPA, Region 4, LSASD**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	--------------------	-------	----------------	------------------	------	----------------	-----	--------------	-------

**Batch 1912017 - V 5030B VOA Wtr Prep**

**MRL Verification (1912017-PS1)**

Prepared & Analyzed: 12/09/19

**EPA 8260C**

1,1-Dichloroethene (1,1-Dichloroethylene)	2.2900		ug/L	2.0000		114	65.4-136			
cis-1,2-Dichloroethene	2.1900		"	2.0000		110	67.6-135			
Tetrachloroethene (Tetrachloroethylene)	2.3500		"	2.0000		118	65.1-133			
trans-1,2-Dichloroethene	2.2800		"	2.0000		114	66.6-134			
Trichloroethene (Trichloroethylene)	2.0500		"	2.0000		102	67.8-134			
Vinyl chloride	2.6600		"	2.0000		133	58.8-135			



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 4 Laboratory Services and Applied Science Division

980 College Station Road, Athens, Georgia 30605-2700

D.A.R.T. Id: 20-0055

Project: 20-0055, Patterson Street Solvent Plume - Reported by Kristin Trapp

**Notes and Definitions for QC Samples**

- U            The analyte was not detected at or above the reporting limit.
- QM-2       Matrix Spike Recovery greater than method control limits